Vodafone Egypt HSW Supplier Policy Detailed Requirements

HSW22 – Local Agreements HSW Supplier's Requirements

Policy Champion:	Day-to-day contact:	Version/Revision:	Date:
Osama Radwan	Mohamed ElMohtady	1.8 "Version 1 – Revision 8" supersedes revision 7 dated April 2019	April 2020

This Supplier Policy Detailed Requirements addresses what is expected to comply with from the Suppliers' side, whenever they will provide Products and/or Services to Vodafone Egypt.

The objective of this Supplier Policy Detailed Requirements is setting out Supplier's obligations in relation to health, safety and wellbeing (HSW) combining:

1. Vodafone Procurement Company S.à r.l. – Supplier Policy – A3 V4 - Health, Safety & Wellbeing (enclosed Pages 2:12)
2. Vodafone Egypt HSW Supplier Policy Detailed Requirements – HSW22A -Local Agreements HSW Supplier's Requirements (enclosed Pages 13:44)

The Supplier Policy Detailed Requirements supports the Global Health, Safety and Wellbeing Policy Standards

Vodafone Egypt: this annex applies to all agreements & contracts with Vodafone operating companies in Egypt including subsidiaries and Joint Ventures (employees, contractors, suppliers) with an interest of 51%, or more, or management control. This include Vodafone Egypt Telecommunication S.A.E, Vodafone Data, and Vodafone Trade.

Services: unless otherwise stated, the annex applies to all services.

People: this Annex applies to all employees and contractors.

Suppliers: this Policy applies to all Suppliers "relevant entity engaged amongst other activities, including but not limited to the development, manufacture and supply of deliverables" to Vodafone Group Plc. in or to Vodafone operating companies in Egypt, in addition to; the supplier policies that are located here.

More information? See our Policy compliance framework.

Compliance levels are monitored and reviewed by appropriate governance bodies. Any breach will be treated as a serious disciplinary offence and may be subject to disciplinary action.

Contents

1. Vodafone Procurement Company S.à r.l. – Supplier Policy – A3 – V4 - Health, Safety & Wellbeing 2
Scope 3
Policy 3
Definitions and interpretation 3
Part A – General Requirements 5
Part B – Specific Requirements for High Risk Activities and Product Supply 7
Part C – Incident Reporting 15
Part D – Consequences of Non-compliance 17
2. HSW22A - Vodafone Egypt Detailed local HSW requirements for Supplier's agreement/contract 20

Vodafone Supplier Policy – A3
Health, Safety & Wellbeing

Scope

All Vodafone Procurement Company procurement agreements with Suppliers.

Policy

Introduction

The phrase "Supplier" or "Supplier personnel" in this Supplier Policy shall, where relevant, also include all officers, employees, contractors, subcontractors and agents of Supplier and other persons under its influence or control. Supplier shall procure compliance by such persons.

All references to "Vodafone" include the relevant contracting entity and other Vodafone Group Companies that benefit from the goods and services being provided.

This VPC Supplier Policy sets out Supplier's obligations in relation to health, safety and wellbeing (HSW) and is detailed into four parts:

Part A: General Requirements;

Part B: Specific Requirements for High Risk Activities and Product supply;

Part C: Incident Reporting; and

Part D: Consequences of Non-compliance.

Definitions and interpretation

The following words and expressions have the following meanings in this VPC Supplier Policy:

"Applicable Laws"	shall have the meaning attributed to it in the relevant Vodafone Procurement Agreement;
"Absolute Rules"	means rules requiring the observation of the following rules at all times: 1) always wearing seat belts when travelling in or operating vehicles; 2) always using suitable PPE, a safety harness and fall protection equipment when working at height. 3) never carrying out electrical work on electrical equipment, circuits and gear without appropriate qualifications and compliance to regulations; 4) never working under the influence of substances (alcohol or drugs) which are illegal or in excess of legal levels or where this impairs ability to perform tasks; 5) never using a hand held phone whilst driving and only making calls by pulling over or using hands free devices, when it is safe to do so; 6) always drive safely and legally; always obey the speed limit; 7) never undertake any street or underground work activities unless competent to do so; and 8) When working in the proximity of power, we always maintain the required safe distance and use of the correct insulated equipment;

"Incident"	means any fatality, major incident or other high potential incident (where loss or injury could have occurred) which will or could result in adverse consequences for Vodafone within 24hours following becoming aware of such an incident including: 1) multiple fractures or fracture of the skull, spine or pelvis; 2) amputation of hand or foot, fingers or toes; 3) loss of sight or penetrating injury to an eye; 4) chemical/biological exposure requiring medical treatment; 5) any other life threatening injury; 6) major events impacting health/safety e.g. fire, explosion, structural collapse, collapse of lifting or construction plant; 7) fall from height; and 8) a significant incident involving a public interface;
"High Risk Activities"	means any activities involving the following: 1) working in confined spaces; 2) overhead work/ lifting operations; 3) ground/ civil/ construction work; 4) product/ equipment safety; 5) radio frequency; 6) electrical work; 7) working at height; 8) driving (where it is an integral part of the job); 9) field installation activities relating to hardware or infrastructure; 10) network build, operate and transfer scenarios (or component activities); 11) manufacturing and distribution processes involving material health and safety risks; 12) such other scenarios as Vodafone may identify (acting reasonably and in agreement with Supplier);
"HSW"	means health, safety and wellbeing;
"PPE"	means personal protective equipment;
"Red Card"	means an incident type that is a major incident resulting in actual loss (i.e. fatality, disabling injury, property damage or business interruption);
"Yellow Card"	means an incident type that is a high potential incident which could result in a loss (i.e. injury, property damage or business interruption).

Part A – General Requirements

1. General

Supplier shall:

1.1. make proper provision for HSW for its employees, visitors, contractors and any sub-contractors working on its behalf;

1.2. comply with Applicable Laws relating to HSW;

1.3. comply with all additional and relevant standards and regulations relating to HSW;

1.4. obtain any necessary permits, licenses or insurances needed;

1.5. operate an appropriate internal HSW management system;

1.6. obtain certification to ISO45001 for relevant High Risk Activities from a recognised external certification body related to the specific country, market, region or project (or alternative equivalent management system approved for this purpose by Vodafone in writing);

1.7. provide appropriate evidence of the competence of Supplier and Supplier personnel when requested by Vodafone;

1.8. ensure that Supplier personnel have access to appropriate levels of expert HSW advice;

1.9. appoint a senior sponsor for HSW management, who shall have responsibility for HSW at all times;

1.10. ensure roles and responsibilities with respect to the delivery of health, safety and wellbeing are clearly defined throughout Supplier organisation;

1.11. ensure equipment is designed, manufactured, installed, constructed, tested, maintained, inspected and certified in accordance with Applicable Law and industry standards;

1.12. continually monitor and review HSW performance and compliance with this VPC Supplier Policy through programmes of inspections, testing and audits;

1.13. regularly submit HSW performance data to Vodafone, attend meetings and participate in audits as reasonably required by Vodafone;

1.14. ensure that appropriate systems and processes are in place (and adequately resourced) to identify and address HSW risks associated with the Vodafone Procurement Agreement;

1.15. have in place mechanisms to ensure that Supplier and Supplier personnel comply with this VPC Supplier Policy and any Vodafone local market HSW requirements communicated from time to time;

1.16. have in place mechanisms to ensure the management of risks associated with specific hazards associated with its obligations under the relevant Vodafone Procurement Agreement; and

1.17. Premises must have a clear and visible evacuation routes and well identified emergency assembly points.

2. Sub-contractors

Supplier shall have and maintain robust mechanisms to manage sub-contractors including:

2.1. systems and processes for assessing HSW capability of sub-contractors;

2.2. communication of Vodafone's HSW requirements and contractual arrangements to flow down Vodafone's requirements to sub-contractors (with appropriate contractual performance management mechanisms);

2.3. systems for regular monitoring and review of HSW performance; and

2.4. prohibitions on further sub-contracting of any High Risk Activities by Supplier's sub-contractor without the express permission of Vodafone, and upon Vodafone request Supplier shall report all parties undertaking High Risk Activity for Supplier.

3. Training and Competence

Supplier shall have and maintain a robust HSW training regime for Supplier personnel to ensure that Supplier and Supplier personnel are trained to deliver their assigned tasks in a safe manner including:

3.1. appropriate training for all tasks (in an appropriate language and delivered via appropriate means for the target audience);

3.2. mechanisms to ensure that High Risk Activities are only completed by trained, competent and qualified Supplier personnel; and

3.3. maintenance of appropriate training records available for inspection by Vodafone at any time.

4. Performance Reporting and KPIs

Where Supplier is undertaking any High Risk Activities, Supplier shall report on the following metrics on request from Vodafone (defined on the basis of GRI Standard 403[Note1] on Occupational Health & Safety), both in relation to their entire operations and specifically for Vodafone related activities covering the scope of all employees and for all workers who are not employees but whose work and/or workplace is controlled by the Supplier:

4.1. number and rate of fatalities as a result of work-related injury;

4.2. number and rate of high-consequence work-related injuries (excluding fatalities);

4.3. number and rate of recordable work-related injuries;

4.4. number of hours worked;

4.5. main types of work-related injury;

4.6. number of site inspections / audits undertaken and percentage of actions successfully completed;

4.7. number of statutory interventions; and

4.8. such other metrics as Vodafone may reasonably request.

Note 1: defined on the basis of recommendations from GRI Standard 403 on Occupational Health & Safety (publically available)

Part B – Specific Requirements for High Risk Activities and Product Supply

Part B is applicable in so far as Supplier is providing Products and/or services that are High Risk Activities.

5. HSW Plan for High Risk Activities

5.1. Supplier shall have and maintain an HSW plan for all High Risk Activities which have been adequately planned and a competent person has approved before commencement of work (where carrying out such High Risk Activities), setting out measures to manage the accompanying risks. Supplier shall manage the risks in accordance with the HSW plan. Supplier shall provide a copy of the HSW plan to Vodafone as soon as it is ready.

5.2. The HSW plan must include:

5.2.1. a scope of work;

5.2.2. key contacts for HSW including qualifications and responsibilities;

5.2.3. risk assessments, method statements and safe systems of work specifically tailored to the circumstances;

5.2.4. HSW training matrix for Supplier personnel;

5.2.5. procedures for emergencies, monitoring, auditing, inspection, certification, incident reporting, investigation, selection and management of subcontractors, selection use and control of high risk products, plant/ equipment and substances;

5.2.6. measures to prevent accidents causing personal injury or death; and

5.2.7. relevant requirements of Applicable Laws and compliance plans.

6. Driving and Vehicle Safety

Supplier shall have and maintain appropriate measures to manage the risks associated with driving and shall ensure:

6.1. Compliance with Applicable Laws and industry standards;

6.2. selection of appropriate vehicles for the intended use;

6.3. use of vehicles for intended purpose;

6.4. pre-use inspection of all vehicles;

6.5. maintenance of vehicles in line with manufacturer recommendations; all 2 wheelers shall be well maintained and as a minimum meet the manufacturer's design criteria.

6.6. maintenance of appropriate servicing and maintenance records;

6.7. fitting of vehicles with appropriate levels of safety equipment; in particular manufacturer's seatbelts and safety restraint systems installed for all seats, airbags and anti- lock braking systems (ABS).

6.8. carrying of passengers does not exceed manufacturer specifications for the vehicle, with no carriage of excess or unauthorised passengers;

6.9. prohibition of the carrying of passengers in the back of pick-up trucks;

6.10. safe carrying of loads and equipment, with loads being secure and not exceeding manufacturer specifications for the vehicle; passengers and loads shall never be transported in the same compartments;

6.11. fitting of hands-free car kits to all vehicles (where safe and legal to do so) and prohibition of the use of hand held mobile phones whilst driving;

6.12. fitting of a speed monitoring device to all vehicles used for "occupational driving" (where a role requires driving as an integral part of the job);

6.13. towing only by vehicles that are fit for purpose and suitable for the size of trailer or equipment being towed, with all trailers, towed equipment and mechanisms for securing towed equipment meeting Applicable Laws and industry standards;

6.14. risks of the journey should be assessed and journey risk management plans be in place, have in place of a schedule of work, geographical areas of responsibility and duration of time on the road. Where a job role involves a significant amount of driving, with this being reviewed regularly; occupational drivers should work no more than 12 hours per shift and have a minimum of 8 hours continuous rest between shifts;

6.15. occupational driving is only done by persons with the necessary competencies to perform such role;

6.16. drivers are appropriately assessed, licensed, trained, and medically fit to operate vehicles;

6.17. appropriate levels of training are delivered to all drivers determined by the risk posed by their role, and such records are maintained for evidence purposes;

6.18. drivers are qualified to drive in the country and region they are driving in and hold the appropriate grade of licence(s), and to maintain such records for evidence purposes;

6.19. implementation of a strict programme to monitor and manage the performance and behaviour of drivers (including but not limited to the use of seats belts by all persons in the vehicle);

6.20. a standard set of driver requirements exist, communicating clear expectations and delivering proper defensive driving techniques through training;

6.21. control of use of drugs and alcohol in relation to driving;

6.22. driving at safe speeds taking into account the road conditions; and

6.23. use of industry-approved safety helmets by drivers and passengers of motorcycles, quads and similar types of vehicle.

7. Working At Height

7.1 Supplier shall assess, manage and where possible eliminate the risks associated with work at height by designing out the need for such activities (excluding portable ladders which is covered separately).

7.2 Supplier shall ensure that:

7.2.1 all sites are designed and constructed with suitable fall prevention measures (e.g. towers are fitted with a Vodafone approved fall arrests system, guard rails, restraint points): ladder cages are not considered an appropriate fall prevention method and must not be installed on vertical ladders;

7.2.2 it sets minimum standards for the competence and fitness for all persons who carry out work at height on Vodafone related work and that only those persons who have been authorised to be on site and trained (training to be refreshed no later than every three years) in working at height are engaged in that activity;

7.2.3 those engaged in working at height activities remain attached to the structure at all times;

7.2.4 working at height activities are not conducted alone;

7.2.5 provisions are made to protect the public from falling objects and restrict unauthorised access; limit the likelihood of tools or equipment falling to a lower level by tethering and barrier off the area into which tools or equipment may fall into if dropped;

7.2.6 it establishes arrangements for the issue, use and storage of PPE and access equipment;

7.2.7 PPE used for working at height is appropriate for fall arrest, and must without exception be a full body harness;

7.2.8 procedures are in place for emergencies occurring at height, e.g. tower rescues, incident reporting procedures; and

7.2.9 all equipment used for access, including ladders, steps, mobile elevated work platforms (MEWPs) and scaffolding are appropriate and inspected prior to use and are only used by appropriately trained people.

8. Portable Ladders

Where poles or structures are accessed using ladders, the supplier shall ensure that:

8.1. only non-conductive ladders with the appropriate insulation rating are used;

8.2. ladders are inspected before use;

8.3. ladders are properly secured (lashed and held);

8.4. workers are trained in the safe use of ladders;

8.5. workers do not over reach;

8.6. ladders must be safely transported and stored; and

8.7. a safety harness must be worn and secured to the pole or structure once the working position is reached.

9. Electrical Work

9.1 Supplier shall have and maintain a risk management process and safe systems of work for electrical tasks.

9.2 Supplier shall ensure that:

9.2.1 no live electrical work is undertaken, which has the potential to cause electrical injury;

9.2.2 persons who have been authorised to be working on electrical equipment and are trained, competent and qualified; working alone is not permitted;

9.2.3 electrical equipment is fit for intended purpose/environment;

9.2.4 portable electrical equipment is inspected at regular intervals;

9.2.5 electrical equipment in wet and/or highly conductive metal areas is low voltage, shielded or protected by a circuit breaker;

9.2.6 electrical equipment with potential to cause electrical injury is isolated from all sources of power and locked off using a formal lock out/tag out system;

9.2.7 excavation works use drawings, cable detection tools, and safe digging practices to minimise the risk from underground electrical services; and

9.2.8 when working near overhead power lines, controls are implemented (e.g. to de-energise, for cable insulation) if the risk assessment or conditions indicate that contact or flash over may occur. This includes assessing vehicle and crane access, where relevant.

10. Radio Frequency (RF) Safety

10.1. Supplier shall fully implement the following provisions, together with any relevant Vodafone local market policy or standard.

10.2. Supplier shall have and maintain documented procedures for site selection, design, installation, commissioning, operation, maintenance and decommissioning phases. These procedures should be in accordance with local (national) regulations as well as recognised industry standards.

10.3. Supplier documented procedures shall cover the following controls:

10.3.1. design specifications and systems of work being in operation to manage the risks in accordance with local legal and recognised industry standards requirements for the general public and workers; and

10.3.2. an Electromagnetic Fields(EMF) risk assessment /design constraints which should be reviewed in the event of a material change to the Radio Base Station.

10.4. Supplier shall ensure:

10.4.1. work is carried out by trained, competent and qualified persons, with training of staff to include an understanding of potential health risks, and risk controls (e.g. isolation/power down procedures, use of monitoring devices), and dealing with potential over-exposures;

10.4.2. that anyone who has an implanted or body worn electronic medical device undergoes a special risk assessment before being permitted to enter into controlled areas where the RF field level is potentially higher than ICNIRP Guidelines;

10.4.3. in the event of any purported interference events (e.g. products located in or on hospital premises where life-critical electronic medical devices operate), Supplier shall ensure that necessary procedures are in place to allow shutdown and/or power limitation of Radio Base Stations and shall comply with relevant national guidelines and notify Vodafone of any such instances;

10.4.4. all relevant Supplier personnel take adequate measures to work safely in the presence of RF Fields, including utilisation of standard safe work procedures, and compliance with supervision, instruction & training;

10.4.5. there is clear signage and demarcation considering any Vodafone personnel, general public and Supplier personnel and effective access controls for access to restricted areas;

10.4.6. no over exposure for any work on or near antennas and implement specific safe working procedures addressing potential health risks and having risk controls, obtaining any necessary approvals needed;

10.4.7. site shut down or power down or other appropriate procedures shall be implemented to control work within relevant exclusion zones; site landlords shall be provided sufficient

information to ensure that they can fulfill their obligations to preserve the safety of third parties;

10.4.8. appropriate guidance shall be available to the general public and workers in accordance with national regulatory or internationally recognised guidelines;

10.4.9. design specifications and systems of work are in operation to manage the risks in accordance with local legal requirements and other relevant standards, for any Vodafone personnel, general public and Supplier personnel; and

10.4.10. maintenance of appropriate records to demonstrate compliance with the above and clear accountability for data.

10.5. Supplier shall ensure that there is a method of auditing and verifying that the required approvals, processes and documentation, set out in this VPC Supplier Policy, are up to date and that Radio Base Stations and Terminal Equipment are compliant with this VPC Supplier Policy with the following elements:

10.5.1. a system to report and investigate any suspected non-compliance incidents (e.g. alleged over-exposure to RF); consider the health of any individual(s) concerned; and ensure safety management systems are working;

10.5.2. compliance with RF exposure limits and risk management is incorporated for all equipment provided; and

10.5.3. records are kept, subject to any applicable data protection legislation, of: (i) Vodafone or Supplier personnel who are potentially exposed to RF field levels above ICNIRP Guidelines (e.g. anyone who maintain antennas); and (ii) any complaints to Supplier from individuals alleging they have suffered personal health effects caused by Radio Base Stations or Terminal Equipment.

11. Product / Equipment Safety

Supplier shall:

11.1. ensure potential HSW risks associated with terminals, plant, equipment and substances used or procured on behalf of Vodafone are assessed;

11.2. only purchase products sourced from those manufacturers/ suppliers of goods or services that demonstrate robust quality assurance processes and ensure the delivery/maintenance of safe products;

11.3. only purchase, make and release products that comply with safe standards of design using an established process for certifying compliance with relevant safety requirements;

11.4. have and maintain controls for the safe use, handling, transportation, maintenance and storage of products;

11.5. ensure all plant and equipment is suitable for its intended use, maintained in line with manufacturer recommendations, inspected / examined before use and only used by those trained, competent and qualified to operate it;

11.6. have incident investigation methods that are documented and include processes to deal with product defects or failures;

11.7. provide any necessary safety procedures;

11.8. ensure that product safety requirements are documented and include procedures for product

11.9. document and retain all documentation pertaining to product safety (such records must be provided to Vodafone on request and retained for as long as is necessary);

11.10. have a process as appropriate for the design, production, verification and approval of user documentation to ensure that all necessary Health & Safety information, marks and warnings are current and included;

11.11. ensure that the correct product marks/certifications are obtained and displayed relevant to the application in which the product is destined. Such marks/certifications must be displayed as required on the product, packaging and any associated documentation. Where product certifications/declarations are the responsibility of other parties (e.g. manufacturers/ suppliers of goods or services) such certification/declarations shall be obtained by Supplier and form part of the development records;

11.12. monitor product performance in terms of product safety related failures or reported incidents until phase out of the product;

11.13. take action to investigate, report, correct, and prevent in the event of a product related safety incident occurring;

11.14. notify Vodafone in the event of a serious risk requiring a product recall or withdrawal from the field;

11.15. have a process for product safety related investigations, advisory notices and recall;

11.16. have suitable information and instructions relating to the installation, use, maintenance, storage and disposal of products are obtained and communicated to end users; and

11.17. provide communication of all necessary instructions to the end user for safe and correct operation in compliance with Applicable Laws and regulations. Such areas shall include (but not be limited to);

11.17.1. aviation or aircraft environment;

11.17.2. flammable liquids or substances;

11.17.3. operating with any medical conditions (e.g. Implanted medical devices); and

11.17.4. electro-explosive devices.

12. Ground / Civil Works

Supplier shall ensure that:

12.1. when conducting ground / civil works it has a mechanism for identifying any buried services;

12.2. it assesses ground conditions prior to conducting any excavations, and takes steps to prevent incidents e.g. collapse, flooding, contamination;

12.3. it places barriers and warning signs around open excavation to warn and protect those in the vicinity of the risk; and

12.4. appropriate measures are in place to safely control traffic.

13. Lifting Operations

13.1. Supplier shall ensure that:

13.1.1. all lifting operations must have a lifting plan; and

13.1.2. all loads in excess of 100kg are lifted mechanically.

13.2. In addition, the supplier shall ensure that all persons involved in the lifting operations;

13.2.1. are suitably trained;

13.2.2. are authorised to be on site and have the necessary approvals;

13.2.3. are aware of and have assessed the risks associated with the task;

13.2.4. are provided with and have been trained in the use of the equipment; and

13.2.5. are medically fit to conduct the task.

13.3. Supplier shall ensure during any lifting operation steps must be taken to:

13.3.1. prevent tools, equipment or loads falling to a lower level;

13.3.2. barrier off the area into which tools or equipment may fall into if dropped;

13.3.3. prevent unauthorized access into the drop zone;

13.3.4. ensure haulers are out of the drop zone;

13.3.5. have the required Working Load Limit for the task defined;

13.3.6. have a recorded 6 monthly inspection by a competent person; and

13.3.7. have a before use or pre-use inspection.

14. Confined Spaces

Supplier shall ensure that:

14.1. it has and maintains a mechanism for identifying confined spaces and assessing and managing the associated risks;

14.2. only those persons that have received appropriate training work in confined spaces;

14.3. where necessary there is the capability and process for testing and monitoring of air quality;

14.4. appropriate breathing apparatus and ventilation equipment is used and records kept of such use; and

14.5. it has and maintains clear emergency and rescue procedures.

15. Warehouse Safety

Where warehousing and/or logistics is fully or significantly dedicated to Vodafone, the Supplier shall have and maintain appropriate measures to manage the risks associated with warehouse safety and shall ensure:

15.1. all who work in or visit the warehouse must have suitable information and instruction on how to remain safe in the environment; this will include details on emergency procedures, common risks, hazard spotting, hazard rectification processes, risk assessment and other key safety requirements, they should be equipped with the appropriate PPE as identified by the warehouse risk assessment. (This PPE may include but not be limited to safety boots/shoes, Hi-Viz jacket/vest, hardhat and protective glasses);

15.2. all must be fitted with fire detection systems, audible fire alarm systems, suitable fire-fighting/suppression systems, emergency lighting and have appropriate processes in place to control the levels of combustible and flammable materials;

15.3. all equipment in the warehouse must be fit for purpose, this includes mobile equipment such as fork lift trucks, access equipment such as warehouse steps and ladders, portable equipment such as electrical tools and appliances, and fixed equipment such as racking, appropriate systems should be in place for regular inspection and monitoring of equipment; and

15.4. adequate welfare facilities must be provided including designated clean areas for eating and drinking, access to drinking water, toilets and washing facilities and rest areas.

16. Fibre Related Activities

Suppliers engaged in this activity shall ensure that the following controls as a minimum are adhered to:

16.1. planning – all cable laying activities must be planned and supported by a safety plan;

16.2. buried services – appropriate controls must be in place to detect or minimise risk of contact with buried services;

16.3. trenching – appropriately engineered shoring, bracing & barriers must be used when working in excavations to prevent injury caused by trench collapse, items falling into the trench or persons falling into the trench;

16.4. underground chambers – underground chambers (confined space) must only be entered when sufficient training and control measures are in place;

16.5. ensure correct separation distances from live cables are maintained;

16.6. proximity detectors are used by all personnel working near power sources;

16.7. appropriate insulated tools are used;

16.8. no throwing of fibre in the vicinity of overhead power lines;

16.9. traffic control – appropriate measures must be in place to safely control traffic;

16.10. training – all operatives must be appropriately trained and competent for the tasks they undertake;

16.11. material handling – appropriate control processes must be in place to control material movement;

16.12. Personal Protective Equipment (PPE) – all operatives must be provided with necessary PPE;

16.13. supervision – all high risk activities associated with cable laying must have the appropriate level of competent supervision on the ground; and

16.14. welfare – appropriate welfare facilities must be made available to all operatives.

17. Control of Access

17.1. Suppliers shall ensure that access to high risk activity work areas are controlled for only authorised persons and in addition:

17.1.1. ensure that hazards associated with high risk activities have been identified, assessed and controls are in place to eliminate the hazard, and that high risk activities and/or activities taking place in a high risk environment are planned and have been approved by a competent person before the work commences; and

17.1.2. ensure that suppliers have a process in place to demonstrate that high risk activity was completed and verified as planned, including keeping any necessary records of activity.

Part C – Incident Reporting

18. Incident Reporting and Investigation

Supplier shall ensure that:

18.1. all necessary systems are in place to report, record and investigate all incidents including product failures;

18.2. where a serious incident occurs that has the potential to directly impact Vodafone, this must be reported in accordance with the reporting process as set out below;

18.3. it co-operates with and supports Vodafone in the investigation of all serious incidents; and

18.4. all details related to incidents and investigations are shared with Vodafone.

19. Incident Report in the Event of an Incident

Supplier shall:

19.1. ensure that it provides a report to Vodafone with concise, timely information concerning any Incident.

19.2. instigate a full investigation into the causes of any Incident and how to avoid reoccurrence and provide the full report to Vodafone within 15 working days.

19.3. co-operate and grant Vodafone reasonable access and audit rights to any scene of an Incident, together with other premises, personnel and documents as is necessary to complete a full investigation.

19.4. where reasonable ensure that the scene of an Incident remains undisturbed except for necessary remediation work. If the scene cannot remain substantially undisturbed, Supplier shall arrange for photographs and measurements, and the necessary drawings and plans, to facilitate the work of the investigation.

19.5. arrange for any witnesses to the Incident to be identified and to be present to assist the investigation and completion of an investigation report.

20. Final Close Out Reports

20.1. Supplier shall issue a close out report which contains a summary of the following information:

- 20.1.1. updated nature of injury and condition/prognosis;
- 20.1.2. description of incident;
- 20.1.3. action taken to prevent reoccurrence;
- 20.1.4. conclusions and recommendations;
- 20.1.5. direct feedback to understand the perspective of the persons involved; and
- 20.1.6. any follow up actions, support for family members, contractors, counselling of individuals and other reasonable remedial activities.

20.2. Supplier shall include the following support documentation and include with the close out report:

20.2.1. contracts/works orders;

20.2.2. safety plans/work method statements;

20.2.3. induction and training records; and

20.2.4. site supervisor/inspection/audit records

21. Final Close Out Meetings

21.1. Supplier shall organise a close out meeting and ensure that the incident has been appropriately managed and Supplier has clearly understood the root cause of the incident that occurred and any lessons learned have been communicated.

21.2. Supplier must address the following key issues:

21.2.1. welfare of the injured person, or in the case of a fatality, the welfare of the individual's family and co-workers;

21.2.2. how to prevent future incidents;

21.2.3. root cause of the incident including human factors; and

21.2.4. Specific lessons learned from all incidents and their communication.

Part D – Consequences of Non-compliance

22. Supplier Obligations

22.1. Supplier shall: (i) comply with this VPC Supplier Policy and the Absolute Rules; (ii) follow an appropriate HSW plan; (iii) have appropriate systems and processes in place to monitor any failures in such compliance; (iv) have an appropriate "consequences" process in place to ensure that Supplier personnel breaching VPC Supplier Policy or Absolute Rules face appropriate disciplinary action, to the extent permitted by Applicable Law and expressly on the basis that Supplier remains responsible for managing its own personnel; and (v) implement this process at the earliest opportunity.

22.2. Supplier shall: (i) immediately cease all related work in the event of any fatality; and (ii) only re-commence work upon Vodafone authorising it in writing to do so. In such circumstances, Supplier shall not be entitled to any right to delay performance, increase the price payable or other form of contractual waiver, forbearance or relaxation.

22.3. Supplier shall (when requested by Vodafone) exclude any Supplier personnel who repeatedly fails to observe this VPC Supplier Policy or the Absolute Rules from being involved in the ongoing provision of products or services to Vodafone. Supplier shall make such exclusion automatically in the event that such personnel are found not wearing appropriate safety harness and fall protection equipment when working at height.

23. Vodafone Rights

23.1. Vodafone shall: (i) have absolute discretion on whether to classify an incident as Red Card or Yellow Card; and (ii) notify Supplier of its decisions in this respect.

23.2. Vodafone shall be entitled to apply the measures set out in 23.4 (Consequence Table), where there is a failure to comply with the VPC Supplier Policy or the Absolute Rules. Supplier shall assist and provide access to information as is necessary to establish a classification. Incidents shall not be classified as Red Card or Yellow Card if Supplier can unequivocally demonstrate compliance to this VPC Supplier Policy or Absolute Rules.

23.3. Any classification of individual incidents shall typically have validity of 36 months from the point of notification; however, this validity is at Vodafone discretion.

23.4. Consequence Table

Incident Cards	Card Description	Consequence
	Yellow Card	Vodafone will send a warning notification.
	3 x Yellow Cards	3 Yellow Cards are equivalent to a single Red Card.
	Related Yellow Card	Any Yellow Card that has a cause related to a previous Yellow Card will result in the card being equivalent and counted as a Red Card.
	1st Red Card	Vodafone may exclude Supplier from participating in future bids or tender opportunities for a number of events or time period of 12 months.
	2nd Red Card	Vodafone may exclude Supplier from participating in future bids or tender opportunities for a further number of events or time period.
	3rd Red Card	Vodafone may terminate all or part of the agreement or any orders placed with Supplier (on the basis of breach of contract by Supplier).

24. Absolute Rules Graphical Representation

WE ALWAYS drive safely and legally: we always wear a seatbelt

WE ALWAYS drive safely and legally: we always obey the speed limit

NEVER carry out work on any electrical equipment unless you're qualified

WE NEVER work under the influence of alcohol or drugs

NEVER undertake any street or underground work activities unless competent to do so

When working in the proximity of power, **WE ALWAYS** maintain the required safe distance and use the correct insulated equipment

WE ALWAYS drive safely and legally: we never use a handheld mobile device when driving

When working at height, **ALWAYS** wear protective gear, attach a safety harness and use fall protection equipment

2. HSW22A - Vodafone Egypt Detailed local HSW requirements for Supplier's agreement/contract

Scope

Applies to All supplier agreement/contracts with Vodafone operating companies in Egypt.

Introduction

This Supplier Policy Detailed Requirements sets out Supplier's additional local obligations in relation to health, safety and wellbeing (HSW) and is split into four parts:

Part A: Detailed general requirements;

Part B: Detailed specific requirements for High Risk Activities and Product supply;

Part C: Detailed incident reporting requirements;

Part D: Detailed consequences of non-compliance

Definitions and interpretation

The following words and expressions have the following meanings in this Supplier Policy Detailed Requirements:

HSW	Health, Safety and Wellbeing.
Products	Any hardware or software product (including any modifications, spare parts, components, drawings, tools and associated documents).
Services	All categories of provided services including but not limited to support and maintenance services, managed services, professional services, catering, hosting events...etc.
Supplier	The relevant entity engaged amongst other activities, including but not limited to the development, manufacture and supply of deliverables to Vodafone Group Plc. or Vodafone Egypt.
Vodafone Egypt	Vodafone operating companies in Egypt including subsidiaries and Joint Ventures (employees, contractors, suppliers) with an interest of 51%, or more, or management control.
Company's Vehicles	Any vehicles owned/rented that is engaged in any Vodafone related task.
"Absolute Rules"	Vodafone main rules that address high risks control measures which require observation at all times: (HSW AR) 1) always wearing seat belts when travelling in or operating vehicles; 2) always using suitable PPE, a safety harness and fall protection equipment when working at height. 3) never carrying out electrical work on electrical equipment, circuits and gear without appropriate qualifications and compliance to regulations; 4) never working under the influence of substances (alcohol or drugs) which are illegal or in excess of legal levels or where this impairs ability to perform tasks; 5) never using a hand held phone whilst driving and only making calls by pulling over or using hands free devices, when it is safe to do so; 6) always drive safely and legally; always obey the speed limit; 7) never undertake any street or underground work activities unless competent to do so; and 8) When working in the proximity of power, we always maintain the required safe distance and use of the correct insulated equipment;
Work approval	Is a method of reviewing whether adequate planning and risk assessment of high risk activities (including identification of reasonable controls) has been completed prior to the activity taking place and before access for the work to be undertaken is authorised.
Approver	Is appointed competent person who has responsibility for ensuring requirements for high risk activities are met prior to approving work to commence.

High Risk Activities	Any activities involving the following: 1) Working in confined spaces; 2) Overhead work/ lifting operations; 3) Ground/ civil/ construction work; 4) Product/ equipment safety; 5) Radio frequency; 6) Electrical work; 7) Working at height; 8) Driving (where it is an integral part of the job); 9) Field installation activities relating to hardware or infrastructure; 10) Network build, operate and transfer scenarios (or component activities); 11) Manufacturing and distribution processes involving material health and safety risks; 12) Catering services; 13) Lone working; 14) Managed Services; 15) Such other scenarios as Vodafone may identify (acting reasonably and in agreement with supplier);
"EN Standards"	European Standards;
"ICNIRP"	International Commission on Non-Ionizing Radiation Protection;
"Anchor"	Fixed object to which ropes or equipment is attached for lifting or for lifelines.
"Competent person"	Someone who has sufficient combination of knowledge, training, experience. The level of competency required will depend on the complexity of the work needed to be performed;
"Lifting plan"	A step by step plan on how the lift will be carried out and a layout of the gear required for the lift;
"Non–conformity"	Failure to conform to accepted standards, rules or laws;
"Safe Working Load SWL"	Maximum load the lifting equipment is certified to withstand under normal use;
"Working Load Limit WLL"	The maximum load that lifting equipment is certified to withstand under normal use and in a given configuration, WLL is only applied to lifting equipment and not rope access and fall arrest equipment;
"Extra Low Voltage (ELV)"	Voltage less than 50v AC or ripple free 120v DC
"Low Voltage (LV)"	Voltage from 50v to 1000v AC or 120 to 1500v DC
"Medium Voltage"	Voltage 1000v to 35Kv AC or greater than 1500vDC
"Portable appliance"	Any portable appliance is any piece of electrical equipment that can easily be moved and is connected by plug or socket.
"Electrical work"	Any work that involves contact with electrical components, switch gear, cables or other components. This includes all installation, maintenance, upgrade and decommissioning activities
"Live"	Electrically charged by being connected to a voltage electricity supply or having a charge retained by capacitance.
"Exposed"	Capable of being inadvertently touched or approached nearer than a safe distance by a person. It is applied to parts not suitably guarded, isolated, or insulated.
"Live electrical work"	Any work will involve persons be exposed to live parts or equipment.
"RCD & ELCB"	Residual Current Device and Earth Leakage Circuit Breaker are devices used to protect the user of electrical equipment in the event of a fault.
"Managed Services Provider (MSP)"	A professional supplier that Vodafone outsources a day-to-day management responsibilities and / or functions of a defined set of services to.

Part A - Detailed General Requirements

1. General

Suppliers shall:

1.1. Comply with all Applicable Laws and regulations related to HSW and Vodafone Absolute Rules;

1.2. Have their own implemented HSW management system which ensures that the risks associated with their business are identified, controlled, and monitored;

1.3. Have a competent person appointed with HSW responsibility for the operation of and compliance with such HSW management system;

1.4. Ensure that all Vodafone requirements, absolute rules, risks and controls are clearly communicated to all sub-contractors and field's operatives and evidence of communication shall be available (e.g. binding contracts, commitment letters, ...etc.);

1.5. Exercise all reasonable care when engaged in any Vodafone Egypt related assignment and follow all reasonable instructions;

1.6. All identified risks and control measures shall be communicated to anyone likely to work on the sites; hierarchy of control to be present;

1.7. Ensure that for any high-risk activity at least one must be trained on emergency response for potential crises (e.g. First Aid & CPR, Firefighting, Evacuation and rescue techniques, emergency shutdown ...etc.) and they are physically capable of carrying out his duties. lone working is prohibited;

1.8. Ensure that all personnel engaged in high risk activities for Vodafone Egypt to have an I.D. cards' system that identifies as a minimum person's identity with a coloured photograph, function, safety certifications, and social number;

1.9. Ensure that all sub-contractors engaged in high-risk activities are limited to only one tier;

1.10. Has a system for PPEs' selection, inspection, and records keeping that meets Vodafone requirements;

1.11. Ensure that all personnel performing a Vodafone task are following the appropriate measures and using appropriate PPEs, Tools ...etc. that are designed, used, tested, inspected, calibrated in accordance with the relevant standards, and conformity shall be made available for Vodafone Egypt review; and

1.12. Ensure that all testing, inspections, calibrations, certification conformities are provided from accredited body in accordance with EN standards, and can demonstrate evidence / records for Vodafone Egypt review.

2. Access and Work Approval for High Risk Activities

Supplier shall:

2.1. have a process to ensure that high risk activities and/or activities taking place in a high risk environment have been adequately planned, associated hazards have been identified, assessed; and action are taking to eliminate/mitigate HSW risks by applying hierarchy of controls effectively;

2.2. have a specific documented risk assessment and method statements specific to the activity and location, and ensure that it has been reviewed to consider additional control measures required, arrangements in the event of an emergency, and that all communicated to anyone likely to work on the sites. All high risk activities and/or activities taking place in a high risk environment are approved by a competent person prior to work commencement, and that access is controlled for only authorized persons;

2.3. have a processes, mechanisms and methods in place to ensure that all high risk activities "100% of the high risk activities" were executed in accordance with plan / risk assessment, verified during the activities, and completed in accordance with HSW requirements whether physically onsite by suppliers' personnel or remotely by other means; and

2.4. ensure that all access and work approval processes including the activities planning, risk assessments, authorization access & work authorisation approval, execution, verification, and completion are monitored, reviewed, compliance can be demonstrated; and records made available for Vodafone reviews. (for references, Sample Site Risk Assessment – Annex HSW22A-1).

3. Training and Competency

3.1. Pre/post examination is mandatory with a minimum passing score of 80% and a maximum of 2-times failure, where a buffer period of two weeks is requested prior re-examination.

3.2. Participants who fail twice in the examination shall not to be enrolled in the same work scope/profile; otherwise, the Supplier's management shall carry out job rotation that acquires lower risk.

3.3. Training certificate shall be obtained by passing the post examination which is valid a maximum of two (2) years for all trainings or else mentioned by the training provider (whichever occurs earlier).

3.4. Each supplier shall have a process to ensure that each personnel is competent and appropriately trained for his/her assigned responsibility, this shall consider the minimum qualifications as follows:

3.4.1. HSW Key contact/manger shall be competent and to be assessed based on the scope and size of the project/operation will be undertaken.

3.4.2. HSW field officers shall be trained on risk assessment, high risk activities, and emergency response and rescue techniques.

3.4.3. Field operatives shall be appropriately trained for his/her assigned responsibility

3.5. Supplier shall use any of the following approved centres by Vodafone Egypt for the relevant training, considering that specified risks' training shall be approved from Vodafone HSW team:

Training Provider	Trainer	Contacts	Required trainings									
			Risk Assessment	Firefighting	First aid & CPR	Electrical safety	Lifting Operation and Slinging	Working at heights and rescue	PPE & Gear Inspection including manual lifting gears	Scaffolding Erection, Dismantling, and Inspection	Road Safety "First year" one year Validity	Defensive Driving "Second Year" one year Validity
Partner Success	Mr. Mohamed El-Masry	0122-214-2705 melmasry@partners-success.com	√	√	√	√						
HSSE Solutions	Dr. Yassin Darwish	0100-007-2146 yassin@hsse-ltd.com	√	√	√	√						
GTSC	Tamer Hossni	0100-004-2708 thosney@gtsc.biz	√	√	√	√	√					√
Safety Point	Mr. Omar Sheta	0100-523-2000 osheta@safetypoint.com.eg Booking@safetypoint.com.eg						√	√	√		
Platinum	Mr. Ahmed El-Naggar	010-000-72095 ahmed.elnaggar@platinum-eg.com						√	√	√		
المركز المصري للقيادة الامنة Egyptian Center for Safe Driving	Mrs. Radwa	0111-994-9989 reservation@rstc-egypt.com									√	√

4. Personal Protective Equipment:

4.1. Risk assessment, method, and job hazard analysis shall be used to identify whether any PPE is required for the task being undertaken, and the minimum standard of PPE on construction sites are: hard hat, safety boot S3.

4.2. All PPE should be checked prior to use to ensure it is still in good working order, maintained and clean.

4.3. Supplier shall dedicate competent person certified from Vodafone approved training provider in the PPE & Gear inspection, who shall be responsible on conducting the inspection **on a quarterly basis** of all PPE & Gears used on sites (either for in house or one tier sub-contractors) , and to be conducted annually by approved training provider; however, In case that the supplier couldn't dedicate a person for this task, then the supplier shall ensure a semi-annual inspection for all PPE & Gears by Vodafone approved training providers.

4.4. Recommended PPE Matrix for activities in (Annex HSW22A-2).

4.5. All PPE used shall comply with EN Standards (e.g. Annex HSW22A-3) and purchased from approved supplier listed below:

PPE Brand	Supplier contacts	
Protecta	Omar Sheta	01005232000
Millar	Saed Okail	01117701220
CAMP	Sky Group (Mohamed El Daly)	01066612802
KAYA Safety	Giza Projects Company (Hams ElKhashab)	01065549199

Part B – Additional Specific Requirements for High Risk Activities and Product Supply

5. HSW Plan

5.1. Supplier shall have and maintain an HSW plan for all High Risk Activities before commencing work (where carrying out such High Risk Activities), setting out measures to manage the accompanying risks. Supplier shall manage the risks in accordance with the HSW plan. Supplier shall provide a copy of the HSW plan to Vodafone as soon as it is ready and before commencing any high risk activity with all relevant evidence of compliance with these standard requirements.

5.2. **The HSW plan** must include details of:

5.2.1. Scope of the work that is to be undertaken;

5.2.2. Key contacts and responsibilities for health, safety and wellbeing delivery including the qualifications and experience of those with specific responsibility for health, safety and wellbeing;

5.2.3. Risk assessments, method statements and safe systems of work that detail how the tasks will be completed safely. These must be specific to the project/ contract and take into account the difference environments that will be encountered;

5.2.4. Training matrix detailing what health, safety and wellbeing training you deliver to your employees;

5.2.5. Details of the monitoring, auditing, inspection, certification and reporting processes that you have in place to ensure that the required standards are achieved;

5.2.6. Details of the suppliers incident reporting and investigation procedures;

5.2.7. Details on how subcontractors will be selected and managed, including communication of client requirements. Further details on specific requirements in this area are included below;

5.2.8. Details of the high risk products, plant/ equipment and substances will be selected, used and controlled throughout the delivery of the works;

5.2.9. Details on how applicable local legislation, Vodafone Absolute rules, and the relevant HSW Standards will be communicated and adhered to; and

5.2.10. Details of the Suppliers emergency processes.

5.3. **Catering services' suppliers** shall have and maintain a H&S plan before commencing work which must include details mentioned in 5.2 and details of the food safety program that covers:

5.3.1. Identification of where and how each hazard can be controlled; and description of how these controls, how controls are to be monitored; the corrective action required if control conditions has not been met; and records that must be in place.

5.3.2. Food cycle risk analysis and control points that includes (Purchase, delivery, storage, preparation & handling, cold holding/display, defrosting, cooking, cooling, freezing, reheating, hot holding/display, transport & distribution).

5.3.3. Biological, physical, chemical contamination, allergies, hygiene and other requirements (i.e. cleaning and disinfection, pest control, waste control, maintenance, personal hygiene, training, supervision and monitoring)

5.3.4. All the controls shall be in accordance with Vodafone, and local/international relevant standards.

5.4. **Outdoor Events' or branded vehicles / road shows suppliers** shall have and maintain a safe event plan before commencing work which must include details of:

5.4.1. The type of event, nature of performers, time of day and duration;

5.4.2. Using sufficient personal protective equipment while installing (e.g. Booths, Backdrops, Wall branding, Danglers...etc.);

5.4.3. Audience profile including age, previous or expected behaviour, special needs, etc.;

5.4.4. Existence or absence of seating;

5.4.5. Site plan including geography of the location and venue; topography;

5.4.6. Risk assessments covering:

5.4.7. Sound temporary structures to withstand the expected loads e.g. Canopies, tents, booths, stand stages, movable ladders etc.;

5.4.7.1. Installations and clearing up (e.g. Backdrops, wall branding, electrical ...etc.);

5.4.7.2. Off-site hazards within the vicinity, e.g. Industrial plant, construction sites, warehouses;

5.4.7.3. Crowd control;

5.4.7.4. Catering & steward;

5.4.7.5. On-Site and off-site traffic; and

5.4.7.6. Electrical installation, temporary wiring, and power supplies control.

5.4.7.7. Working in dark / low visibility areas

5.4.8. Emergency & Evacuation Plans;

5.4.8.1. Fire, explosions, terrorism or structural failure

5.4.8.2. Power & Safety Equipment failure

5.4.8.3. First Aid & Ambulance presence

5.4.8.4. Weather e.g. excessive heat/cold/rain/wind

5.4.8.5. Evacuation Routes & Emergency Exits

5.4.8.6. Firefighting equipment and consideration of requirements for inaccessible areas

5.5. **Managed Service Provider:** shall have and maintain a safe operational plan as a part of HSW plan before commencing work which shall include:

5.4.9. Detailed scope of the operation including location, nature of operation, working pattern, premises details (e.g. layout, area, number of floors, accessibility, geography of the location and venue; topography...etc.);

5.4.10. Risk assessments, method statements and safe systems of work that detail how the operation will be managed safely through different stages (i.e. construction, site preparation, commissioning, and operation) considering:

5.4.10.1. Off-site hazards within the vicinity, e.g. Industrial plant, construction sites, warehouses;

5.4.10.2. Access requirements for people with disability and/or mobility needs;

5.4.10.3. Factors that affecting workplace environment include (Welfare facilities & Hygiene -i.e. Rest rooms, catering, washing rooms, pest control, first aid provision, Ergonomics, lighting, ventilation, and clean water supplies ...etc.);

5.4.10.4. Property and facility management include corrective and preventive maintenance program by competent vendors, with clearly communicated processes for reporting faults and controlling and authorizing work;

5.4.10.5. Safe storage and handling of material/goods; and

5.4.10.6. On-Site and Off-Site Traffic, considering proper traffic arrangements and segregation / signage for the protection of pedestrians and visitors.

5.4.11. Emergency & contingency Plans (fire/explosion, terrorism; structural failure; collapse; disorder; lighting or power failure; safety equipment failure, e.g. excessive heat/cold/rain);

5.4.12. Fire safety and emergency procedures to include: (Training, Evacuation plans, Emergency exits, Firefighting equipment and consideration of requirements for inaccessible areas, Fire detection / prevention equipment and testing requirements) in accordance with national statutory requirements and in consultation with the local Fire Authority.

6. Driving and Vehicle Safety

Suppliers, supplier's personnel, and contractors shall comply with Vodafone Supplier Policy– A3 (paragraph 6) in addition to the following requirements:

6.1. **Vehicle specifications**

6.1.1. All vehicles purchased, hired or leased must be in line with local policies and legislative requirements, and be assessed as fit for their intended purpose.

6.1.2. All vehicles must be fitted with appropriate safety features, ex. minimum double airbags, anti- lock braking systems (ABS) and have manufacturer's three (3) points seatbelts and safety restraint systems installed and functional for all seats / occupants.

6.1.3. The number of passengers must not exceed manufacturer's specifications for the vehicle. No carrying of excess passengers or transporting people in the back of pickup trucks. Transporting unauthorized passengers is prohibited.

6.1.4. Loads must be secure and must not exceed manufacturer's specification and legal limits for the vehicle. Passengers and loads shall never be transported in the same compartments.

6.1.5. All vehicles must be fitted of hands-free car kits and ensure prohibition of the use of hand held mobile phones or any other devices while operating the vehicle.

6.1.6. All vehicles must be equipped with speed and location tracking system (telematics) where the system has to be approved and authorized from national regulators and authorities (e.g. NTRA).

6.1.7. All vehicles must be equipped with Visual Tracking System "approved from national regulator authorities" that records and live-streams videos from inside and outside the vehicle as long as it's operated or having passengers inside during Vodafone work-related activities where and when applicable, legitimate and agreed to do so.

6.2. **Vehicle** shall be replaced after five (5) years as of date of manufacturing or reaching three hundred thousand (300,000) KM (whichever occurs earlier).

6.3. **Vehicles' tyres** must be fit for the propose, not to have any lump, bulge or tear caused by separation or partial failure of the structure, and to be replaced when defected/or every 50,000km of use (whichever occurs earlier) unless stated by manufacturer.

6.4. **Vehicle maintenance** shall be done at approved maintenance centres or workshops assigned and approved by manufacture. The Supplier shall only use genuine replacement parts and tyres in accordance with the vehicle manufacturer's maintenance and specifications. Records of maintenance should be retained and monitored.

6.5. **Drivers:** must be appropriately assessed, licensed, trained, and medically fit to operate the vehicle within their defined driver classification and have access to health surveillance and ongoing monitoring to ensure they are fit to drive. Drivers are obliged to abide to absolute rules, follow proper safe road behaviours at all times, Expect the Unexpected (e.g. reduce speed when driving through any areas impacted by road works unless specific speed stated by official authority), using the vehicle only for its intended purpose, and ensure that all passengers' seatbelts are fastened including their own, as long as they are in the vehicles, and must not carry any unauthorised passengers in or on the vehicle. Drivers shall report to the Supplier any health/medical issues/incident which could affect their own safety performance. When driving only essential phone calls are allowed through car kit and drivers must limit the frequency and duration of the call.

6.6. **Vehicle passengers** are responsible for their own safety. Their behaviours shall support the safe operation of the vehicle by doing the following:

6.6.1. Report immediately any driving violation.

6.6.2. No smoking inside company vehicles.

6.6.3. Always fasten their seat belts while inside the vehicles

6.7. **Incident reporting & notification**; Supplier shall report all road traffic accidents, severe weather conditions, and any arising route related issues to Vodafone Egypt Health and Safety team on 01001793777 as soon as possible, and to send official notification within 24hrs in case of incident that at least covers the incident notification form in Annex (HSW22A-9) and to include as a minimum "location, injured persons & type of injury, short description of the incident & immediate actions, Vehicle & driver details, photos" .

6.8. Supplier shall have a programme for **medical examination** where any personnel driving company vehicles for business related issues covering:

6.8.1. **Pre-employment written and signed commitment** that the driver doesn't suffer from chronic disease "such as but not limited to epilepsy" that could affect the ability to operate the vehicles safely (e.g. losing conscious or fainting ...etc.).

6.8.2. **Pre-employment and annual:** medical checks that includes as a minimum:

6.8.2.1. Diabetes test to avoid Coma;

6.8.2.2. Balance test to avoid sudden dizziness;

6.8.2.3. Full drug test that includes qualitative and quantitative (Cannabinoids, Benzodiazepines, Barbiturates, Amphetamine, Tramadol, Opiates, Vodo, Strox, Flaka, Lyrica, Actig, Adderall, Alpra, Zolam, Amital, Avinza);

6.8.2.4. Back bone survey to check for disk rupture; and

6.8.2.5. Ophthalmic (vision & colour blindness) test.

6.8.2.6. Blood pressure examination.

6.8.2.7. Depakin test (Valproic acid level)

6.8.3. **Random drug test:** annual random drug test examinations to all personnel driving company vehicles covering the whole workforce.

6.8.4. **Remedial Drug test:** for drivers and assignee who had accidents.

6.9. **Training**; defensive driving training is mandatory for all drivers, before driving any vehicle. The following types of training should be offered:

6.9.1. **Basic** training for any personnel driving company's vehicles;

6.9.2. **Remedial** training for drivers and assignee who had accidents; and

6.9.3. **Periodic** refresher update of basic training typically provided every two (2) years.

6.10. **Drivers** who are not medically fit to drive shall not be accepted to operate vehicles until being fit to do so and upon passing a medical assessment by a **qualified doctor**.

6.11. **Journey Management & Trip planning**: Risks of the road journey shall be assessed and controls shall be in place. Journey management plans should identify the risk of driver fatigue considering distance, total working hours, total driving hours, single and multiple journeys, rest periods, time, road type, driving in the dark and must always consider return journeys, highlighting that the work schedules, geographical areas of responsibility, health surveillance needs and duration of time on the road are reviewed regularly, considering some main controls to mitigate/reduce the risk such as:

6.11.1. Drivers shall work for a maximum of six consecutive days and have a minimum of one full day off on a weekly basis, considering the below examples:

6.11.1.1. Working at morning example (6AM-6PM): In cases such as the last shift ends on Thursday 6 PM, then Friday shall be a full day off, and returning to work could be either on the next Saturday morning shift or Saturday night shift, highlighting that working on the Friday in such case will be considered a breach

6.11.1.2. Working at night example (6PM-6AM): In cases such as the last shift ends on Friday 6 AM, then he shall take Saturday as a full day off, and returning to work could be either on the following Sunday morning shift or Sunday night shift, highlighting that working on this Saturday in such case will be considered a breach.

6.11.1.3. In Ramadan Month and such occasions: Drivers' working time shall be a consecutive time either at morning or at night and to be reduced in relevant with Ramadan fasten time, highlighting the other journey management aspects shall be considered.

6.11.2. Drivers shall take fifteen (15) minutes rest after every two (2) hours of continuous driving.

6.11.3. Drivers total maximum working time per each working day shall be equal or less than twelve (12) hours shift period, which including trip from home to work, any other work, rest time, waiting and driving time.

6.11.4. Drivers shall have a minimum of eight (8) hours uninterrupted off duty rest between shifts.

6.11.5. Drivers shall take additional rest when experiencing tiredness or fatigue while driving.

6.11.6. In case of the trip require staying for a day or more; then line managers/supplier shall be responsible to ensure that the appropriate accommodation and welfare facilities are provided, so that the driver can have his/her rest in.

6.11.7. Night traveling between governorates shall not be undertaken and to be avoided with alternative safe scheduling.

6.11.8. Any exception requires a prior approval from Vodafone Egypt senior manager and HSW team, in addition to, extra precautions shall be considered such as speed limits reduction, fatigue assessment, and GPS surveillance till ensuring safe arrival to assigned destination.

6.11.9. Maximum of ten (10) hours within the twelve (12) hour shift period, including trip from home to work, any other work, rest time, waiting and driving time and a one day off on a weekly basis.

6.12. **Adverse weather conditions:** during bad weather conditions that might include (heavy fog, heavy rains, sandy storms or any condition that could affect the vehicle stability or road visibility), Supplier shall assess all driving activities to take the proper safe decision whether to stop driving till being able to drive safely or to take appropriate precautions from Health and Safety prospective while driving.

6.13. Supplier shall dedicate a responsible person for the Implementation of a strict program to monitor driver behavior, included as a minimum:

6.13.1. Drivers commitment to speed limits, and night travelling, and not to drive at speeds that are dangerous for the road conditions, through GPS tracking system / Telematics;

6.13.2. Seatbelts must be worn by all occupants at all times when a vehicle is in motion & this could be through sensors, cameras, mystery shoppers or other agreed with Vodafone Egypt HSW team;

6.13.3. Drivers must not carry any unauthorised passengers in or on the vehicle; and

6.13.4. Drivers must not be under the influence of alcohol or drugs, or any other substance or medication that could impair their ability to drive, and No smoking rule is applied while vehicle is in motion.

6.14. Supplier shall fully comply with forms in this standard – Annex HSW22A-4 - driving related Absolute Rules - commitment statement).

6.15. All records shall be kept and maintained up-to-date for each person/vehicle including but not limited to (pre-employment / regular and random medical examination, defensive driving training, appropriate licences, accident history, violation history, maintenance/repairing log, insurance records, Absolute Rules - driving related - commitment statement – Annexes – (Annex HSW22A-4, Annex HSW22A-5 & Annex HSW22A-6), driver's safety performance evaluation record and emergency equipment tools).

7. Working at Heights

Suppliers, supplier's personnel, and contractors shall comply with Vodafone Supplier Policy– A3 (paragraph 7) in addition to the following requirements:

7.1. Suspend work at height authorization for any person whose medical conditions presents obvious risks to his safety while at work;

7.2. Have a programme for medical examination where any personnel engaged in activity where there is a potential to fall from **1.8m** or more, covering:

7.2.1. Pre-employment written and signed commitment that the working at height rigger doesn't suffer from any chronic disease "such as but not limited to epilepsy" that could affect the ability to perform the job safely (e.g. losing conscious or fainting ...etc.)

7.2.2. Pre-employment and annual: medical checks that includes as a minimum:

7.2.2.1. Back bone survey for disk ruptures;

7.2.2.2. Diabetes test, Heart disease/chest pain;

7.2.2.3. Giddiness/difficulty with balance;

7.2.2.4. High blood pressure;

7.2.2.5. Fear of heights/vertigo;

7.2.2.6. Ophthalmic (vision & colour blindness) test; and

7.2.2.7. Full drug test that includes qualitative and quantitative (Cannabinoids, Benzodiazepines, Barbiturates, Amphetamine, Tramadol, Opiates, Vodo, Strox, Flaka, Lyrica, Actig, Adderall, Alpra, Zolam, Amital, Avinza);

7.2.2.8. Depakin test (Valproic acid level)

7.2.3. **Random drug test:** annual random drug test examinations to all working at heights personnel.

7.3. Training: Prior to any engagement of personnel in activities where there is a potential to fall from 1.8m or higher, he/she must attend and pass appropriate trainings at Vodafone Egypt approved training providers;

7.3.1. Basic training for all engaged personnel; and

7.3.2. Periodic refresher update of basic training typically provided every two (2) years.

7.4. No-one is permitted to work on fragile roofs (e.g. corrugated sheets, roof with sky lights/ weak points);

7.5. No-one is permitted to work within two (2) meters of an unprotected roof edge without use of suitable body harnesses attached to a fall protection device (e.g. anchor point, wire or rail fall arrest system);

7.6. Make sure that all working at heights is performed under supervision from site engineer or team leader or HSW officer, fall arrest equipment and a rescue plans must be in place;

7.7. Any work involving use of tools and equipment needing to be undertaken within two (2) meters of an unprotected roof edge shall be preceded by the declaration and marking of safer working area and an evacuated drop zone below the work area;

7.8. Consideration is taken to make sure that the system used for handling loads whilst climbing shall be given prior to the activity. These systems may include carrying light loads in a backpack, manhandling by use of ropes or winches and the use of hoists or cranes;

7.9. All personnel will ensure that all equipment used are suitable and adequate to the purpose intended, and has been properly inspected, tested and examined;

7.10. **Weather conditions:** Structures shall not be climbed if the following conditions are present:

7.11. Wind storms; Heavy rain; High or gusting winds; Poor visibility; and

7.12. If any of these conditions in Clause 7.10 are detected and considered detrimental to continue working, personnel working at height shall immediately stop all activities.

7.13. All WAH activities must have a minimum of two riggers per activity both trained on rescue techniques with rescue kit should be available on site.

7.14. **Scaffolding:**

7.14.1. Scaffolding (mobile and fixed) to be structurally sound, erected & use; alternation and dismantling in accordance with safe work practices and by suitably qualified persons. High risk installation should be certified and inspected prior to use and / or every 7 days by a qualified person. In case of accidental event and /or adverse weather conditions; re-inspection is required.

7.14.2. The erecting and dismantling of scaffolding must only be done by trained and competent scaffolders.

7.14.3. All competent scaffolders shall have in their possession a valid training certificate for the erecting and dismantling of scaffolding

7.14.4. All users of scaffolding shall be trained and hold a valid certificate for working at height

7.14.5. There shall be a safe access to the scaffold "As a minimum this should be a tied ladder with 3 rungs projecting above the step off at the platform level to provide a handhold i.e.: the equivalent of at least 1m", and a safe system for lifting any materials up to the working height.

7.14.6. Ensure that there are no gaps in guard rails and toe bards forming edge protection through which either anyone could fall or an object be dropped onto people below, Scaffolding shall be suitably anchored, secured to adjacent structures, and shall be inspected pre-use by user, and weekly by competent inspector.

8. Portable Ladders:

8.1. Suppliers, supplier's personnel, and contractors shall comply with Vodafone Supplier Policy– A3 (paragraph 8) in addition to the following requirements:

8.2. Staff and contractors shall commit that the portable ladder used is suitable for the task & only used for temporary work at height with the following specifications:

8.3. Fit for purpose: Aluminum of lightweight & can be used for range of tasks, for electrical work it is advised to use (Glass Fibber). Wooden ladders should be avoided.

8.4. Correct Usage:

8.4.1.1. Good condition (firm & clean treads), right position (fully opened, locked into place & will not move at the bottom), secured (fastened or anchored at all times and/or being held by another person), standing on (firm, clear, dry, horizontal & not slippery) surface, long enough not to make the user have to stand on the top 3 rungs.

8.4.1.2. User shall only carry light materials and tools (up to 10kg), always maintain 3-point (2 hands & a foot OR 2 feet & a hand) contact on the ladder, do not overreach, ensure having a safe handhold on the steps, and avoid side-on working.

8.4.1.3. Stepladder shall be only used when the working time doesn't exceed 15:30 minutes.

9. Electrical work

Suppliers, supplier's personnel, and contractors shall comply with Vodafone Supplier Policy– A3 (paragraph 9) in addition to the following requirements:

9.1. No live electrical work that has the potential to cause injury is permitted. The only exception to this is work with ELV systems where switching the equipment off is not practical or would cause significant disruption. Where live ELV work is deemed necessary the following precautions must be adhered to:

- 9.1.1. Any person working on live must be appropriately trained;
- 9.1.2. A permit to work must be in place (see Annex HSW22A-7– Electrical permit) ;
- 9.1.3. 1000v Insulated tools that conform to EN 60900 must be used;
- 9.1.4. As a minimum class 00 for ELV and class 0 for LV gloves that conform to IEC 60903 must be worn;
- 9.1.5. An arc flash face shield that conforms to EN166 and EN170 must be worn;
- 9.1.6. All jewellery, watches, necklaces, rings etc. are to be removed before working; and
- 9.1.7. Low flammability clothes to be worn (e.g. non-synthetic).

9.2. Where live work is deemed necessary on voltage systems exceeds ELV, approval from Vodafone Egypt HSW team & task owner Senior Manager is required before commencing the work, considering that all ELV live work precautions must be adhered to, in addition to, di-electrical shoes that conform EN 50321 must be worn or Switchgear insulating matting that conform BS EN6111 and against electric shock up to 1000 Working Volt to be used;

9.3. All personnel working on electrical equipment shall be proved competent and authorized;

9.4. Prior to work on or nearby live parts to which personnel may be exposed to, it must be de-energized using approved lockout / tagout procedures and proved dead. Approach boundaries must be considered. Stored energy must be safely released;

9.5. Before circuits or equipment is re-energized, even temporarily; the competent person must conduct tests and visual inspections as necessary to verify that circuits and equipment can be safely energized;

9.6. All electrical work on medium voltage and above MUST be controlled using a step by step photographic sign off for each life critical stage of the process;

9.7. All electrical installations and equipment must be designed, installed and maintained in line with statutory requirements, manufacturers recommendations and industry best practice;

9.8. The location of and access to electrical installations must be controlled to prevent unauthorized access.

9.9. All ladders used near exposed energized sources must have non- conductive side rails and must be clean (free of oil, grease or contamination that would cause it to be conductive). Ropes and hand lines used near exposed energized parts must be nonconductive;

9.10. All cables should be routed in such a way that they cannot be mechanically damaged i.e. pinched, crushed, cut or worn. They must be routed in such a way as to allow safe access. Splicing is prohibited;

9.11. Temporary electrical power and lighting installations 600 volts or less, including flexible cords, cables, extension cords and distribution panels, may only be used during and for renovation, maintenance, or repair, or testing. for decorative lighting of special events and similar for a period not to exceed 30 days;

9.12. RCD protection must be provided on all temporary-wiring circuits, including extension cords, used on construction sites. RCD must also be used when extension cords and/or equipment are used in wet, damp or conductive locations or in construction sites;

9.13. All portable appliances must undergo periodic inspection and testing, and visually pre-use inspected;

9.14. Electrical equipment not in use, with a potential to cause electrical injury is isolated from all sources of power and locked off using a formal lock out/tag out system;

9.15. Flexible cords and cables must be UL listed or equivalent, suitable for the location and intended use, not to be used as a substitute for fixed wiring, and must be protected from accidental damage;

9.16. All employees working on electrical equipment or parts must have adequate PPEs for electrical works; and

9.17. When work is to be performed near overhead lines, the lines must be de- energized and grounded whenever possible. If it is not possible to de-energize and ground overhead lines, then other protective measures must be taken to prevent direct or indirect before the work is started.

9.18. All electrical installations and equipment must be designed, installed and maintained in line with statutory requirements, manufacturers' recommendations and industry best practice. As a minimum, installations must have:

9.18.1. A documented routine visual checks every 12 months.

9.18.2. A thorough inspection and test every 5 years.

10. Radio Frequency (RF) Safety

Suppliers, supplier's personnel, and contractors shall comply with Vodafone Supplier Policy– A3 (paragraph 10) in addition to the following requirements:

10.1. In case Supplier personnel may be exposed to Radio Frequency (RF) field's areas where RF is present at levels that may exceed national guidance, then there shall be a signage posted at their boundaries;

10.2. All personnel who need to work in close proximity to (RF) radiators shall use an RF monitor at all times;

10.3. Before working on antennas, first ensure their deactivation by requesting that operator(s) to disable the appropriate transmitters (site shut down);

10.4. If deactivation of required antenna(s) cannot be guaranteed, then:

10.4.1. Do not stop in front of antennas;

10.4.2. Maintain a minimum of 2 metres clearance in front of the antennas (Egyptian Protocol limit); and

10.5. Use approved personal RF monitors while working near antennas.

10.6. If work is required on transmitting antennas, to avoid unnecessary exposure, the technician should place himself in a way that compliance with international (ICNIRP) reference levels is achieved;

10.7. EMF personal monitor: Not mandatory, but recommended as an additional safety measure. The personal monitors are set to measure the RF exposure levels and give sound alarms whenever measured field value are higher than ICNIRP occupational exposure limits; and

10.8. Record Keeping, Records of those staff that are potentially exposed above international (ICNIRP) Public exposure guidelines should be kept. Typical individuals who may fall into this category may be antenna riggers, radio installers or maintenance engineers.

11. Product / Equipment Safety

Suppliers, supplier's personnel, and contractors shall comply with Vodafone Supplier Policy– **A3 (paragraph 11).**

12. Ground / Civil Works

Suppliers, supplier's personnel, and contractors shall comply with Vodafone Supplier Policy– A3 (paragraph 12).

13. Overhead work/Lifting operations

13.1. Suppliers, supplier's personnel, and contractors shall comply with Vodafone Supplier Policy– A3 (paragraph 13); in addition to, the following requirements:

13.1.1. All lifting activities must be performed through a predesigned lifting plan and undertaken using suitable equipment and competent person. For high risk lifts suitable engineering certification to be obtained;

13.1.2. A pre-lift test must be done after all the procedures are in place, and the lifting operation assessment must consider Load weight, centre of gravity, balance and stability; (See Annex HSW22A-8)

13.1.3. All heavy equipment operators must be licensed with equivalent operating licenses and should undertake the proper daily inspection checklists;

13.1.4. Hoists, Cranes and Derricks shall have a valid inspection certificate/load test from accredited third party and working within equipment specifications and in accordance with EN Standards e.g. load charts, validation twelve (12) months for lifting equipment/six (6) months for lifting people;

13.1.5. All Lifting accessories shall pass visual inspection, free from defects/cuts, used properly within SWL/F.S/WLL in accordance with EN Standards (e.g. Slings, pulleys, hocks, carabiners);

13.1.6. Drop zones must be clearly defined and established. This can be done in various ways, like setting up barricades, using danger tape, fencing off the appropriate areas or using a point's man to patrol the area;

13.1.7. All persons on site must be aware of and inducted regarding the risk assessment, before the lift commences.

13.1.8. No lifting shall be done during any wet weather conditions such as rain and/or lightning, and not recommended to be done in wind conditions above 5 m/s. The site supervisor shall ultimately take responsibility and lifts can be done if the risk assessment allows the rigging team to continue with the lift;

13.1.9. No lifting shall be done during night, unless adequate lighting is available on site, such as head lamps or spot lights, and additional hazards have been mitigated in the risk assessment (Provide at least 70% of daylight intensity and prior approval from VF business owner and H&S team);

13.1.10. Working near overhead electrical power line measures shall be considered such as: ensure that none of the crane, load line or load can become a conductive, and that the operation is not within the prohibited zone;

13.2. Specific requirements for Mobile Crane Operations:

13.2.1. No one is permitted to board or leave the crane without obtaining the Crane Operator's permission & the crane shall not be left unattended.

13.2.2. Ensure that the ground (soil) can sustain loads imposed by the crane and allow to operate within the levels / parameters specified by the crane manufacturer. Side loads shall be avoided.

13.2.3. Ensure that when siting a crane, the point loads through the outrigger / stabiliser beams and jack pads are spreading to prevent the crane overturning or instability and can accommodate the crane with the outriggers extended and set as specified in the load chart.

13.2.4. Danger to and from underground services (gas, electricity, water) shall be taken into consideration to ensure that the crane foundation is clear of such services or that they are adequately protected.

13.2.5. On-site travel of fully rigged wheeled cranes, whether loaded or unloaded, shall not be allowed.

13.2.6. While in transit the boom shall be retracted and carried in line with the direction of motion and the superstructure secured against rotation (or the boom placed in a boom rack mounted on the carrier). The empty hook shall be lashed or otherwise restrained so that it cannot swing freely. If the crane has a telescopic boom it shall be set to the fully closed position.

13.2.7. Counterweights shall be properly secured and under no circumstances counterweights shall be used heavier than the manufacturer's recommended weight.

13.3. Specific requirements for man riding basket operations:

13.3.1. The suitability of the mobile crane has to be checked carefully. (e.g. The crane shall have a factor of safety of 10:1 on crane capacity for each personnel lifting operation & the lifting capacity of the crane employed is reduced to 10% at any given radius & The hook must have a safety catch)

13.3.2. The crane, suspended baskets, hook, catch, and fixed load lifting attachment to be inspected prior to each use & Lifting slings for suspended baskets shall not be used for any other purpose.

13.3.3. A crane driver always to be present at the normal crane control station when the basket is occupied.

13.3.4. Visible and/or audible communication between the persons in the basket and the crane driver shall be available at all times during the lifting operation.

13.3.5. The required equipment to perform an emergency rescue must be available.

13.3.6. People in the basket shall wear a harness with lanyard. A safety lanyard to be attached to crane hook or basket anchoring point.

13.3.7. Unintended movement of the basket should be prevented e.g. by means of guide ropes or anchoring.

13.3.8. The basket to be positioned on a firm surface when entering or exiting and/or to be secured to the structure where the work is to be performed.

13.4. Specific requirements for Counter Weight Winches:

13.4.1. Each winch, with its accessories (including derrick, gooseneck, eye-plate, eyebolt, or other attachments) should be tested with a proof load that should exceed the safe working load as follows:

13.4.1.1. If the SWL < 20 tons, the proof load should exceed the SWL by at least 25%;

13.4.1.2. If the 50 tons > SWL ≥ 20 tons, the proof load should exceed the SWL by at least 5 tons; and

13.4.1.3. If the SWL > 50 tons, the proof load should exceed the safe working load by at least 10%.

13.4.2. The proof load should be applied either:

13.4.2.1. by hoisting movable weights after the movable weights have been hoisted, then the derrick should be swung as far as practicable first in one direction and then in the other; or

13.4.2.2. by means of a spring or hydraulic balance or a similar appliance, with the derrick at an angle to the horizontal which should be specified in the certificate/record of the test, then the derrick swung as far as practicable first in one direction and then in the other.

13.4.3. Where counterweights are used, the design of the suspended working platform should ensure that the balancing moments cannot be adversely affected by easy removal of any counterweight.

13.4.4. All counterweights should be securely attached at the inner end of the outriggers to prevent tampering by any person, and the materials used must not be removed or discharged accidentally. Water or other liquids, earth, clay, sand, chipping or aggregates cannot be used as counterweights.

13.4.5. Where a suspended working platform is counterbalanced by counterweights, the counterweights on any outriggers should not be less than 3 times the weight necessary to balance the load on the projecting part of the outriggers when the working platform/loads is fully loaded.

13.5. Specific requirements for Manual lifting:

13.5.1. The maximum manual lifting load must not exceed 100kgs, thereafter a professional rigger must be appointed to continue with the required mechanical lift (by means of cranes, lifting machines, etc.).

13.5.2. Sharp edge protection / lifting blocks must be used to prevent slings being pinched and damaged.

13.5.3. Wind loading, and the additional forces it adds to the system and structure, must be considered.

13.5.4. The correct knots should be used when lifting (e.g. Figure of eight on a bight, Double figure eight loop, Figure of nine on a bight, Klemheist knot).

13.5.5. For lifting and lowering between 1-40 kilograms a pulley 1:1 system must be used, 1:3 system must be used from 40 kilograms up to 100 kilograms.

13.5.6. Anchor "attachment" points: fixed object of suitable strength to which ropes or equipment is attached for the purpose of manual lifting in order to support a load. Planned anchor points should at least comply with EN795; otherwise, Self-identified & Deviation anchor points can be used, but must have minimum break strength of 30 KN's. This must be determined by a competent person, considering that either way; both of placing and testing of anchor points must be performed by a competent person.

13.5.7. No vehicles must be used for lifting. (This includes vehicle mounted winches.), furthermore, manual lifting and lowering of any human load without approved mechanical aids/MEWP is not allowed.

13.5.8. A Rigging Supervisor, A hauler/rigger must be:

13.5.8.1. Appointed in writing by the supplier as a Rigging Supervisor, and must be medically fit, hold a valid certificate for Fall Arrest, Fall Arrest Rescue, Rope Rigging.

13.5.8.2. Complete a daily pre-task risk assessment, lifting plan, work permit and perform a TBT with the relevant rigging team, and ensure that that all persons involved in the lifting process have been made aware of their roles and responsibilities, ensure the correct slinging and rope rigging methods are used and confirm that the pre-lift was done correctly according to the lifting plan.

13.5.8.3. Ensure the correct implementation of the chosen lifting plan and also ensure that all rope rigging equipment and procedures are safe for use and fit for purpose on-site.

13.5.9. A hauler/rigger must be medically fit, hold valid certificates for Fall Arrest, Fall Arrest Rescue, Rope Rigging, adhere to the risk assessment and lifting plan set out by the Rigging Supervisor, ensure that the correct rope rigging principles are adhered to, and immediately notify the Rigging Supervisor of any dangerous occurrence or dangerous action

14. Confined Spaces

Suppliers, supplier's personnel, and contractors shall comply with Vodafone Supplier Policy– A3 (paragraph 14) in addition to the following requirements:

14.1. No work shall be commenced in confined spaces including any chamber, tank, vat, silo, pit, trench, pipe, sewer, flue, well or other similar space in which, by virtue of its enclosed nature, there arises a reasonably foreseeable specified risks unless permitted; and

14.2. Emergency equipment and procedures at least including (rescue harness; lifting tripod or other suitable means to retrieve persons from confined space; emergency breathing apparatus; suitable first aid kit; an observer and means of communication).

15. Warehouse Safety

Suppliers, supplier's personnel, and contractors shall comply with Vodafone Supplier Policy– A3 (paragraph 15) in addition to the Vodafone HSW S11 Warehouse Safety Policy requirements which will be communicated to relevant suppliers.

16. Fibre Related Activities

Suppliers, supplier's personnel, and contractors shall comply with Vodafone Supplier Policy– A3 (paragraph 16) in addition to Vodafone Global HSW S06 Health & Safety – FTTX installation and maintenance Policy's requirements which will be communicated to relevant suppliers.

17. Lone Working

Suppliers, supplier's personnel, and contractors shall comply with the following requirements:

17.1. Lone workers can, although not exclusively, be categorized as follows:

17.1.1. Work alone outside normal office hours where there are no regular security checks on premises; and

17.1.2. Who handle cash (delivery staff, retail workers etc.?)

17.1.3. Who visit remote locations?

17.2. Each undertaking to be determine based on the need for lone working assessments, which shall include:

17.2.1. A safe means of travel to and from the workplace/ premises – including when working out of hours (e.g. The nature of the tasks and the length of time a working will be alone); and

17.2.2. Restricted access, parking lots, security features and state of the building etc. Should be taken into consideration. In all cases, adequate first aid equipment and on call assistance as well as a sound means of communication must be in place.

Part C – Additional Incident Reporting & Investigation Process

18. Suppliers, supplier's personnel, and contractors shall comply with Vodafone Supplier Policy– A3 (Part C) in addition to minimum data required to be filled in annex HSW22A-9.

Part D – Additional Incident Reporting & Investigation Process

19. Suppliers, supplier's personnel, and contractors shall comply with Vodafone Supplier Policy– A3 (Part D) and obligation to compensate any of the human resources whether it's his own resources or his sub-contractors that are working for Vodafone Egypt's premises based on the following:

Fatality cases: The minimum immediate compensation shall be Fifty-Five (55) months from the total pay or minimum amount of One Hundred thousand Egyptian pounds (100,000.00 Egyptian Pounds) to be paid, whichever is greater, and shall be paid to the deceased person's family according to relevant Egyptian laws.;

Disability cases: Based on the same amount mentioned above in in the Fatality cases, compensation shall be a percentage in accordance to partial and permanent disability insurance index mentioned in the Egyptian Social Insurance Law and its valid amendments at the time of incident, and to be paid to the injured person or his official trustee according to relevant Egyptian laws.

Annexes

The current Annexes may be modified or updated without modification of the entire policy/document!

Annex (HSW22A-1)

Site Risk Assessment Safety Checklist				
Form 1/2				
Important Note: This form must be assessed carefully according to job type, any marked questions with "Unsafe", you should go to form 2/2 named "Residual risk register" to re-assess the uncontrolled identified hazards, where additional control measures must be in place prior starting the job				
Assessment Date:				
Site ID:				
Site Name:				
Site type:				
Contractor:		**Signature:**		
	Potential Hazards	***Status***		
		YES (Safe)	***NO (Unsafe)***	***NA***
People	Person(s) who carry the job:			
	1- Are all team members are competent, certified, and authorized to do the job?			
	2- Are all team members are Medically fit to do the job they are assigned to			
	3- Is a competent supervision available on site?			
	4- Is any high risk activity by minimum of two (2) personnel attending and at least one of them trained on emergency procedures; (e.g. WAH Rescue, emergency shut down, first Aid, Firefighting ...etc.?			
General Site Conditions	1- Is the site housekeeping in good conditions?			
	2- Is the site is secured and has limited access ? and are all the warning and safety signage in place (e.g. Electrical, limited access, climbing, Radiation ...etc. ?			
	3- Are the site & surrounding area free from flammable, combustible liquids, or gases, explosives agents, vapors, fumes, dusts, and mists?			
	4- Are all the means (e.g. Doors, road, stairs ..etc.) allow safe access and egress ?			
	5- Is there a safe distance from overhead electrical cables ?			
	6- Is the site free of animals, snake, and other harms attack?			
	7- Is electromagnetic risk controlled?			
	8- Are all electrical conductors and apparatus passed visually inspection "isolated and working properly" (e.g. wires, cables, switches, controls, generator, transformers, lamps, batteries, fuses, D.B protection, Earth means installed etc.)?			
	9- Is there any further unsafe condition observed in site ?			
Activity	1- Is manual lifting used in accordance with good practices "e.g. Planned, appropriate pulley's system used, drop zones marked, secured and done under supervision ...etc." ?			
	2- Are lifting operations planned before being undertaken and using suitable equipment, competent operator who has a valid license and applying Good Work Practices?			
	3- Are appropriate controls for working at height applied (e.g. Only by trained and physically proven, two riggers minimum, using fall arrest or fall restraint system properly... etc.?			
	4- Is the rooftop safe (e.g. roof edge protected, no skylight, no fragile roof, no weak points)?			
	5- Is the rooftop safe enough (no skylight, no fragile roof, no weak points)?			
	6- Safe load limits are calculated prior to start the work?			
	7- is the area under loading clear and allow safe movements? Is drop zone marked?			
	8- Rigging equipment for material handling is inspected prior to use in each shift?			
	9- Are all Hot Works controls applied (e.g. Planned, trained on use and techniques ones, using Proper PPEs/PPCs, rescue and emergency plane developed and in place... etc.?			
	10- Are electrical work controls applied (e.g. No live working, proper PPEs, Tag out/Lockout, portable hand tools grounded or double insulated, Earth means, permanent wiring used instead of extension cords ... etc.??			
PPE & Tools	1- Are appropriate PPEs used and pre-inspected as hazards are indicated?			
	2- Are fall protection PPEs and tools used in a good safe working condition (e.g. harness, lifelines, and lanyards?			
	3- Foot & Head protection (in a good safe working condition)			
	4- Are all tools and equipment subject to an appropriate system of pre-use/after use checks, visual examination and are they maintained in a safe condition, neatly stored, safely carried?			
Car Safety	1- Does each van, bus, or truck used to transport employees comply with Vodafone requirement (e.g. Airbags, ABS, seatbelts, equipped with emergency kits etc.)?			
	2- Is the car driver trained on safe driving techniques?			
	3- Is there an inspection checklist inside the car, signed by the site engineer?			
	4- Are car daily inspection, preventive/corrective maintenance, and driver evaluation done and proven?			
	5- Are there a speed monitoring system and car kit installed in the car?			
Emergency Response	1- Is there an emergency response plan in place ?			
	2- Are People well trained on the emergency plan?			
	3- Is the first aid kit fully loaded with all the required materials?			
	4- Is there a certified fire fighter at the site?			
	6- Is there proper maintained 3 Kg fire extinguisher with the team ?			
	7- Is there a certified working at height rescuer at the site?			
	8- Is there proper maintained rescue kit and prepared to use ?			

Residual Risk Register					
Form 2/2					
A	Death/Major injury or major damage to property or equipment	1	Likely to occur	A1/A2/B1	Unacceptable, Stop the work, immediate action to reduce the risk, apply more control
B	Reportable injury (I.e. Over 3 days absence) or damage to property or equipment	2	Possible to occur	A3/B2/C1	Urgent attention to reduce risk
C	Minor injury or minor damage to property or equipment	3	Slight chance of occurring	B3/C2/C3	Attention is required , Frequent review to ensure

Identified Hazards (uncotrolled)	Additional Control Measures	Risk Evaluation		
		Severity	Liklihood	Priority

Assesor's Signature / Date	

Annex (HSW22A-2)

PPE DESCRIPTION		CONSTRUCTION WORKS																FACILITIES MANAGEMENT									NETWORKS		
	REPLACEMENT PERIOD	Heavy Machinery (Excavation, lifting etc)	Scaffolding/Platform/ Heights	Electrical Works	Hot works (Welding)	Confined Space	Rigging	Mechanic works	Concerete Work	Working with pressurised water and air	Flooring works	Painting	Basic Cleaning after construction	Demolition works	Working with grinders	Manual Handling	Works involving chemicals	General cleaning	Facade cleaning	Waste disposal works	Fire fighting	Catering works	Clinic works	Security	Maintenance	Warehouse	Electrical works	Mast/Towers	Rooftops
WORKCLOTHES																													
Reflective vest	6 MONTHS	X	X	X	X	X	X		X	X	X	X	X	X	X	X		X	X	X						X			
Welding suit					X																								
FOOT PROTECTION																													
Safety shoes (toe protection)	1 YEAR	X	X		X	X	X		X				X	X	X				X	X						X			X
Dielectric boots	3 YEARS			X																							X		
HAND PROTECTION																													
Hygen glove																						X	X						
Mechnical gloves (Cut/Abrasion)	6 MONTHS	X	X			X	X	X	X	X				X	X	X		X	X						X	X		X	X
Chem resist gloves	6 MONTHS					X	X	X			X	X	X			X	X	X	X						X				
Dielectric gloves	3 YEARS			X		X																					X		
FALL PROTECTION																													
Safety harness	5 YEARS		X			X	X	X	X			X		X					X						X	X		X	X
Safety rope	5 YEARS		X			X	X	X	X			X		X					X						X	X		X	X
Shock absorbing lanyards	5 YEARS		X											X					X							X		X	X
HEARING PROTECTION																													
Earplug/Earmuff	3 MONTHS	X	X	X	X	X	X	X		X				X	X		X	X	X		X				X	X			
EYE & FACE PROTECTION																													
Safety glasses (Color/Impact resist)	2 YEARS	X	X				X	X	X	X				X	X	X		X	X						X	X	X	X	X
Safety glasses (Transparent/Impact resist)	2 YEARS	X	X			X	X	X	X	X	X	X	X	X	X	X		X	X						X	X			
Faceshield/Chemical Resist	2 YEARS				X	X		X						X			X								X				
HEAD PROTECTION																													
Safety hardhat/Impact resist	5 YEARS	X	X	X	X	X	X	X	X	X	X	X		X	X				X		X				X	X	X	X	X
RESPIRATORY PROTECTION																													
Hygen mask																						X	X						
Respirator	3 YEARS					X								X						X	X								
Cartridge	2Y-SHELF																												
WELDING PROTECTION																													
Leather glooves	1 YEAR				X									X														X	X
Leather apron	1 YEAR				X									X															
Welding googles	2 YEARS				X									X															

Annex (HSW22A-3)

PPE Standards:

- PPE for Working at Heights

1. Fall Arrest Equipment Standards:
    1. EN 361 EN 358, EN 813 Harness for fall arrest
    2. EN 354/ EN 355 Lanyards/ Energy (shock) absorbers for industrial use
    3. EN 360 Retractable line fall arrestors
    4. EN 362 Connectors (karabiners) for industrial use
    5. EN 363 Complete fall arrest systems
    6. EN 353-1 Fall arrestors on a rigid anchorage line/rail
    7. EN 353-2 Fall arrestors on a flexible rigid anchorage line/rope
    8. EN 795 Anchors for fall arrest, Types A, B, C, D
2. Work Positioning Equipment:
    1. EN 358 Sit harnesses
    2. EN 358 Lanyards for work positioning (pole straps, etc.)
    3. EN 341 Descenders
    4. EN 567 Rope clamps (ascenders, etc.)
    5. EN 12278 Pulleys
    6. EN 1891 Ropes for "industrial" rope access and climbing
3. Other PPE for working at height
    1. EN 397 Construction industry safety helmets
    2. EN 12492 Mountaineering helmets
    3. EN 12275 Maillions (quick links)
    4. EN 566 or EN 795B or EN 1492-2 for rigging slings/ Slings (man-made fibre)
    5. BS 1290 Wire Slings

- PPE FOR ELECTRICAL WORK:

1. EN/IEC 60903 Live working - Gloves of insulating material and Insulated tools
2. EN50321 Footwear for Live working
3. EN6111 Switchgear insulating matting
4. EN166 and EN170 Arc flash face shield

Annex (HSW22A-4)

For all professional drivers in Vodafone Egypt

تعليمات السلامة و الصحة المهنية للقيادة الامنة

طبقا لسياسة شركة فودافون مصر ---------- **(الاسم رباعي)** ----------

بطاقة شخصية رقم ---------- رقم ID ---------- اسم **الشركة:** ----------

بالتزامي الكامل بتنفيذ تعليمات السلامة و الصحة المهنية الآتية و في حالة مخالفتي لأي من/كل هذه التعليمات أن تقوم الشركة بتطبيق الجزاء طبقا للائحة الجزاء آت في هذا الإقرار.

توقيع السائق: ---------- **التاريخ:** / /

1- **حزام الأمان:** - **ارتداء حزام الأمان قبل التحرك بالسيارة.** - **عدم التحرك بالسيارة إلا بعد التأكد من أن جميع ركاب السيارة قاموا بربط حزام الأمان (الكراسي الأمامية و الخلفية).**	2- **عدم استخدام يديه لاستعمال التليفون المحمول (او أي جهاز اخر) أثناء القيادة.** ***يسمح في الحالات الطارئة الهامة فقط التحدث في التليفون المحمول من خلال السماعة و لمدة قصيرة**	3- **عدم تناول أي مخدرات او كحوليات و كذلك أي أدوية إلا بمعرفة إدارة الحركة.**	4- **عدم تجاوز سرعة الطريق المحددة تحت أي سبب**
5- **الإبلاغ عن لحوادث/الاصابات:** - إبلاغ مدير الحركة بأي إصابات أو مشاكل صحية قد تؤثر على أمان و سلامة القيادة و الركاب. - إبلاغ مدير الحركة بأي حوادث او مشاكل فنية في السيارة قد تؤثر على أمان و سلامة القيادة و الركاب.	6- **عدم التدخين داخل سيارات الشركة** تحت أي سبب و عدم السماح لأي من ركاب السيارة بالتدخين داخل السيارة.	7- **الفحص اليومي للسيارة:** - فحص السيارة يوميا و تسجيل الفحص في النموذج الخاص بهذا الفحص و إبلاغ مدير الحركة بأي مشاكل متعلقة بهذا الفحص.	8- **الالتزام بتوقيتات الصيانة** اللازمة للسيارة و عدم التأخر في تنفيذها.

لائحة الجزاءات

نوع المخالفة	المرة الأولى	المرة الثانية
عدم ارتداء حزام الأمان أثناء القيادة	إنذار كتابي بالفصل	فصل نهائي
تعدي سرعة الطريق المقررة	إنذار كتابي بالفصل	فصل نهائي
استخدام المحمول باليد أثناء القيادة	إنذار كتابي بالفصل	فصل نهائي
القيادة تحت تأثير مخدرات / كحوليات	فصل نهائي	
السرعة الزائدة المتسببة في حادث يمكن أن يؤدي لخسائر بشرية و مادية	فصل نهائي	

Annex (HSW22A-5)

" Driving Absolute Rules"

Driver Safety & Quality Evaluation From

نموذج تقييم سلامة و جودة السائق

Thank you for your time. It is important to us to receive your feedback regarding driver safety performance. Please fill this form and send it by mail to **HSW Help Desk**, *for more details, please have a look on the back of this paper*.

Driver name (اسم السائق):	Date (التاريخ):
Plate number (رقم اللوحة):	

Question (السؤال)	Yes نعم	No لا	Comment (ملاحظات)
Does driver comply with road speed limits? هل السائق ملتزم بالسرعة المحددة للطريق؟			
Does driver fasten his seatbelt while driving? هل يقوم السائق بربط حزام الأمان أثناء القيادة؟			
Do all car passengers (including you) fasten their seatbelts? Have you been asked to? هل يقوم جميع ركاب السيارة (بما في ذلك أنت) بربط حزام الأمان؟ هل طلب منك ربط الحزام؟			
Does driver use handheld mobile or any other device while driving? Are the telephone calls only for emergency and done through the car Bluetooth kit for a limited short duration? هل يقوم السائق استخدام يديه لاستعمال التليفون المحمول او أي جهاز اخر أثناء القيادة.؟ عند استخدام التليفون للتحدث يكون ذلك في الحالات الطارئة الهامة و من خلال السماعة البلوتوث الملحقة بالسيارة و لمدة قصيرة؟			
Is the car clean? هل السيارة نظيفة؟			
Do driver/any passenger smoke inside the car? هل يقوم السائق أو احد الركاب بالتدخين داخل السيارة؟			
Does driver leave enough distance between his car and the car in front of him? هل يترك السائق مسافة كافية بين سيارته والسيارة التي أمامه طوال مدة الرحلة؟			
Does driving use signals and mirrors frequently and when necessary? هل يستخدم السائق الإشارات والمرايا بصورة صحيحة؟			
Does driver follow safety rules in changing lanes? هل يتبع السائق قواعد السلامة في تغيير الحارات ؟			
Does driver pay full attention to other vehicles, and road users هل يقوم السائق بالانتباه الكامل للمركبات ومستخدمي الطرق الأخرى؟			
Does driver keep lane as much as possible? Does he use the proper lane? هل يستخدم السائق الحارة الصحيحة المخصصة له بأمان؟			

Employee Name (الإسم)	
ID number	Mobile number

Safety Driving Absolute Rules

قواعد السلامة المطلقة القيادة

Abide road speed limits	التقيد بحدود السرعة على الطريق
Fasten seatbelt (All car passengers).	ربط حزام الأمان لكل مستخدمي السيارة
Do not use handheld mobile while driving.	عدم استخدام المحمول باليد أثناء القيادة
Do not drive under the influence of drugs or alcohols	عدم قيادة السيارة تحت تأثير المخدرات أو الكحول

Safe Travelling distance

3 seconds rule. Select a fixed object on road, and count 1001, 1002, and 1003. If you reach the object before counting 1003, you should leave more space. The below table is a guide:

Driving Speed (KM/Hr) سرعة القيادة (كم / ساعة)	Travelling distance (Meter) مسافة السفر (متر)
30	20
40	27
50	35
60	40
70	50
80	55
90	65
100	70
120	85

At stopping, you should to see the wheels of the car in front of you

في حالة التوقف، يجب عليك أن ترى عجلات السيارة أمامك

Lane change rules ***قواعد الأمان الخاصة تغيير الحارات***

- Look at mirror, avoid blind spot.

انظر على المرآة، تجنب النقطة العمياء

- Use signal and increase your speed slightly.

استخدام الإشارات وزيادة السرعة قليلا

- Leave enough space and time to other cars to see you and realize your decision.

اترك مساحة كافية و وقت كافي للسيارات الأخرى لرؤيتكم ولتحقيق قرارك

- Change the lane.

قم بتغيير الحارة

Annex (HSW22A-6)

" Driving Absolute

Vehicle Daily Check-up from

نموذج فحص السيارة اليومي

اسم السائق		اليوم		التاريخ	
نوع السيارة	☐ باص ☐ ميكروباص ☐ سيارة ☐ نقل ☐ فان				
رقم السيارة					

ضع علامة (√) إذا كانت نتيجة الفحص (نعم) أو علامة (X) إذا كانت نتيجة الفحص (لا)

نوع الفحص	الحالة		ملاحظات
	نعم	لا	
1. فحص مستوى زيت المحرك			
2. فحص أجهزة التنبيه والتأكد من صلاحيتها			
3. فحص عجلات السيارة والتأكد من صلاحيتها			
4. فحص الفرامل والتأكد من صلاحيتها			
5. التأكد من صلاحية الإطار الاحتياطي			
6. فحص الإضاءة الخاصة بالمعدة والتأكد من صلاحيتها			
7. التأكد من صلاحية طفاية الحريق			
8. حزام الأمان موجود وبحالة جيدة			
9. البطارية سليمة وأقطابها سليمة			

توقيع السائق القائم بالفحص:

تعليق السيد مدير الحركة على (أعطال) الفحص:

Annex (HSW22A-7)

Energized Electrical Work Permit	
Part I: To be completed by the requester or supervisor of the job	
(1) Identify requester Name:_____ Work Unit:_____	Date: _____
(2) Job location: _____	
(3) Description of work to be done: _____	
(4) Explain why the circuit cannot be de-energized or the work delayed until the next scheduled outage: _____	
(5) Signature of requester:_____Title:_____	
Part II: To be completed by the qualified/authorized person(s) completing the work	
(6) Description of circuit and equipment: _____	
(7) Detailed description of procedure to be used in performing the above work: _____	
(8) Safe work practices to be used: (Check all that apply)	
Barriers/Boundaries	Non-conductive covers/blankets
Voltage rated tools	Attendant
PPE	OTHER – (Describe)
Lock Out & Tag Out other circuits/tools	
(9) Maximum Voltage that will be exposed:	
(10) What rating is the upstream protective device? (Amperage):	
(11) Limited and Restricted Boundaries for **Shock Protection hazard**: Table **(130.4(D)(a))** for **(AC)** systems and Table **(130.4(D)(b))** for **(DC)** Systems in the **NFPA 70E** standard): Limited boundary =_____ Restricted boundary = _____	
(12) Determination of flash protection boundaries: Table **(130.7(C)(15)(A)(b))** for **(AC)** systems and Table **(130.7(C)(15)(B))** for **(DC)** Systems in the **NFPA 70E** standard): Higher Voltages must be calculated by Electrical Engineer. **Calculation Results:** _____meter _____cm	
(13) Determination of **Arc-Flash Hazard PPE Categories**: Table **(130.7(C)(15)(A)(b))** for **(AC)** systems and Table **(130.7(C)(15)(B))** for **(DC)** Systems in the **NFPA 70E** standard):	

(14) PPE required to safely perform the task: *Table* **(130.7(C)(16) Personal Protective Equipment (PPE)** based on **NFPA 70E** standard

- **Check all that apply.**

- **Circle class of PPE and minimum calorie rating where applicable.**

Voltage rated gloves – class 00, 0, 1, 2, 3, 4	Long sleeve shirt (non-melting)
Voltage rated tools	Long pants (non-melting)
Safety glasses or goggles	Long sleeve FR shirt - Calorie rating 4, 8, 25, 40
Hearing protection	Long FR pants - Calorie rating 4, 8, 25, 40
Hardhat - (Class G "Formally A" up to 2,200 Volts / Class E "Formally B" up to 20,000 Volts)	FR coveralls- Calorie rating 4, 8, 25, 40
Hardhat with flame retardant liner - (Class G up to 2,200 Volts / Class E up to 20,000 Volts)	FR jacket or rainwear- Calorie rating 4, 8, 25, 40
Leather boots/shoes	Flash suit- Calorie rating 4, 8, 25, 40
Leather gloves	Flash hood - Calorie rating 4, 8, 25, 40
Dielectric over-boots/shoes	Balaclava (sock hood) – Hazard/Risk Category 2* only
Arc rated face-shield - Calorie rating 4, 8, 25, 40	OTHER:

(15) Method used to restrict access to the work area:

Safety Signs and Tags (tape, physical barrier)
Attendant

(16) Will a job briefing be completed that covers all of the following items?

Hazards associated with the job	Energy source controls
Work procedures involved	PPE
Special precautions	Other

Do you agree the above work can be done safely? Yes (Forward to HSW) No (Return to requester) Note that additional information may be requested by the Electrical Safety Committee.(i.e. HSW & Operation Owner)

Qualified Person performing work: _____ Date: _____

Qualified Person performing work: _____ Date: _____

Attendant:_____ Date: _____

Qualified Person's Supervisor: _____ Date: _____

Part III: To be completed by members of PSU Electrical Safety Committee

Approvals:

Services Representative: Signature_____ Job Title_____ Date_____

Electrical Engineer: Signature_____ Job Title_____ Date_____

HSW: Signature_____ Job Title_____ Date_____

Permit Expiration Date & Time:

Approved **NOT Approved**

Annex (HSW22A-8)

LIFTING OPERATION PLAN	PAGE 1 of 1
Location:	Area:
Site /Project ID #	
Is Diagram/Sketch/Calculations Of Lifting Operation Enclosed? YES/NO NR.:	
Description Of Lifting Operation:	
Lift Category: Routine: Non-Routine:	
Weight Of Load: Actual /Assessed (delete as appropriate)	
Lifting Equipment & Accessories to be used (specify type ,SWL and colour code)	
All Lifting Operations Require The Following To Be Considered But This List Is Not Exhaustive.	
o Cultural, communication and language difficulties	o Conflicting tasks in area
o Weight, size, shape and centre of gravity of load	o Environmental conditions including permissible limits weather and permissible limits
o Availability of approved lifting points on load	o Lighting in the pick-up and lay-down areas;
o Method of slinging/attaching/detaching the load	o Proximity hazards, obstructions, path of load
o Overturning/load integrity/need for tag lines	o Working under suspended loads
o Suitability and condition of lifting equipment to be used	o Access and emergency escape routes
o Initial and final load positions and how it will get there	o Experience, competence and training of personnel
o Ground and underground considerations	o Number of personnel required for task
o Lifting over live equipment	o Pre-Use Inspection of equipment by operator
o Number and duration of lift(s)	o Visibility of the load
Task Details (Step By Step)	
Method(s) Of Communication To Be Used Radio o Verbal o Hand Signals o	
Steps Taken To Eliminate Danger To Personnel Involved and Others (including barriers where appropriate):	
De-brief and learning points:	
Prepared By/Name: Signature: Date:	
Reviewed By/Name: Signature: Date:	
Approved By/Name: Signature: Date:	

Annex (HSW22A-9)

PART A. INCIDENT – NOTIFICATION

This section is to be completed by the relevant Senior Manager and forwarded to the Local Market CEO, Local Market Executive Team and Local Market H&S Manager within 24-48 hrs. of the incident.

Incident Classification

Nature of Incident

- ☐ Major incident – fatality
- ☐ Major incident – serious injury
- ☐ Near miss
- ☐ HiPo (High Potential Incident)

Country + region of incident
Specific location of incident
Date of incident — Time of incident
Date form completed
Date investigation due
Reported by + contact number
Investigation lead + contact number
VF Manager responsible for area/project

Business area of incident location

- ☐ Customer Operations
- ☐ Legal & Governance
- ☐ Retail
- ☐ Human Resources
- ☐ Finance
- ☐ Marketing
- ☐ Technology
- ☐ Property
- ☐ Other: Please specify

Particulars

* For more injured persons please complete and attach the 'Incident Notification Form Continuation Sheet'

Details of injured person(s)

Name of injured person
Age/D.O.B — ☐ Male ☐ Female
Employing company
Relationship to Vodafone — ☐ Employee ☐ Contractor ☐ Public ☐ Property/Structure

Role/job

- ☐ Civil Worker
- ☐ Electrician
- ☐ Member of Public
- ☐ Engineer
- ☐ Executive
- ☐ Security Guard / Caretaker
- ☐ Climber / Rigger
- ☐ Driver
- ☐ Sales Representative
- ☐ Other: Please specify

Nature of incident / injury

Contact type

- ☐ Caught in / between
- ☐ Caught on
- ☐ Extreme heat / cold
- ☐ Fall on same level
- ☐ Fall from different level
- ☐ Struck against
- ☐ Struck by
- ☐ Overstress, over exertion, overload

Injury type

- ☐ Adverse reaction
- ☐ Bruise / contusion
- ☐ Burn / scold
- ☐ Cut / abrasion
- ☐ Dislocation
- ☐ Fracture
- ☐ Sprain / strain

Part of body

- ☐ Arm
- ☐ Leg
- ☐ Back
- ☐ Torso
- ☐ Hand
- ☐ Foot
- ☐ Head
- ☐ Neck
- ☐ Eye

Description of the incident (be clear and factual)

* Please include a sketch of the incident scene at the end of this report

Immediate action(s) taken

Please insert photos or files related to the incident

PART B. INCIDENT INVESTIGATION

This section is to be completed by the relevant Senior Manager and forwarded to the Local Market CEO, Local Market Executive Team, and Local Market H&S Manager within 20 days of the incident.

Root cause analysis – Part I Immediate Causes

Substandard Acts / Practices (select all that apply)

- ☐ Failure to secure
- ☐ Failure to warn
- ☐ Making safety devices inoperable
- ☐ Improper loading
- ☐ Removing safety devices
- ☐ Operating at improper speed
- ☐ Horse play
- ☐ Failure to use PPE properly
- ☐ Operating equipment without authority
- ☐ Improper placement
- ☐ Using defective equipment
- ☐ Servicing equipment in operation
- ☐ Improper lifting
- ☐ Improper position for task
- ☐ Using equipment improperly
- ☐ Operating under the influence of drugs / alcohol

Substandard Conditions (select all that apply)

- ☐ Noise exposure
- ☐ Fire and explosion hazards
- ☐ Defective tools, equipment or material
- ☐ Poor housekeeping
- ☐ Congestion or restricted action
- ☐ Operating equipment without authority
- ☐ Radiation exposure
- ☐ Inadequate guards / barriers
- ☐ Inadequate or improper protective equipment
- ☐ Inadequate ventilation
- ☐ Inadequate warning system
- ☐ Inadequate access or illumination
- ☐ Hazardous environmental conditions: gas, vapour, dust, fumes

Root cause analysis – Part II Basic Causes

Personal factors

- ☐ Improper motivation
- ☐ Inadequate capability – physical / physiological
- ☐ Inadequate capability – mental / psychological
- ☐ Lack of knowledge
- ☐ Lack of skill
- ☐ Stress – physical / physiological
- ☐ Stress – mental / psychological

Job/system factors

- ☐ Abuse or misuse
- ☐ Inadequate engineering
- ☐ Inadequate leadership or supervision
- ☐ Inadequate maintenance
- ☐ Inadequate purchasing
- ☐ Inadequate tools, equipment, materials
- ☐ Inadequate work standards

Supporting Documentation Provided

- ☐ Design drawings, equipment specifications
- ☐ Equipment / workplace inspection records
- ☐ External investigation records
- ☐ Meeting minutes
- ☐ Photos
- ☐ Risk assessments / method statements
- ☐ Sketch / diagrams of scene
- ☐ Witness statements
- ☐ Previous incident reports
- ☐ Other: Please specify

Summary of findings

Action plan

Action:	
Date for completion:	Responsibility:

Action:	
Date for completion:	Responsibility:

Action:	
Date for completion:	Responsibility:

Days lost information

Person 1			Person 3		
Returned to work:	☐ Yes	☐ No	Returned to work:	☐ Yes	☐ No
Number of days lost:			Number of days lost:		

Person 2			Person 4		
Returned to work:	☐ Yes	☐ No	Returned to work:	☐ Yes	☐ No
Number of days lost:			Number of days lost:		

Loss estimation (please state whether in local currency or € equivalent)	
Type (select ALL that are appropriate)	Amount € / local currency
☐ Business disruption	
☐ Equipment	
☐ Investigation costs	
☐ Property	
☐ Statutory fine / penalty	
☐ Other	
Total (estimated):	

Actual severity:	☐ Minor	☐ Major	☐ None
Potential severity:	☐ Minor	☐ Major	☐ None
Probable frequency of incident recurring:	☐ High	☐ Medium	☐ Low