Vodafone Egypt SHW Supplier Policy Detailed Requirements

SHW22 – Local Agreements SHW Supplier's Requirements

Policy Champion:	Day-to-day contact:	Version/Revision:	Date:
Osama Radwan	Mohamed Hegazy	1.9 "Version 1 – Revision 9"	12 June 2025

This Supplier Policy Detailed Requirements addresses what is expected to comply with from the Suppliers' side, whenever they provide Products and/or Services to Vodafone Egypt.

The objective of this Supplier Policy Detailed Requirements is to set out the Supplier's obligations in relation to safety, health, and well-being (SHW).

The purpose of this policy is to protect safety and health, and to promote the well-being of our customers, employees, partners, which includes our suppliers and the communities in which we operate. Vodafone has a simple global commitment: no one gets hurt.

Vodafone Egypt: this annexe applies to all agreements & contracts with Vodafone operating companies in Egypt, including subsidiaries and Joint Ventures (employees, contractors, suppliers) with an interest of 51% or more, or management control. This includes Vodafone Egypt Telecommunication S.A.E., Vodafone Data, and Vodafone Trade.

Services: Unless otherwise stated, the annexe applies to all services.

People: This Annexe applies to all employees and contractors.

Suppliers: This Policy applies to all Suppliers "relevant entity engaged amongst other activities, including but not limited to the development, manufacture and supply of deliverables" to Vodafone Egypt, in addition to the supplier policies that are located here.

Compliance levels are monitored and reviewed by appropriate governance bodies. Any breach will be treated as a serious disciplinary offence and may be subject to disciplinary action.

Contents

Scope 2
Introduction 2
Definitions and interpretation 2
Part A - Detailed General Requirements 5
Part B – Specific Requirements for High-Risk Activities and Product Supply 10
Part C – Incident Reporting & Investigation Process 32
Part D – Consequences of Non-compliance 35
Annexes 37

Scope

Applies to all supplier agreements/contracts with Vodafone operating companies in Egypt.

Introduction

The phrase "Supplier" or "Supplier personnel" in this Supplier Policy shall, where relevant, also include all officers, employees, contractors, subcontractors and agents of Supplier and other persons under its influence or control. Supplier shall procure compliance by such persons.

This Supplier Policy Detailed Requirements sets out the Supplier's additional local obligations in relation to safety, health, and wellbeing (SHW) and is split into four parts:

Part A: Detailed general requirements;

Part B: Detailed specific requirements for High-Risk Activities and Product supply;

Part C: Detailed incident reporting requirements; and

Part D: Detailed consequences of non-compliance

Definitions and interpretation

The following words and expressions have the following meanings in this Supplier Policy Detailed Requirements:

SHW	Safety, Health, and Wellbeing.
Products	Any hardware or software product (including any modifications, spare parts, components, drawings, tools and associated documents).
Services	All categories of provided services, including but not limited to support and maintenance services, managed services, professional services, catering, hosting events, etc.
Supplier	The relevant entity engaged amongst other activities, including but not limited to the development, manufacture and supply of deliverables to Vodafone Egypt.
Vodafone Egypt	Vodafone operating companies in Egypt, including subsidiaries and Joint Ventures (employees, contractors, suppliers) with an interest of 51% or more, or management control.
Company's Vehicles	Any vehicles owned/rented that are engaged in any Vodafone-related task.
Absolute Rules	Vodafone's main rules that address high-risk control measures, which require observation at all times: (SHW AR) • always wearing seat belts when travelling in or operating vehicles; • always using suitable PPE, a safety harness and fall protection equipment when working at height; • never carrying out electrical work on electrical equipment, circuits and gear without appropriate qualifications and compliance with regulations; • never working under the influence of substances (alcohol or drugs) which are illegal or in excess of legal levels, or where this impairs the ability to perform tasks; • never using a handheld phone whilst driving and only making calls by pulling over or using hands-free devices, when it is safe to do so; • always drive safely and legally; always obey the speed limit; • never undertake any street or underground work activities unless competent to do so; and • when working in the proximity of power, we always maintain the required safe distance and use the correct insulated equipment.
Work approval	It is a method of reviewing whether adequate planning and risk assessment of high-risk activities (including identification of reasonable controls) have been completed prior to the activity taking place and before access for the work to be undertaken is authorised.

Approver	A competent authorised person who has responsibility for ensuring requirements for high-risk activities are met prior to approving work to commence.
Incident	An occurrence arising out of, or during, work that could or does result in injury and ill health.
Work-Related Incident	An injury or illness is work-related if an incident or exposure in the work environment either caused or contributed to the resulting condition or significantly aggravated a pre-existing injury or illness.
Lost Time Injury	A work-related injury or illness involves one or more days away from work.
Restricted Work Case	When an injury or illness involves restricted work or job transfer, but does not involve death or days away from work.
Near Miss	Any work-related incident where no injury or ill health occurs but has the potential to do so.
Observations	Unsafe acts are behaviours that can **potentially** lead to damage to property, personal injury, or death. Unsafe conditions are circumstances, environment, or state of equipment which **could** lead to an incident occurring.
High Risk Activities	Any activities involving the following: • Overhead work/ lifting operations; • ground/ civil/ construction work; • product/ equipment safety; • radio frequency; • electrical work; • working at height; • driving (where it is an integral part of the job); • field installation activities relating to hardware or infrastructure; • network build, operate and transfer scenarios (or component activities); • manufacturing and distribution processes involving material safety and health risks; • catering services; • lone working; • managed Services; • hot work activities; • confined space activities; • warehouse operations; and • such other scenarios as Vodafone may identify (acting reasonably and in agreement with the supplier).
EN Standards	European Standards.
ICNIRP	International Commission on Non-Ionizing Radiation Protection.
Anchor	Fixed inspected & certified object to which ropes or equipment are attached for lifting or for lifelines.
Competent person	Someone who has a sufficient combination of knowledge, training, and experience. The level of competency required will depend on the complexity of the work that needs to be performed.
Lifting plan	A step-by-step plan on how the lift will be carried out and a layout of the gear required for the lift.
Non–conformity	Failure to conform to accepted standards, rules or laws.
Safe Working Load (SWL)	The maximum load the lifting equipment is certified to withstand under normal use.
Working Load Limit (WLL)	The maximum load that lifting equipment is certified to withstand under normal use and in a given configuration, WLL is only applied to lifting equipment and not rope access and fall arrest equipment.
Extra Low Voltage (ELV)	Voltage less than 50V AC or ripple-free 120V DC.
Low Voltage (LV)	Voltage from 50V to 1000V AC or 120 to 1500V DC.
Medium Voltage	Voltage 1000V to 35kV AC or greater than 1500V DC.

Portable appliance	Any portable appliance is any piece of electrical equipment that can easily be moved and is connected by plug or socket.
Electrical work	Any work that involves contact with electrical components, switch gear, cables or other components. This includes all installation, maintenance, upgrade and decommissioning activities.
Live	Electrically charged by being connected to a voltage electricity supply or having a charge retained by capacitance.
Exposed	Capable of being inadvertently touched or approached nearer than a safe distance by a person. It is applied to parts not suitably guarded, isolated, or insulated.
Live electrical work	Any work will involve persons being exposed to live parts or equipment.
RCD & ELCB	Residual Current Device and Earth Leakage Circuit Breaker are devices used to protect the user of electrical equipment in the event of a fault.
Managed Services Provider (MSP)	A professional supplier that Vodafone outsources day-to-day management responsibilities and/or functions of a defined set of services to.
PPE	Personal Protective Equipment.
QR	Quick Reporting.
Red Card	An incident type that is a major incident resulting in actual loss (i.e. fatality, disabling injury, property damage or business interruption).
Yellow Card	A breach of the absolute rules or an incident type that results in or could have had the potential to result in a major incident.
GRI 403	GRI (Global Reporting Initiative) is the independent, international organisation that helps businesses and other organisations take responsibility for their impacts by providing them with a global common language to communicate those impacts. GRI 403 contains disclosures for organisations to report information about their occupational health and safety-related impacts and how they manage these impacts.
Inspection	On-site examinations of work areas, equipment, and processes to identify hazards and potential risks.
Audit	Systematic, independent and documented *process* for evaluating the organisation's SHW management system by obtaining audit evidence and evaluating it objectively to determine the extent to which the audit criteria are fulfilled.
Hot Work	Hot work is any operation that results in the emission of concentrated sources of heat, such as sparks or molten metal. Examples include welding, brazing, cutting, grinding, paint stripping and torch-applied roofing.
Workers	All persons on any given site where work is conducted under its direct control, and includes any persons it procures directly or indirectly through sub-contracting for the purposes of fulfilling its obligation in connection with this Schedule.
Supervisor	Person appointed and responsible to oversee the safety and health compliance, and requires necessary industry experience, training and may require specific technical knowledge and management skills to ensure safety through educating, sponsoring, coaching, mentoring, advising and directing any onsite activities throughout the project/operation. This person shall monitor 100% of the activities and is not authorised to perform any other activity, and he shall not leave the site during the activities under any circumstances.

Part A - Detailed General Requirements

1. General

Suppliers shall:

1.1. make proper provision for SHW for its employees, visitors, contractors and any subcontractors working on its behalf;

1.2. comply with all Applicable Laws, relevant standards and regulations related to SHW and Vodafone Absolute Rules;

1.3. obtain any necessary permits, licenses or insurances needed;

1.4. obtain certification to ISO45001 for relevant High Risk Activities from a recognised external certification body related to the specific country, market, region or project (or alternative equivalent management system approved for this purpose by Vodafone in writing);

1.5. provide appropriate evidence of the competence of Supplier and Supplier personnel when requested by Vodafone;

1.6. ensure that Supplier personnel have access to appropriate levels of expert SHW advice;

1.7. have a competent person appointed with SHW responsibility for the operation of and compliance with the SHW management system;

1.8. ensure roles and responsibilities with respect to the delivery of safety, health and wellbeing are clearly defined throughout the Supplier organisation;

1.9. ensure the equipment/tools are designed, manufactured, installed, constructed, tested, calibrated, maintained, inspected and certified in accordance with the local legislations and industry standard, have a certificate of conformity from an accredited body to the relevant EN Standard, manufacturer's instructions are followed, and evidence/records can be demonstrated;

1.10. continually monitor and review SHW performance and compliance with this Vodafone Supplier Policy through programs of inspections, testing, and audits;

1.11. regularly submit SHW performance data to Vodafone, report near misses & observations through QR code or any equivalent method, attend meetings, and participate in audits as reasonably required by Vodafone;

1.12. ensure that appropriate systems and processes are in place (and adequately resourced) to identify and address SHW risks associated with Vodafone;

1.13. have in place a mechanism to ensure that the supplier and supplier personnel comply with Vodafone supplier policy and SHW requirements communicated from time to time;

1.14. have in place a mechanism to ensure that the management of risks associated with specific hazards that are associated with its obligations under the relevant Vodafone agreements;

1.15. ensure premises have clear and visible evacuation routes and well-identified emergency assembly points;

1.16. ensure that all subcontractors engaged in high-risk activities are limited to only one tier;

1.17. integrate worker well-being & psychological safety into their SHW management systems/plans. This includes identifying and addressing potential psychosocial risks such as high job demands, low job control, and unclear roles, Suppliers should implement strategies (preventive measures and promote a positive working environment) that support workers' wellbeing, including:

1.17.1. prevent exposure to psychosocial risks (Psychosocial risk management assessment & preventive measures to cover at least Job/task design, Workload, schedule, Job control, Environment and equipment, culture, Interpersonal relationships at work);

1.17.2. protect & promote mental health and well-being at work (Strengthen awareness, skills and opportunities for recognising and acting early on mental health issues to cover at least assessing and advising on the need for leave from work, modifications to work and, where appropriate, by providing psychosocial interventions); and

1.17.3. support employment initiatives to participate in and thrive at work (reasonable adaptation of working environments to match the capacities/needs/preferences of the worker, Return-to-work programs, and supported initiatives).

1.18. have mechanisms in place to ensure compliance with the following requirements for Lone working activities:

1.18.1. lone workers can, although not exclusively, be categorised as follows:

1.18.1.1. work alone outside normal office hours where there are no regular security checks on premises;

1.18.1.2. who handles cash (delivery staff, retail workers, etc.); and

1.18.1.3. who visits remote locations?

1.18.2. each undertaking is to be determined based on the need for lone working assessments, which shall include:

1.18.2.1. a safe means of travel to and from the workplace/ premises, including when working out of hours (e.g. the nature of the tasks and the length of time a worker will be alone); and

1.18.2.2. restricted access, parking lots, security features and state of the building, etc. It should be taken into consideration. In all cases, adequate first aid equipment and on-call assistance, as well as a sound means of communication, must be in place.

1.19. ensure that all Vodafone requirements, absolute rules, risks, and controls are clearly communicated to all suppliers, suppliers' personnel, subcontractors, field operatives, and to anyone likely to work/be present during the work on-site. Evidence of communication shall be retained and made available;

1.20. all high-risk activities and/or activities taking place in a high-risk environment shall have documented method statements, risk assessment and arrangements in the event of emergency specific to the activity and location, and shall be reviewed to consider residual risks and additional control measures when needed, approved by a competent person prior to work commencement, communicated to anyone likely to work/be present on-site, and that access is controlled for only authorised persons;

1.21. the effective implementation of Vodafone requirements shall be verified, compliance shall be demonstrated, and records shall be made available for Vodafone reviews;

1.22. the emergency response plan shall be in place specific to the activity and location, including appointment of a competent person to respond to potential emergency scenarios as applicable (e.g. First Aid & CPR, Firefighting, Evacuation and rescue techniques, emergency shutdown, etc.). The appointed person shall be physically capable of carrying out their duties;

1.23. night activities, including driving, shall not be undertaken unless deemed necessary with prior approval from the Vodafone Business Related Manager and the SHW Team, applicable controls to reduce the risk and monitoring the activity shall be in place. Lone work is prohibited;

1.24. ensure that all personnel engaged in high-risk activities for Vodafone Egypt have a physical or electronic ID card system that identifies, as a minimum person's identity with a coloured photograph, role and function, safety certifications, and social insurance number;

1.25. supplier shall has a system for PPE selection, inspection, and record-keeping that meets these requirements:

1.25.1. risk assessment, method, and job hazard analysis shall be used to identify whether any PPE is required for the task being undertaken, and the minimum standard of PPE on construction sites is hard hats, safety boots;

1.25.2. all PPE should be checked prior to use to ensure it is still in good working order, maintained and clean;

1.25.3. recommended PPE Matrix for activities to be provided by the supplier;

1.25.4. PPE should be replaced based on the manufacturer's requirements and based on its condition;

1.25.5. ensure that regular PPE inspection is conducted by a competent person, documented and recorded as follows:

1.25.5.1. either quarterly by a competent person certified from a Vodafone-approved training provider in the PPE & Gear inspection, and once annually by an approved external inspector;

1.25.5.2. or a semi-annual inspection for all PPE & Gears by an approved external inspector

1.25.6. all PPE used shall comply with the EN Standards and be purchased from an approved supplier (Annexe SHW22-1); and

1.25.7. ensure that all personnel performing a Vodafone task are following the appropriate measures and using appropriate PPEs, tools, measuring instruments, equipment and products.

1.26. suppliers' risk assessment shall comply with the following requirements (but not limited to):

1.26.1. risk Assessment shall be completed, filled out, and signed by a competent person;

1.26.2. the template must include the assessment date, site ID/name/type, contractor's name, assessor's name and signature;

1.26.3. the risk assessment shall include a clear description of the scope of work and any potential hazards related to the work environment, its surroundings, and the nature of the activities, who might be harmed and how, the existing control measures following the hierarchy of controls, and detailed to the level of tasks and job roles;

1.26.4. the risk assessment shall undergo additional re-evaluation onsite, and any residual risks/additional control measures shall be identified and recorded; and

1.26.5. the risk assessment evaluation shall follow the risk assessment methodology & matrix below:

Rating	Severity (S)	Likelihood (L)
5	Fatality(ies)	Almost certain (common occurrence)
4	"Long-term, life-altering injury or illness resulting in permanent total or partial disability. Examples: amputation w/loss of bone, severe disfigurement, paralysis, loss of limb/organ/vision/hearing"	Likely (known to occur)
3	Injury or illness requiring medical treatment or resulting in temporary disability or loss of function. Examples: deep laceration, object embedded in eye, bone fracture, concussion, dislocation, injury requiring surgery.	Possible (could occur)
2	Injury or illness requiring first aid treatment only. Examples: minor cuts, bruises, sprains, strains, abrasions, irritation, inflammation, object in eye removed by flushing.	Unlikely (possible but not likely to occur)
1	No impact	Rare (almost impossible)

Risk Assessment Matrix		(S)/(L)	1	2	3	4	5
Risk Rating	Action	1	1	2	3	4	5
1:2	**LOW RISK (L)** As low as reasonably practicable (ALARP): May be acceptable. However, attention is required & frequent review	2	2	4	6	8	10
3:6	**ADEQUATELY CONTROLLED RISK (A)** Review task to see if risk can be reduced further.	3	3	6	9	12	15
8:12	**MODERATELY CONTROLLED RISK (M)** Further Risk Reduction Measures should be considered.	4	4	8	12	16	20
15:25	**HIGH RISK (H)** Unacceptable, stop the work, Immediate action to reduce risk by re-assessing & applying the controls.	5	5	10	15	20	25

2. Control of Sub-contractors (tiers are limited only to one tier)

Supplier shall have and maintain robust mechanisms to manage subcontractors, including:

2.1. systems and processes for assessing the SHW capability of sub-contractors;

2.2. communication of Vodafone's SHW requirements and contractual arrangements to flow down Vodafone's requirements to sub-contractors (with appropriate contractual performance management mechanisms);

2.3. systems for regular monitoring and review of SHW performance; and

2.4. prohibitions on further sub-contracting of any High-Risk Activities by Supplier's sub-contractor without the express permission of Vodafone, and upon Vodafone's request, Supplier shall report all parties undertaking High Risk Activity for Supplier.

3. Training and Competence

Supplier shall have and maintain a robust SHW training regime for Supplier personnel to ensure that Supplier and Supplier personnel are trained to deliver their assigned tasks in a safe manner, including:

3.1. an appropriate training and awareness program for all tasks (in an appropriate language and delivered via an appropriate means for the target audience), including but not limited to:

- 3.1.1. Induction session to be conducted prior to assuming role/job responsibilities;
- 3.1.2. external training by approved providers according to Vodafone requirements and the nature of the job;
- 3.1.3. refreshment training sessions for all training courses, whether internal or external;
- 3.1.4. internal trainings that cover hazard communications, rules, risk & controls associated with the job/roles & responsibilities;
- 3.1.5. seasonal training based on events calendar (Ramadan, Heat stress, etc.);
- 3.1.6. training sessions following any incident to share the lessons learned; and
- 3.1.7. training sessions for communicating any new alerts.

3.2. mechanisms to ensure that High Risk Activities are only completed by trained, competent and qualified Supplier personnel; all personnel must be competent and appropriately trained for the assigned responsibility, which shall consider the minimum qualifications as follows:

- 3.2.1. SHW Key contact/manager shall be competent and to be assessed based on the scope and size of the project/operation will be undertaken. This person must be interviewed and accepted by the Vodafone SHW team. A transition plan shall be submitted in case of any change;
- 3.2.2. SHW field officers shall be trained on risk assessment, high-risk activities, emergency response, and rescue techniques;
- 3.2.3. the activities' supervisors must have an approved risk assessment training;
- 3.2.4. field operatives shall be appropriately trained for his/her assigned responsibility; and
- 3.2.5. each activity must have appointed person(s) for emergency response with the relevant approved training(s).

3.3. external training shall be provided from Vodafone Egypt's approved training providers listed in (Annexe SHW22-1), considering that other specified risks' external training shall be approved by the Vodafone SHW team; and the following applies:

- 3.3.1. mandatory pre/post examination with a minimum passing score of 80% and a maximum of 2 times failure, where a buffer period of two weeks is requested prior to re-examination;
- 3.3.2. participants who fail twice in the examination shall not be enrolled in the same work scope/profile; otherwise, the Supplier's management shall carry out job rotation that acquires lower risk; and
- 3.3.3. a training certificate shall be obtained by passing the post examination, which is valid for a maximum of two (2) years for all trainings or else mentioned by the training provider (whichever occurs earlier);

3.4. maintenance of appropriate training records available for audit by Vodafone at any time.

4. Performance Monitoring, Reporting & KPIs

Suppliers shall have a complete monitoring and reporting program that covers the details of monitoring, auditing, inspection, certification, and reporting processes that you have in place to ensure that the required standards are achieved, including:

4.1. supervision – All high-risk activities must have the appropriate level of competent supervision on the ground;

4.2. SHW inspections and audit program. The minimum inspection target is 70% full physical inspection on site to cover all high-risk activities. This percentage could be increased based on the project assessment;

4.3. management tours including senior leaders, project managers & SHW teams;

4.4. measurements, testing, calibration and thorough examination;

4.5. compliance reviews;

4.6. conduct Self-Assessment against the ISO45001 requirements at least once annually; and

4.7. where Supplier is undertaking any High Risk Activities, Supplier shall report on the following metrics on request from Vodafone **Note1** both in relation to their entire operations and specifically for Vodafone related activities covering the scope of all employees and for all workers who are not employees but whose work and/or workplace is controlled by the Supplier:

4.7.1. number and rate of fatalities as a result of work-related injury;
4.7.2. number and rate of work-related injuries (excluding fatalities); including categorisation of the main types of injury and severity;
4.7.3. number and rate of recordable work-related injuries;
4.7.4. number of lost time and restricted work cases;
4.7.5. number of hours worked;
4.7.6. main types of work-related injury;
4.7.7. number of breaches of Absolute rules;
4.7.8. number of site inspections/audits undertaken and percentage of actions successfully completed;
4.7.9. number of statutory interventions;
4.7.10. management team visits (quarterly);
4.7.11. number of Quick Reports (monthly);
4.7.12. number of internal trainings;
4.7.13. number of total training manhours with a clear breakdown by internal, external,…etc.;
4.7.14. number of total safe man-hours worked & number of safe miles driven;
4.7.15. number of sites worked, number of high-risk activities, total activities, inspected physically VS inspected remotely;
4.7.16. number of performed emergency drills/tests; and
4.7.17. such other metrics as Vodafone may reasonably request.

Note 1: defined on the basis of recommendations from GRI Standard 403 on Occupational Health & Safety (publicly available)

Part B – Specific Requirements for High-Risk Activities and Product Supply

5. SHW Plan for High-Risk Activities

5.1. Supplier shall have and maintain an SHW plan for all High Risk Activities before commencing work (where carrying out such High Risk Activities), setting out measures to manage the accompanying risks. Supplier shall manage the risks in accordance with the SHW plan. Supplier shall provide a copy of the SHW plan to Vodafone as soon as it is ready and before commencing any high-risk activity, with all relevant evidence of compliance with these standard requirements;

5.2. the SHW plan must include details of:

5.2.1. **Scope of the work that is to be undertaken**

- 5.2.1.1. details of service scope (what will be included or not included);
- 5.2.1.2. nature of the activities will be performed in the scope;
- 5.2.1.3. high-risk activities involved in the scope will be provided;
- 5.2.1.4. working pattern (shifts/working hours); and
- 5.2.1.5. site plan including geography of the location and venue; topography, including highlights of the Off-site hazards within the vicinity, e.g. Industrial plant, construction sites, warehouses.

5.2.2. **Key contacts and responsibilities for safety, health and wellbeing delivery**

- 5.2.2.1. the Organisation Chart include reporting lines of the SHW;
- 5.2.2.2. key contacts information;
- 5.2.2.3. SHW responsibilities;
- 5.2.2.4. SHW team qualifications & experience; and
- 5.2.2.5. access to SHW experts/consultants, internal or external.

5.2.3. **Risk assessments, method statements and safe systems of work that detail how the tasks will be completed safely. These must be specific to the project/contract and consider the different environments that will be encountered**

- 5.2.3.1. risk assessments;
- 5.2.3.2. method statement & site rules;
- 5.2.3.3. safe system of work/procedures;
- 5.2.3.4. specified hazards; and
- 5.2.3.5. access & work approval for high-risk activities.

5.2.4. **Resources' Management:**

- 5.2.4.1. resources onboarding process;
- 5.2.4.2. competency & training matrix statement;
- 5.2.4.3. medical fitness matrix statement;
- 5.2.4.4. competency & Training program includes internal and external training and regular awareness/refreshment program;
- 5.2.4.5. PPE matrix; and
- 5.2.4.6. resources Plan, Resource Compliance Tracking sheet.

5.2.5. **Details of the monitoring, auditing, inspection, certification and reporting processes that you have in place to ensure that the required standards are achieved**

- 5.2.5.1. inspection & monitoring program (percentage/frequency of on-site inspection/monitoring on high-risk activities/operations), and layers of verification of the quality of inspection;
- 5.2.5.2. audit Program (Internal/External);
- 5.2.5.3. testing, measurement, calibration & certification;
- 5.2.5.4. frequency of reporting and templates of reporting;
- 5.2.5.5. senior management reviews, engagement and tours;
- 5.2.5.6. leading and lagging indicators, and KPIs; and
- 5.2.5.7. output from monitoring and audits, including non-conformities, percentage of completed actions, incident reporting, consequence management and rewarding.

5.2.6. **Details of the supplier's incident reporting and investigation procedures**

- 5.2.6.1. incident reporting & investigation procedure;

5.2.6.2. service level agreement, Immediate reporting, Official Notification 24hrs, Full Investigation; and

5.2.6.3. commitment to Vodafone rights and consequence management.

5.2.7. **Details on how subcontractors will be selected and managed, including communication of client requirements. Further details on specific requirements in this area are included below:**

5.2.7.1. identification of the need to use subcontractors on this project/contract;

5.2.7.2. selection and approval/rejection of SHW criteria of the suppliers;

5.2.7.3. supplier SHW clauses in contracts with suppliers that align with VF requirements, including mechanisms for penalty and reward;

5.2.7.4. the supplier process is in place to monitor the SHW performance of subcontractors and reviews this on a regular basis; and

5.2.7.5. identification of the need to use casual workers, if yes, what type of activities/work will be delivered by casual workers and what are the SHW controls accordingly.

5.2.8. **Details of the high-risk products, plant/ equipment and substances will be selected, used and controlled throughout the delivery of the work**

5.2.8.1. safety Data Sheet for the high-risk products, plant/ equipment and substances;

5.2.8.2. selection criteria /method of the high-risk products, plant/ equipment and substances; and

5.2.8.3. method statement of how the risk products, plant/ equipment and substances will be used & controlled.

5.2.9. **Details on how applicable local legislation, Vodafone Absolute rules, and the relevant SHW Standards will be communicated and adhered to**

5.2.9.1. compliance status in the register of the applicable local legislation;

5.2.9.2. compliance status in the register of the relevant SHW Standards;

5.2.9.3. clear and auditable process for communication of risk and controls to field operatives & Sub- subcontractors; and

5.2.9.4. absolute rules are included in the plan and communicated to all layers, including subcontractor personnel.

5.2.10. **Details of the Supplier's emergency processes**

5.2.10.1. fire, explosions, terrorism or structural failure;

5.2.10.2. power & Safety Equipment failure;

5.2.10.3. first Aid & Ambulance presence;

5.2.10.4. weather, e.g. excessive heat/cold/rain/wind;

5.2.10.5. evacuation Routes & Emergency Exits;

5.2.10.6. firefighting equipment and consideration of requirements for inaccessible areas;

5.2.10.7. rescue from working at heights; and

5.2.10.8. specified Hazard Rescue (Confined spaces).

5.2.11. **Supporting documents**

5.2.11.1. ISO 45001 valid certification and S&H management system self-assessment; and

5.2.11.2. recent S&H history (Incidents rates & frequencies for the last 3 years).

5.3. **Catering services'** suppliers shall have and maintain an S&H plan before commencing work, which must include details mentioned in "5.2" and details of the food safety programme that covers:

5.3.1. identification of where and how each hazard can be controlled; description of how these controls, how controls are to be monitored; the corrective action required if control conditions have not been met; and records that must be in place;

5.3.2. food cycle risk analysis and control points that include (Purchase, delivery, storage, preparation & handling, cold holding/display, defrosting, cooking, cooling, freezing, reheating, hot holding/display, transport & distribution);

5.3.3. biological, physical, chemical contamination, allergies, hygiene and other requirements (i.e. cleaning and disinfection, pest control, waste control, maintenance, personal hygiene, training, supervision and monitoring);

5.3.4. events' suppliers shall follow applicable control measures stated in "5.4";

5.3.5. SHW 14 VFE Food Safety and Workplace Hygiene Policy requirements shall be applied; and

5.3.6. all the controls shall be in accordance with Vodafone and local/international relevant standards.

5.4. **Outdoor Events' or branded vehicles/road shows suppliers** shall have and maintain a safe event plan before commencing work, which must include details of:

5.4.1. engineering consultant reports (civil, electric, mechanical, fire, etc.) from Vodafone approved Engineering Consultants' list;
5.4.2. the type of event, nature of performers, time of day and duration;
5.4.3. using sufficient personal protective equipment while installing (e.g. Booths, Backdrops, Wall branding, Danglers, etc);
5.4.4. audience profile including age, previous or expected behaviour, special needs, etc.;
5.4.5. existence or absence of seating;
5.4.6. site plan including geography of the location and venue; topography;
5.4.7. sound temporary structures to withstand the expected loads, e.g. Canopies, tents, booths, stand stages, movable ladders etc.;
5.4.8. detailed Risk assessments including:
5.4.8.1. installations and clearing up (e.g. Backdrops, wall branding, electrical, etc.);
5.4.8.2. off-site hazards within the vicinity, e.g. Industrial plant, construction sites, warehouses;
5.4.8.3. crowd control;
5.4.8.4. catering & steward;
5.4.8.5. on-site and off-site traffic;
5.4.8.6. electrical installation, temporary wiring, and power supplies control; and
5.4.8.7. working in dark/low visibility areas.
5.4.9. emergency & Evacuation Plans;
5.4.9.1. fire, explosions, terrorism or structural failure;
5.4.9.2. power & Safety Equipment failure;
5.4.9.3. first Aid & Ambulance presence;
5.4.9.4. weather, e.g. excessive heat/cold/rain/wind;
5.4.9.5. evacuation Routes & Emergency Exits; and
5.4.9.6. firefighting equipment and consideration of requirements for inaccessible areas.

5.5. **Managed Service Provider:** shall have and maintain a safe operational plan as a part of the SHW plan before commencing work, which shall include:

5.5.1. detailed scope of the operation including location, nature of operation, working pattern, premises details (e.g. layout, area, number of floors, accessibility, geography of the location and venue; topography, etc);
5.5.2. risk assessments, method statements and safe systems of work that detail how the operation will be managed safely through different stages (i.e. construction, site preparation, dismantling, commissioning, and operation), considering:
5.5.2.1. off-site hazards within the vicinity, e.g. Industrial plant, construction sites, warehouses;
5.5.2.2. access requirements for people with disability and/or mobility needs;
5.5.2.3. factors that affect the workplace environment include (Welfare facilities & Hygiene -i.e. rest rooms, catering, washing rooms, pest control, first aid provision, ergonomics, lighting, ventilation, and clean water supplies, etc.);
5.5.2.4. property and facility management include a corrective and preventive maintenance programme by competent vendors, with clearly communicated processes for reporting faults and controlling and authorising work;
5.5.2.5. safe storage, manual handling, loading and offloading of material/goods; and
5.5.2.6. on-site and off-site Traffic, considering proper traffic arrangements and segregation/signage for the protection of pedestrians and visitors.
5.5.3. emergency & contingency plans (fire/explosion, terrorism; structural failure; collapse; disorder; lighting or power failure; safety equipment failure, e.g. excessive heat/cold/rain); and

5.5.4. fire safety and emergency procedures to include: (training, evacuation plans, emergency exits, firefighting equipment and consideration of requirements for inaccessible areas, Fire detection/prevention equipment and testing requirements) in accordance with national statutory requirements and consultation with the Local Fire Authority.

6. Supervision

6.1. All high-risk activities must be supervised;

6.2. supplier shall ensure the roles and responsibilities of the supervisor are clearly defined and communicated;

6.3. a supervisor is an individual appointed to oversee and ensure the Safety, Health & Wellbeing of all workers and any other persons in close proximity to work activities. This role requires a combination of knowledge, training, experience, and authority to effectively manage and mitigate risks associated with high-risk activities. The responsibilities and qualifications of a Supervisor include:

6.3.1. **appointment and training**

6.3.1.1. the Supervisor must be formally appointed through a robust assessment process that evaluates their skills, attitude, authority, and competence; and

6.3.1.2. they must undergo appropriate training to understand the tasks at hand and maintain up-to-date knowledge of SHW regulations and best practices.

6.3.2. **authority and control**

6.3.2.1. the Supervisor must have the authority to control work activities and, if necessary, stop work to prevent unsafe conditions; and

6.3.2.2. they must be empowered to enforce compliance with SHW policies and procedures and ensure that all safety measures are implemented correctly.

6.3.3. **risk management and hazard control**

6.3.3.1. the Supervisor is responsible for assessing various safety hazards and determining the likelihood of serious incidents occurring; and

6.3.3.2. they must conduct regular inspections to identify and rectify hazards. If a hazard cannot be fixed, the Supervisor must escalate the issue to higher management.

6.3.4. **communication and leadership**

6.3.4.1. the Supervisor must communicate clear expectations to workers and effectively manage the team to ensure a positive safety culture; and

6.3.4.2. they should encourage near-miss reporting and investigate any unsafe acts or observations to prevent more serious incidents.

6.3.5. **control of works**

6.3.5.1. the Supervisor must ensure that all necessary controls are in place to manage risks; and

6.3.5.2. they are accountable for the overall scope of work while monitoring their execution to ensure compliance with safety standards.

6.3.6. **emergency preparedness**

6.3.6.1. the Supervisor must establish and validate procedures for emergencies, including incident reporting and response plans are in place; and

6.3.6.2. they must ensure that all workers are trained in emergency procedures and that necessary equipment is available and functional.

7. Driving and Vehicle Safety

Suppliers, supplier's personnel, and contractors shall comply with the following requirements:

7.1. **vehicle specifications**

7.1.1. all vehicles purchased, hired or leased must be in line with local policies and legislative requirements, and be assessed as fit for their intended purpose;

7.1.2. all 2-wheelers usage shall be prohibited;

7.1.3. all vehicles must be fitted with appropriate safety features, ex. minimum double airbags, anti-lock braking systems (ABS), and have manufacturer's three (3) point seatbelts and safety restraint systems installed and functional for all seats/occupants;

7.1.4. the number of passengers must not exceed the manufacturer's specifications for the vehicle, no carrying of excess passengers or transporting people in the back of pickup trucks, transporting unauthorised passengers is prohibited;

7.1.5. loads must be secure and must not exceed the manufacturer's specification and legal limits for the vehicle. Passengers and loads shall never be transported in the same compartments;

7.1.6. all vehicles used for transporting tools and equipment must be fitted with a solid protection barrier for the driver;

7.1.7. all vehicles must be fitted with hands-free car kits and ensure the prohibition of the use of handheld mobile phones or any other devices while operating the vehicle;

7.1.8. all vehicles must be equipped with a speed and location tracking system (telematics) where the system has to be approved and authorised by national regulators and authorities (e.g. NTRA). The supplier shall ensure that the vehicles' telematics includes the following driver behaviour features: monitoring of (Speed, seatbelt, fatigue, night travelling, and harsh braking/acceleration);

7.1.9. all mass transportation vehicles must be equipped with a Visual Tracking System "approved by national regulator authorities" that records and live-streams videos from inside and outside the vehicle as long as it's operated or has passengers inside during Vodafone work-related activities, where and when applicable, legitimate and agreed to do so; and

7.1.10. towing only by vehicles that are fit for purpose and suitable for the size of trailer or equipment being towed, with all trailers, towed equipment and mechanisms for securing towed equipment meeting applicable Laws and industry standards.

7.2. **vehicle shall be replaced after seven (7) years as of the date of manufacturing or reaching four hundred and fifty thousand (450,000) Km (whichever occurs earlier). The following instructions should be followed:**

7.2.1. the manufacturing year is calculated from the start of the model year release or the first official vehicle license registration (whichever occurs earlier);

7.2.2. when any existing vehicle reaches either 5 years or 300,000 Km, the suppliers shall submit a full, detailed and itemised report to the Vodafone SHW team for review and approval. The report should confirm that the vehicle is in safe condition. This report should be written by a competent person, and in one of the manufacturer's approved maintenance centres; and

7.2.3. all new injected vehicles shall be reviewed against the requirements and confirmed prior to work commencement, and the Suppliers shall plan the upgrade of their existing vehicles' telematics to ensure completion of the upgrade and share bi-weekly progress.

7.3. the Supplier is fully responsible for the vehicle from safety and safe operation points of view through regular maintenance & checks;

7.4. **vehicles' tyres** shall be checked and monitored to ensure it is fit for the propose, not to have any lump, bulge or tear caused by separation or partial failure of the structure, and to be replaced when defected/or every 50,000 Km of use (whichever occurs earlier) unless stated by manufacturer Contractor/supplier shall keep records for all tyres check and change;

7.5. **vehicle maintenance shall be done based on the following requirements:**

7.5.1. vehicle's regular maintenance for the engine that includes only (oil change & oil filter) can be done at any approved centre for oil change. Contractor/Supplier shall monitor the efficiency of the vehicles;

7.5.2. any other vehicle's maintenance (including and not limited to any part replacement) must be done by the approved maintenance centres or workshop authorised by the vehicle's manufacturer and shall only use genuine parts in accordance with the vehicle manufacturer's maintenance and specifications;

7.5.3. contractor/Supplier must perform a full diagnosis check report that covers all the vehicle's condition from the approved maintenance centres or workshop authorised by the vehicle's manufacturer every 40,000 Km or 6 months (whichever is soonest). The Check report must be done to cover all the vehicle's checklists and maintenance; and

7.5.4. all Records of maintenance and car check reports should be retained and monitored, and be available for Vodafone reviews.

7.6. **drivers:**

7.6.1. must be appropriately assessed, licensed, trained, and medically fit to operate the vehicle within their defined driver classification and have access to health surveillance and ongoing monitoring to ensure they are fit to drive; and authorised to drive their company's vehicle;

7.6.2. have at least 3 years relevant driving experience starting from the license issuance date, and between 23 & 65 years old;

7.6.3. obliged to abide by absolute rules, ensure all passengers fasten their seatbelts, including their own, and follow proper safe road behaviours at all times;

7.6.4. shall expect the Unexpected (e.g. reduce speed when driving through any areas impacted by road works unless a specific speed is stated by the official authority);

7.6.5. must not carry any unauthorised passengers in or on the vehicle, and ensure that the vehicle is only used for its intended purpose;

7.6.6. shall report to the Supplier any health/medical issues/incidents which could affect their own safety performance; and

7.6.7. ensure that only essential phone calls are allowed through the vehicle kit when driving, and they must limit the frequency and duration of such calls, or park safely to take the call.

7.7. **vehicle passengers are responsible for their own safety. Their behaviours shall support the safe operation of the vehicle by doing the following:**

7.7.1. report immediately any driving violation;

7.7.2. no smoking inside company vehicles; and

7.7.3. always fasten their seat belts while inside the vehicles

7.8. incident reporting & notification: Suppliers shall report all incidents, severe weather conditions, and any arising route related issues to the contact person in Vodafone as soon as possible, and to send official notification within 24hrs in case of incident and to include as a minimum "location, injured persons & type of injury, short description of the incident & immediate actions, Vehicle & driver details, photos";

7.9. supplier shall have a programme for **medical examination** where any personnel driving company vehicles for business-related issues, covering:

7.9.1. **pre-employment written and signed commitment** that the driver doesn't suffer from chronic disease "such as but not limited to epilepsy" that could affect the ability to operate the vehicles safely (e.g. losing consciousness or fainting, etc.);

7.9.2. **pre-employment and annual medical checks through approved labs (Annexe SHW22-1) that include, as a minimum:**

7.9.2.1. diabetes test to avoid Coma;

7.9.2.2. balance test to avoid sudden dizziness;

7.9.2.3. full drug test that includes qualitative and quantitative (Cannabinoids, Benzodiazepines, Barbiturates, Amphetamine, Tramadol, Opiates, Vodo, Strox, Flaka, Lyrica, Actig, Adderall, Alpra, Zolam, Amital, Avinza);

7.9.2.4. back bone survey to check for disk rupture;

7.9.2.5. ophthalmic (vision & colour blindness) test;

7.9.2.6. blood pressure examination; and

7.9.2.7. depakin test (Valproic acid level).

7.9.3. **random drug test:** annual random drug test examinations to all personnel driving company vehicles, covering the whole workforce through approved labs (Annexe SHW22-1). Random drug test targeted percentage not less than 120%;

7.9.4. **remedial Drug test:** for drivers and assignees who had accidents through approved labs (Annexe SHW22-1); and

7.9.5. drivers who **are not medically fit** to drive shall **not be accepted** to operate vehicles until they are fit to do so and upon passing a medical assessment **by a qualified doctor**;

7.10. training: defensive driving training is mandatory for all drivers before driving any vehicle. The following types of training should be offered:

7.10.1. **basic** training for any personnel driving the company's vehicles;
7.10.2. **remedial training** for drivers and assignees who had accidents, and
7.10.3. **periodic refresher** update of basic training is typically provided every two (2) years**.**

7.11. **journey Management & Trip planning:** Risks of the road journey shall be assessed, and controls shall be in place. Journey management plans should identify the risk of driver fatigue considering distance, total working hours, total driving hours, single and multiple journeys, rest periods, time, road type, driving in the dark and must consider return journeys, highlighting that the work schedules, geographical areas of responsibility, health surveillance needs and duration of time on the road are reviewed regularly, considering some main controls to mitigate/reduce the risk such as:

7.11.1. drivers shall work for a maximum of six (6) consecutive days and have a minimum of one (1) full day off on a weekly basis, considering the following examples:
7.11.1.1. working at morning example (6AM-6PM): In cases such as the last shift ends on Thursday 6 PM, then Friday shall be a full day off, and returning to work could be either on the next Saturday morning shift or Saturday night shift, highlighting that working on the Friday in such case will be considered a breach;
7.11.1.2. working at night example (6PM-6AM): In cases such as the last shift ends on Friday 6 AM, then he shall take Saturday as a full day off, and returning to work could be either on the following Sunday morning shift or Sunday night shift, highlighting that working on this Saturday in such case will be considered a breach; and
7.11.1.3. in Ramadan Month and such occasions: Drivers' working time shall be a consecutive time either in the morning or at night, and to be reduced in relevant to Ramadan fasting time, highlighting the other journey management aspects shall be considered.
7.11.2. drivers shall take a fifteen (15) minute rest after every two (2) hours of continuous driving;
7.11.3. drivers' total maximum working time per working day shall be maximum of ten (10) hours within the twelve (12) hours shift period, which includes trip from home to work, any other work, rest time, waiting and driving time;
7.11.4. drivers shall have a minimum of eight (8) hours uninterrupted off-duty rest between shifts;
7.11.5. drivers shall take additional rest when experiencing tiredness or fatigue while driving;
7.11.6. in case of the trip requiring staying for a day or more, then the line managers/supplier shall be responsible for ensuring that the appropriate accommodation and welfare facilities are provided, so that the driver can have his/her rest; and
7.11.7. night travelling (From sunset to sunrise) between governorates shall not be undertaken and to be avoided with alternative safe scheduling.

7.12. **adverse weather conditions:** during bad weather conditions that might include (heavy fog, heavy rains, sandy storms or any condition that could affect the vehicle stability or road visibility), Supplier shall assess all driving activities to take the proper safe decision whether to stop driving till being able to drive safely or to take appropriate precautions from Safety and health prospective while driving;

7.13. **supplier shall dedicate a responsible person for the Implementation of a strict programme to monitor driver behaviour, implementation of a strict programme to monitor and manage the performance of work-related driving and driver behaviour to reduce serious injuries and fatalities through the promotion of safer driving behaviours using in-vehicle hardware solutions (telematics), or app based solutions (unless such monitoring is prohibited by Applicable Laws. Any such implementation shall:**

7.13.1. be used to improve employee engagement on safe driving behaviours through self-awareness and coaching to help influence perceptions & behaviours and provide performance data and insights to primarily help identify trends, patterns and key focus areas, to enable initiatives to achieve safer driving performance;
7.13.2. include the following functionality or features:

7.13.2.1. identify drivers such as using a tag or sign in process where vehicle is a shared or pool vehicle;
7.13.2.2. road-specific speed sensitivity or posted speed limit monitoring;
7.13.2.3. provide timely notifications;
7.13.2.4. provide road speed and driver over-speed detection; and
7.13.2.5. harsh detection event such as monitoring harsh braking and accelerating.

7.13.3. drivers' commitment to speed limits, night driving, and not to drive at speeds that are dangerous for the road conditions, through a GPS tracking system / Telematics;

7.13.4. seatbelts must be worn by all occupants at all times when a vehicle is in motion & this could be through sensors, cameras, mystery shoppers, or other means agreed with the Vodafone Egypt SHW team;

7.13.5. drivers must not carry any unauthorised passengers in or on the vehicle; and

7.13.6. drivers must not be under the influence of alcohol or drugs, or any other substance or medication that could impair their ability to drive, and the no-smoking rule is applied while the vehicle is in motion.

7.14. supplier shall ensure that a safety & quality evaluation is conducted for all drivers, focusing on compliance with driving-related absolute rules;

7.15. supplier shall ensure that a safety & quality evaluation is conducted for all drivers, focusing on compliance with driving-related absolute rules;

7.16. courier suppliers must adhere to all the requirements mentioned in section (7);

7.17. **supplier shall ensure that all his drivers sign a commitment statement, "driving related absolute rules", including:**

7.17.1. fasten seatbelts (All car passengers);
7.17.2. never driving under the influence of substances, drugs or alcohol;
7.17.3. never use a handheld phone whilst driving and only make calls by pulling over or using hands-free devices, when it is safe to do so;
7.17.4. report any accident/injury;
7.17.5. no smoking allowed inside the vehicles;
7.17.6. vehicle daily check-up; and
7.17.7. conduct all preventive maintenance on schedules.

7.18. **the commitment statement shall include the list of disciplinary actions for any breaches:**

Disciplinary Actions		
Breach Type	**First time**	**Second time (Within 6 months of the warning letter)**
Driving without wearing a seat belt	Warning letter	Termination
Exceeding speed limits	Warning letter	Termination
Using a handheld phone while driving	Warning letter	Termination
Driving under the influence of drugs or alcohol	Termination	
High-speed leading to an accident, causing a loss	Termination	

7.19. all records shall be kept and maintained up-to-date for each person/vehicle including but not limited to (pre-employment / regular and random medical examination, defensive driving training, appropriate licenses, accident history, violation history, maintenance/repairing log, insurance records, Vehicle daily check-up, Absolute Rules - driving related - commitment statement - driver's safety performance evaluation record and emergency equipment tools).

8. Working at Heights

Suppliers, supplier's personnel, and contractors shall comply with the following requirements for working at heights as defined as any activity where a person could fall to a lower level, including but not limited to:

- accessing rooftops;
- climbing structures;
- using ladders to access areas or work above ground or floor level;
- using a mobile elevating work platform (MEWP);
- using suspended access equipment;
- using scaffolds;
- work requiring rope access; and
- accessing underground areas.

8.1. supplier shall assess, manage, and, where possible, eliminate the risks associated with work at height by designing out the need for such activities (excluding portable ladders, which are covered separately);

8.2. it sets minimum standards for the competence and fitness of all persons who carry out work at height on Vodafone-related work, and only those persons who have been authorised to be on site and trained (training to be refreshed no later than every two years) in working at height are engaged in that activity;

8.3. those engaged in working at height activities remain attached to the structure at all times with an appropriate fall protection system;

8.4. supplier shall ensure that all sites are designed and constructed with suitable fall prevention measures (e.g. towers are fitted with a Vodafone-approved fall arrest system, guard rails, restraint points): ladder cages are not considered an appropriate fall prevention method and must not be installed on vertical ladders;

8.5. suspend work at height authorisation for any person whose medical conditions present obvious risks to their safety while at work;

8.6. have a programme for medical examination where any personnel engaged in activity where there is a potential to fall from 1.8m or more, covering:

8.6.1. pre-employment written and signed commitment that the working at height rigger doesn't suffer from any chronic disease, "such as but not limited to epilepsy" that could affect the ability to perform the job safely (e.g. losing consciousness or fainting …etc.);

8.6.2. pre-employment and annual medical checks through approved labs (Annex SHW22-1) that include, as a minimum:

8.6.2.1. back bone survey for disk ruptures;

8.6.2.2. diabetes test, Heart disease/chest pain;

8.6.2.3. giddiness/difficulty with balance;

8.6.2.4. high blood pressure;

8.6.2.5. fear of heights/vertigo;

8.6.2.6. ophthalmic (vision & colour blindness) test;

8.6.2.7. full drug test that includes qualitative and quantitative (Cannabinoids, Benzodiazepines, Barbiturates, Amphetamine, Tramadol, Opiates, Vodo, Strox, Flaka, Lyrica, Actig, Adderall, Alpra, Zolam, Amital, Avinza); and

8.6.2.8. depakin test (valproic acid level).

8.6.3. random drug test: annual random drug test examinations to all working at heights personnel through approved labs (Annexe SHW22-1). Random drug test targeted percentage not less than 120%.

8.7. training: Prior to any engagement of personnel in activities where there is a potential to fall from 1.8m or higher, he/she must attend and pass appropriate training at Vodafone Egypt-approved training providers;

8.7.1. **basic** training for all engaged personnel;

8.7.2. **periodic** refresher update of basic training is typically provided every two (2) years; and

8.7.3. **annual** Internal training and awareness program provided by the safety manager.

8.8. no one is permitted to work on fragile roofs (e.g. corrugated sheets, roof with skylights/ weak points);

8.9. no one is permitted to work within two (2) meters of an unprotected roof edge without the use of suitable body harnesses attached to a fall protection device (e.g. anchor point, wire or rail fall arrest system);

8.10. make sure that all working at heights is performed under supervision from a site engineer or team leader, or SHW officer, with fall arrest equipment and a rescue plan & rescuer must be in place;

8.11. any work involving the use of tools and equipment needing to be undertaken within two (2) meters of an unprotected roof edge shall be preceded by the declaration and marking of a safer working area and an evacuated drop zone below the work area;

8.12. consideration is taken to make sure that the system used for handling loads whilst climbing is given prior to the activity. These systems may include carrying light loads in a backpack, manhandling by use of ropes or winches and the use of hoists or cranes;

8.13. all personnel will ensure that all equipment used is suitable and adequate for the purpose intended, and has been properly inspected, tested and examined;

8.14. weather conditions: Structures shall not be climbed if the following conditions are present: (Wind storms, Heavy rain, High or gusting winds, Poor visibility);

8.15. wind speed shall be considered not to exceed 10m/sec when measured at the specific working at height location, and the limit of wind speed shall be reduced by 30% to (maximum 7m/sec) whenever the speed measurement is done through other means such as weather forecast;

8.16. if any of these conditions in Clause 8.14 are detected and considered detrimental to continue working, personnel working at height shall immediately stop all activities;

8.17. those engaged in working at height activities remain attached to the structure at all times;

8.18. provisions are made to protect the public from falling objects and restrict unauthorised access; limit the likelihood of tools or equipment falling to a lower level by tethering and barrier off the area into which tools or equipment may fall if dropped;

8.19. establish arrangements for the issue, use and storage of PPE and access equipment;

8.20. PPE used for working at height is appropriate for fall arrest and must, without exception, be a full-body harness;

8.21. procedures are in place for emergencies occurring at height, e.g. tower rescues, incident reporting procedures;

8.22. all equipment used for access, including ladders, steps, mobile elevated work platforms (MEWPs) and scaffolding, is 8appropriate and inspected prior to use and is only used by appropriately trained people;

8.23. all WAH activities must have a minimum of two riggers per activity, both trained on rescue techniques, with a rescue kit available on site;

8.24. **scaffolding:** Suppliers, supplier's personnel, and contractors shall comply with the following requirements:

8.24.1. scaffolding (mobile and fixed) to be structurally sound, erected & used; alternation and dismantling in accordance with safe work practices and by suitably qualified persons. Installations should be certified and inspected prior to use and/or every 7 days by a qualified person. In case of an accidental event and /or adverse weather conditions, re-inspection is required;

8.24.2. the erecting and dismantling of scaffolding must only be done by trained and competent scaffolders;

8.24.3. all competent scaffolders shall have in their possession a valid training certificate for the erecting and dismantling of scaffolding;
8.24.4. all users of scaffolding shall be trained and hold a valid certificate for working at height;
8.24.5. there shall be a safe access to the scaffold "As a minimum this should be a tied ladder with 3 rungs projecting above the step off at the platform level to provide a handhold i.e.: the equivalent of at least 1m", and a safe system for lifting any materials up to the working height; and
8.24.6. ensure that there are no gaps in guard rails and toe boards forming edge protection through which anyone could fall or an object be dropped onto people below. Scaffolding shall be suitably anchored, secured to adjacent structures, and shall be inspected pre-use by the user and weekly by a competent inspector.

9. Portable Ladders

Suppliers, supplier's personnel, and contractors shall comply with the following requirements:

9.1. the supplier shall ensure that the portable ladder used is suitable for the task & only used for temporary work at height, with the following specifications:

9.1.1. fit for purpose: only non-conductive ladders with the appropriate insulation rating are used, wooden ladders should be avoided;
9.1.2. ladders are inspected before use; confirming good condition (firm & clean treads), right position (fully opened, locked into place & will not move at the bottom);
9.1.3. secured (fastened or anchored at all times and/or being held by another person);
9.1.4. standing on (firm, clear, dry, horizontal & not slippery) surface, long enough not to make the user have to stand on the top 3 rungs;
9.1.5. worker shall only carry light materials and tools (up to 10kg), always maintain 3-point contact on the ladder, do not overreach or lean sideways, ensure having a safe handhold on the steps, and avoid side-on working;
9.1.6. the stepladder shall be used only when the working time doesn't exceed 15 to 30 minutes;
9.1.7. where poles or structures are accessed using ladders, the supplier shall ensure that a safety harness must be worn and secured to the pole or structure once the working position is reached; and
9.1.8. ladders must be safely transported and stored.

10. Electrical work

Suppliers, supplier's personnel, and contractors shall comply with the following requirements:

10.1. supplier shall have and maintain a risk management process and safe systems of work for electrical tasks;

10.2. no live electrical work that has the potential to cause injury is permitted. The only exception to this is work with ELV systems, where switching the equipment off is not practical or would cause significant disruption. Where ELV work is deemed necessary, the following precautions must be adhered to:

10.2.1. any person working on live must be competent, authorised and appropriately trained;
10.2.2. a permit to work must be in place (Including Date, time, location, description & details of procedures, safe work practices, max. exposure time, PPEs and approvals);
10.2.3. 1000v Insulated tools that conform to EN 60900 must be used;
10.2.4. as a minimum, class 00 for ELV and class 0 for LV gloves that conform to IEC 60903 must be worn;
10.2.5. an arc flash face shield that conforms to EN166 and EN170 must be worn;
10.2.6. all jewellery, watches, necklaces, rings, etc., are to be removed before working; and
10.2.7. low flammability clothes to be worn (e.g. non-synthetic).

10.3. all personnel working on electrical equipment shall be proven competent, trained and authorised;

10.4. where live work is deemed necessary on voltage systems exceeds ELV, approval from Vodafone Egypt SHW team & task owner Senior Manager is required before commencing the work, considering that all ELV live work precautions must be adhered to, in addition to, di-electrical shoes that conform EN 50321 must be worn or Switchgear insulating matting that conform BS EN6111 and against electric shock up to 1000 Working Volt to be used;

10.5. prior to working on or near live parts to which personnel may be exposed, it must be de-energised using approved lockout / tagout procedures and proved dead. Approach boundaries must be considered. Stored energy must be safely released;

10.6. before circuits or equipment is re-energised, even temporarily, the competent person must conduct tests and visual inspections as necessary to verify that circuits and equipment can be safely energised;

10.7. all electrical work on medium voltage and above MUST be controlled using a step-by-step photographic sign-off for each life-critical stage of the process;

10.8. electrical equipment in wet and/or highly conductive metal areas is low voltage, shielded or protected by a circuit breaker;

10.9. the location of and access to electrical installations must be controlled to prevent unauthorised access;

10.10. all ladders used near exposed energised sources must have non-conductive side rails and must be clean (free of oil, grease or contamination that would cause it to be conductive). Ropes and hand lines used near exposed energised parts must be nonconductive;

10.11. all cables should be routed in such a way that they cannot be mechanically damaged, i.e. pinched, crushed, cut or worn. They must be routed in such a way as to allow safe access. Splicing is prohibited;

10.12. temporary electrical power and lighting installations 600 volts or less, including flexible cords, cables, extension cords and distribution panels, may only be used during and for renovation, maintenance, repair, or testing. for decorative lighting of special events and similar, for a period not to exceed 30 days;

10.13. RCD protection must be provided on all temporary-wiring circuits, including extension cords, used on construction sites. RCD must also be used when extension cords and/or equipment are used in wet, damp or conductive locations or in construction sites;

10.14. all portable appliances must undergo periodic inspection and testing and be visually inspected;

10.15. electrical equipment not in use, with a potential to cause electrical injury, is isolated from all sources of power and locked off using a formal lockout/tagout system;

10.16. flexible cords and cables must be UL-listed or equivalent, suitable for the location and intended use, not to be used as a substitute for fixed wiring, and must be protected from accidental damage;

10.17. all employees working on electrical equipment or parts must have adequate PPE for electrical works;

10.18. when work is to be performed near overhead lines, the lines must be de-energised and grounded whenever possible. If it is not possible to de-energise and ground overhead lines, then other protective measures must be taken to prevent direct or indirect contact before the work is started;

10.19. excavation works use drawings, cable detection tools, and safe digging practices to minimise the risk from underground electrical services; and

10.20. all electrical installations and equipment must be designed, installed and maintained in line with statutory requirements, manufacturers' recommendations and industry best practice. As a minimum, installations must have:

10.20.1. a documented routine visual check every 12 months; and
10.20.2. a thorough inspection and test every 5 years.

11. Radio Frequency (RF) Safety

Suppliers, supplier's personnel, and contractors shall comply with the following requirements:

11.1. supplier shall fully implement the following provisions, together with any relevant Vodafone local market policy or standard;

11.2. supplier shall have and maintain documented procedures for site selection, design, installation, commissioning, operation, maintenance and decommissioning phases. These procedures should be in accordance with local (national) regulations as well as recognised industry standards;

11.3. supplier documented procedures shall cover the following controls:

11.3.1. design specifications and systems of work being in operation to manage the risks in accordance with local legal and recognised industry standards requirements for the general public and workers; and

11.3.2. an Electromagnetic Fields(EMF) risk assessment /design constraints, which should be reviewed in the event of a material change to the Radio Base Station.

11.4. supplier shall ensure:

11.4.1. work is carried out by trained, competent and qualified persons, with training of staff to include an understanding of potential health risks, and risk controls (e.g. isolation/power down procedures, use of monitoring devices), and dealing with potential over-exposures;

11.4.2. that anyone who has an implanted or body-worn electronic medical device undergoes a special risk assessment before being permitted to enter into controlled areas where the RF field level is potentially higher than ICNIRP Guidelines;

11.4.3. in the event of any purported interference events (e.g. products located in or on hospital premises where life-critical electronic medical devices operate), Supplier shall ensure that necessary procedures are in place to allow shutdown and/or power limitation of Radio Base Stations and shall comply with relevant national guidelines and notify Vodafone of any such instances;

11.4.4. all relevant Supplier personnel take adequate measures to work safely in the presence of RF Fields, including utilisation of standard safe work procedures, and compliance with supervision, instruction & training;

11.4.5. there is clear signage and demarcation considering any Vodafone personnel, general public and Supplier personnel and effective access controls for access to restricted areas;

11.4.6. no overexposure for any work on or near antennas and implement specific safe working procedures addressing potential health risks and having risk controls, and obtaining any necessary approvals needed;

11.4.7. site shut down or power down, or other appropriate procedures shall be implemented to control work within relevant exclusion zones; site landlords shall be provided sufficient information to ensure that they can fulfil their obligations to preserve the safety of third parties;

11.4.8. appropriate guidance shall be available to the general public and workers in accordance with national regulatory or internationally recognised guidelines;

11.4.9. design specifications and systems of work are in operation to manage the risks in accordance with local legal requirements and other relevant standards, for any Vodafone personnel, the general public and Supplier personnel; and

11.4.10. maintenance of appropriate records to demonstrate compliance with the above and clear accountability for data.

11.5. supplier shall ensure that there is a method of auditing and verifying that the required approvals, processes and documentation, set out in this Supplier Policy, are up to date and that Radio Base Stations and Terminal Equipment are compliant with this Supplier Policy with the following elements:

11.5.1. a system to report and investigate any suspected non-compliance incidents (e.g. alleged over-exposure to RF); consider the health of any individual(s) concerned; and ensure safety management systems are working;

11.5.2. compliance with RF exposure limits and risk management is incorporated for all equipment provided; and

11.5.3. records are kept, subject to any applicable data protection legislation, of: (i) Vodafone or Supplier personnel who are potentially exposed to RF field levels above ICNIRP Guidelines (e.g. anyone who maintain antennas); and (ii) any complaints to Supplier from individuals alleging they have suffered personal health effects caused by Radio Base Stations or Terminal Equipment.

11.6. in case Supplier personnel may be exposed to Radio Frequency (RF) fields where RF is present at levels that may exceed national guidance, then there is signage that shall be posted at their boundaries, considering any Vodafone personnel, general public and Supplier personnel;

11.7. all personnel who need to work in close proximity to (RF) radiators shall use an RF monitor at all times;

11.8. before working on antennas, first ensure their deactivation by requesting that the operator(s) disable the appropriate transmitters (site shut down);

11.9. if deactivation of required antenna(s) cannot be guaranteed, then:

11.9.1. do not stop in front of antennas, and

11.9.2. maintain a minimum of 2 meters clearance in front of the antennas (Egyptian Protocol limit).

11.10. use approved personal RF monitors while working near antennas;

11.11. if work is required on transmitting antennas, to avoid unnecessary exposure, the technician should place themselves in a way that compliance with international (ICNIRP) reference levels is achieved;

11.12. electromagnetic field personal monitor: Not mandatory but recommended as an additional safety measure. The personal monitors are set to measure the RF exposure levels and give sound alarms whenever measured field values are higher than ICNIRP occupational exposure limits; and

11.13. record Keeping, Records of those staff who are potentially exposed above the international (ICNIRP) Public exposure guidelines should be kept. Typical individuals who may fall into this category may be antenna riggers, radio installers or maintenance engineers.

12. Product / Equipment Safety

Suppliers, supplier's personnel, and contractors shall comply with the following requirements:

12.1. ensure potential SHW risks associated with terminals, plant, equipment and substances used or procured on behalf of Vodafone are assessed;

12.2. only purchase products sourced from those manufacturers/ suppliers of goods or services that demonstrate robust quality assurance processes and ensure the delivery/maintenance of safe products;

12.3. only purchase, make and release products that comply with safe standards of design using an established process for certifying compliance with relevant safety requirements;

12.4. have and maintain controls for the safe use, handling, transportation, maintenance and storage of products;

12.5. ensure all plant and equipment is suitable for its intended use, maintained in line with manufacturer recommendations, inspected/examined before use and only used by those trained, competent and qualified to operate it;

12.6. have incident investigation methods that are documented and include processes to deal with product defects or failures;

12.7. provide any necessary safety procedures;

12.8. ensure that product safety requirements are documented and include procedures for product;

12.9. document and retain all documentation pertaining to product safety (such records must be provided to Vodafone on request and retained for as long as is necessary);

12.10. have a process as appropriate for the design, production, verification and approval of user documentation to ensure that all necessary Safety and Health information, marks and warnings are current and included;

12.11. ensure that the correct product marks/certifications are obtained and displayed relevant to the application in which the product is destined. Such marks/certifications must be displayed as required on the product, packaging and any associated documentation. Where product certifications/declarations are the responsibility of other parties (e.g. manufacturers/ suppliers of goods or services), such certifications/declarations shall be obtained by the Supplier and form part of the development records;

12.12. monitor product performance in terms of product safety-related failures or reported incidents until the phase out of the product;

12.13. take action to investigate, report, correct, and prevent in the event of a product-related safety incident occurring;

12.14. notify Vodafone in the event of a serious risk requiring a product recall or withdrawal from the field;

12.15. have a process for product safety-related investigations, advisory notices and recall;

12.16. suitable information and instructions relating to the installation, use, maintenance, storage and disposal of products are obtained and communicated to end users; and

12.17. provide communication of all necessary instructions to the end user for safe and correct operation and maintenance in compliance with Applicable Laws and regulations. Such areas shall include (but not be limited to):

12.17.1. aviation or aircraft environment;
12.17.2. flammable liquids or substances;
12.17.3. operating with any medical conditions (e.g. implanted medical devices); and
12.17.4. electro-explosive devices.

13. Ground / Civil Works

Suppliers, supplier's personnel, and contractors shall comply with the following requirements:

13.1. when conducting ground / civil works it has a mechanism for identifying any buried services, detection equipment such as (GPR-Ground Penetrating Radars) shall be used;

13.2. it assesses ground conditions prior to conducting any excavations, and takes steps to prevent incidents, e.g. collapse, flooding, contamination;

13.3. it places barriers and warning signs around open excavation to warn and protect those in the vicinity of the risk;

13.4. appropriate measures are in place to safely control traffic;

13.5. have mechanisms in place to ensure compliance with the following requirements for tower erection activities:

13.5.1. site Engineers /Team Leaders must be clear on their roles and responsibilities and make all needed efforts to make sure that the installation process is up to the manufacturer's standards;
13.5.2. any SHW issue which needs the activity to be suspended should be reported to the Vodafone SHW team. The site activity is to be resumed only after having the Vodafone SHW team's permission after they review all corrective actions;
13.5.3. project/operation managers and Supervisors have a responsibility to ensure that the technical guidelines are understood and properly executed. A mechanism should be in place to check and accept the main installation milestones, and not to rely on final stage acceptance;

13.5.4. following each segment, and before starting any other segment assembling, the site supervisor must get the approval from higher level competent person confirming that the segment has been erected in accordance with the manufacturer's manual This means that the first approval shall be done by onsite competent engineer and the second approval shall be obtained from higher level competent person at technical office (e.g. Project/Operation/Construction Manager). The supplier shall not start the following stage not load anything on the structure unless final approval has been obtained; and

13.5.5. all tower erection activities must not start unless authorised by on-site safety and health personnel and under their direct supervision.

13.6. have mechanisms in place to ensure compliance with the following requirements for **Hot Work** activities:

13.6.1. hot work should be avoided and not be performed unless deemed necessary. Hot Work should only be undertaken if alternatives have been discounted, i.e. mechanical fixing, sawing, adhesives, etc., and shall not proceed unless the following requirements are met:

13.6.1.1. a site and task-specific risk assessment has been conducted;

13.6.1.2. potential fuel sources, flammable and combustible materials have been identified, removed or isolated;

13.6.1.3. stored energy from associated process systems has been discharged;

13.6.1.4. permit-to-Work is issued by an Authorised Person responsible for carrying out the risk assessment of the job, and responsible for specifying the necessary control measures and precautions, e.g. isolations, site preparations, emergency procedures which shall be acknowledged by all personnel involved including the hot work (competent person), fully understand the contents, limitations and scope of the Permit and its full implications, and sign the Permit-to-Work for acceptance of the permit to confirm understanding of the requirements and the obligation to carry out the instructions correctly prior to commencement of work; and

13.6.1.5. if the Hot Work involves or produces substances hazardous to health, then the work must include any additional control measures as necessary to Control Health hazards;

13.6.2. hot work is to be undertaken only by competent and trained personnel. Operators should be suitably trained in the process, familiar with the equipment to be used and instructed where special precautions need to be taken;

13.6.3. only proper and safe welding equipment should be selected for and used in the welding operations, maintained and serviced in accordance with the manufacturer's instructions, and it must be pre-use inspected by a competent person, attended at all times while alight or in operating mode, and extinguished immediately after use;

13.6.4. the welding equipment should be regularly inspected, maintained and tested by competent personnel, and any damaged equipment should be clearly labelled as such and taken out of service immediately until repair can be undertaken. The inspection and maintenance records of the welding equipment should be kept properly;

13.6.5. a trained person (Fire watcher), not directly involved with the work, must provide a continuous fire watch during and for at least one hour after completion of the hot work to ensure that the working area and all adjacent areas are free of smouldering materials or flames. Fire watch periods should be extended where determined necessary by a suitable and sufficient fire risk assessment, fire extinguishers of the appropriate type to be made available and readily accessible;

13.6.6. appropriate personal protective equipment and clothing shall be properly provided, inspected and used in accordance with the risk assessment and relevant standards;

13.6.7. all Flammable substances, liquids, and compressed gases within a minimum radius of 10m around the area of hot work must be removed; this area must be swept clean of combustibles, drips and waste;

13.6.8. all combustible material shall be removed; other combustible materials that cannot be removed shall be covered or screened with overlapping sheets of flame retardant/non-combustible material/thoroughly drenched with water, or covered with damp sand, whichever is suitable;

13.6.9. where work is above floor level, non-combustible curtains or sheets are suspended beneath the work to collect sparks. All holes and other openings through which sparks may fall should be closed where practicable or covered with sheets of non-combustible materials;

13.6.10. proper ventilation to be ensured to avoid the accumulation of fumes, for welding operations in the open area, effective measures to prevent hot slag or sparks from being carried away by wind shall be implemented; and

13.6.11. hot work shall be prohibited at any material/system contaminated with or containing combustible /flammable residue or pressurised, and avoided in rainy day/wetted areas, and limiting/restrictive spaces.

14. Lifting operations

Suppliers, supplier's personnel, and contractors shall comply with the following requirements:

14.1. all lifting activities must be performed through a predesigned lifting plan and undertaken using suitable equipment and a competent person. For high-risk lifts suitable engineering certification is required to be obtained;

14.2. a pre-lift test must be done after all the procedures are in place, and the lifting operation assessment must consider Load weight, centre of gravity, balance, stability, SWL for lifting equipment/accessories and task details;

14.3. all heavy equipment operators must be licensed with equivalent operating licenses and should undertake the proper daily inspection checklists;

14.4. the operator is always to be present at the normal crane control station when the basket is occupied;

14.5. hoists, Cranes and Derricks shall have a valid inspection certificate/load test from an accredited third party and working within equipment specifications and in accordance with EN Standards, e.g. load charts, validation for twelve (12) months for lifting equipment/six (6) months for lifting people;

14.6. all Lifting accessories shall pass visual inspection, free from defects/cuts, used properly within SWL/F.S/WLL in accordance with EN Standards (e.g. Slings, pulleys, hooks, carabiners);

14.7. drop zones must be clearly defined and established. This can be done in various ways, like setting up barricades, using danger tape, fencing off the appropriate areas or using a point man to patrol the area;

14.8. all persons on site must be:

14.8.1. aware of and inducted regarding the risk assessment, before the lift commences;
14.8.2. suitably trained;
14.8.3. authorised to be on site and have necessary approvals; and
14.8.4. medically fit to conduct the task.

14.9. supplier shall ensure that during any lifting operation, steps must be taken to:

14.9.1. prevent tools, equipment or loads from falling to a lower level;
14.9.2. prevent unauthorised access to the drop zone;
14.9.3. ensure haulers are out of the drop zone;
14.9.4. visible and/or audible communication between the persons in the basket and the crane driver shall be available at all times during the lifting operation;
14.9.5. have the required working load limit for the task defined;
14.9.6. have a recorded 6-monthly inspection by a competent person; and
14.9.7. have a before-use or pre-use inspection.

14.10. no lifting shall be done during any wet weather conditions such as rain and/or lightning, and wind speed shall be considered to not exceed 10m/sec when measured at the specific lifting location, and the limit of wind speed shall be reduced by 30% to (maximum 7m/sec) whenever the speed measurement is done through other means such as weather forecast. The site supervisor shall ultimately take responsibility, and lifts can be done if the risk assessment allows the rigging team to continue with the lift;

14.11. no lifting shall be done during night, unless adequate lighting is available on site, such as head lamps or spot lights, and additional hazards have been mitigated in the risk assessment (Provide at least 70% of daylight intensity and prior approval from the VF business owner and the SHW team);

14.12. ensure that the ground (soil) can sustain loads imposed by the crane and allow it to operate within the levels/parameters specified by the crane manufacturer. Side loads shall be avoided;

14.13. working near overhead electrical power line measures shall be considered, such as ensuring that none of the crane, load line or load can become conductive, and that the operation is not within the prohibited zone;

14.14. danger to and from underground services (gas, electricity, water) shall be taken into consideration to ensure that the crane foundation is clear of such services or that they are adequately protected;

14.15. each winch, with its accessories (including derrick, gooseneck, eye-plate, eyebolt, or other attachments), should be tested with a proof load that should exceed the safe working load;

14.16. where counterweights are used, the design of the suspended working platform should ensure that the balancing moments cannot be adversely affected by the easy removal of any counterweight;

14.17. all counterweights should be securely attached at the inner end of the outriggers to prevent tampering by any person, and the materials used must not be removed or discharged accidentally. Water or other liquids, earth, clay, sand, chipping, or aggregates cannot be used as counterweights; and

14.18. **specific requirements for manual lifting**

14.18.1. the maximum manual lifting load by rope rigging techniques must not exceed 100 kgs; thereafter, a professional rigger must be appointed to continue with the required mechanical lift (by means of cranes, lifting machines, etc.);

14.18.2. a non return/brake device must be used in manual lifting operations using ropes and pulleys irrespective of the weight of the load;

14.18.3. sharp edge protection/lifting blocks must be used to prevent slings from being pinched and damaged;

14.18.4. wind loading, and the additional forces it adds to the system and structure, must be considered;

14.18.5. the correct knots should be used when lifting (e.g. Figure of eight on a bight, Double figure eight loop, Figure of nine on a bight, Klem heist knot);

14.18.6. for lifting and lowering between 1-40 kilograms, a pulley 1:1 system must be used; a 1:3 system must be used from 40 kilograms up to 100 kilograms;

14.18.7. no vehicles must be used for lifting. (This includes vehicle-mounted winches.), Furthermore, manual lifting and lowering of any human load without approved mechanical aids/MEWP is not allowed;

14.18.8. anchor “attachment” points: fixed object of suitable strength to which ropes or equipment is attached for the purpose of manual lifting in order to support a load. Planned anchor points should at least comply with EN795; otherwise, Self-identified & Deviation anchor points can be used, but must have a minimum break strength of 30 KN. This must be determined by a competent person, considering that either way, both of placement and testing of anchor points must be performed by a competent person;

14.18.9. a Rigging Supervisor, A hauler/rigger must be:

14.18.9.1. appointed in writing by the supplier as a Rigging Supervisor, and must be medically fit, hold a valid certificate for Fall Arrest, Fall Arrest Rescue, and Rope Rigging;

14.18.9.2. complete a daily pre-task risk assessment, lifting plan, work permit and perform a toolbox talk with the relevant rigging team, and ensure that all persons involved in the lifting process have been made aware of their roles and responsibilities, ensure the correct slinging and rope rigging methods are used and confirm that the pre-lift was done correctly according to the lifting plan; and

14.18.9.3. ensure the correct implementation of the chosen lifting plan and also ensure that all rope rigging equipment and procedures are safe for use and fit for purpose on-site.

14.18.10. a hauler/rigger must be medically fit, hold valid certificates for Fall Arrest, Fall Arrest Rescue, Rope Rigging, adhere to the risk assessment and lifting plan set out by the Rigging Supervisor, ensure that the correct rope rigging principles are adhered to, and immediately notify the Rigging Supervisor of any dangerous occurrence or dangerous action.

15. Confined Spaces

Suppliers, supplier's personnel, and contractors shall comply with the following requirements:

15.1. no work shall be commenced in confined spaces including any chamber, tank, vat, silo, pit, trench, pipe, sewer, flue, well or other similar space in which, by virtue of its enclosed nature, there arises a reasonably foreseeable specified risks unless permitted;

15.2. has and maintains a mechanism for identifying confined spaces, assessing and managing the associated risks;

15.3. only those persons who have received appropriate training work in confined spaces;

15.4. where necessary, there is the capability and process for testing and monitoring of air quality; and

15.5. emergency equipment and procedures, at least including (rescue harness; lifting tripod or other suitable means to retrieve persons from confined space; emergency breathing apparatus; suitable first aid kit; an observer adjacent to the manhole at all times, low voltage light and means of communication).

16. Warehouse Safety

Suppliers, supplier's personnel, and contractors shall comply with Vodafone SHW S11 Warehouse Safety Policy requirements, which will be communicated to relevant suppliers in addition to the following requirements:

16.1. all who work in or visit the warehouse must have suitable information and instruction on how to remain safe in the environment; this will include details on emergency procedures, common risks, hazard spotting, hazard rectification processes, risk assessment and other key safety requirements, they should be equipped with the appropriate PPE as identified by the warehouse risk assessment. (This PPE may include, but not be limited to, safety boots/shoes, Hi-Viz jacket/vest, hardhat and protective glasses);

16.2. all must be fitted with fire detection systems (including beam detection), audible fire alarm systems, suitable fire-fighting/suppression systems, emergency lighting and have appropriate processes in place to control the levels of combustible and flammable materials;

16.3. all equipment in the warehouse must be fit for purpose, this includes mobile equipment such as fork lift trucks, access equipment such as warehouse steps and ladders, portable equipment such as electrical tools and appliances, and fixed equipment such as racking, appropriate systems should be in place for regular inspection and monitoring of equipment;

16.4. adequate welfare facilities must be provided, including designated clean areas for eating and drinking, access to drinking water, toilets, washing facilities with hot & cold water, lockers, change rooms and rest areas;

16.5. emergency preparedness and evacuation routes include clear and visible (signposted) evacuation routes and clearly identified assembly points, fire exits, appropriate fire extinguishers, electrical panels and access aisles and stairways kept clear of any obstructions;

16.6. emergency evacuation procedures are to be in place and staff trained;

16.7. provision for first aid, including trained first aid training, shall be made at each location. The first aid provisions should be routinely maintained to ensure they remain fit for purpose;

16.8. for Lithium-ion (Li-ion) batteries:

16.8.1. routine inspection, use, maintenance, handling, storage (including segregation), disposal and emergency response arrangements are in place and be subject to a separate risk assessment for each instance and area of use;

16.8.2. charging areas include segregated areas (from heat sources and combustible materials), restricted access, segregated zones, temperature, suitable ventilation and venting (off gas and pressure venting). Regular (automated infrared or hot spot) thermal testing equipment should be available and used as necessary;

16.8.3. storage at ground level in segregated, bulk blocks or on racks when covered by fire suppression systems;

16.8.4. any charging uses the manufacturer's specification and not be left on charge when the warehouse is unoccupied;

16.8.5. inspection arrangements, including on delivery, storage, handling (including use) and disposal, identifying any signs of impact, crushing, indentation and penetration;

16.8.6. a returns management process in place which includes inspection, safe storage, monitoring and safe disposal. This should include external safe storage (away from heat, ignition sources and combustible material) wherever possible;

16.8.7. Battery Energy Supply Systems (BESS) are located outside and away from the main storage building areas and should include at least 3 metres of space between the sides of the BESS unit and any nearby structure or object and at least 1.5 metres of space between the sides of the BESS unit and any near structure or object, off gas detection and shut off controls, off gas vents to release the build-up of flammable gases and pressure vents to relieve explosive events. Suppression systems should not allow total flooding due to the battery release of oxygen and the subsequent creation of pressure;

16.8.8. uninterrupted Power Supply (UPS), where used, has an aspirating fire detection system, off-gas detection and water mist or sprinkler protection system implemented;

16.8.9. for charging material handling equipment such as forklifts or power assisted pallet trucks that use Li-ion batteries, adequate fire alarm and sprinkler protection is in place and, avoiding the use of extension leads; and

16.8.10. employees are trained in the risks of Li-ion batteries and have safe systems to manage risk.

16.9. racking and storage installations are fixed to a physical structure (wall, floor), have recorded weekly visual check of condition, have load limits clearly defined and displayed, be designed for the purpose, be installed and maintained in line with manufacturers requirements, are subjected to regular, formal, planned and recorded inspections by a competent person and have adequate barrier protection to prevent strikes by vehicles or equipment; and

16.10. fixed electrical installations within the warehouse undergo a routine inspection as required by regulations or at least annually, whichever occurs sooner and include visual inspection, Residual Current Device testing, and other necessary checks. A comprehensive inspection and testing of the entire system shall be carried out as required by regulations or at a minimum interval of every five years, whichever occurs sooner.

17. Fibre Related Activities

Suppliers, supplier's personnel, and contractors shall comply with Vodafone Global SHW S06 Safety and Health – FTTX installation and maintenance Policy requirements, which will be communicated to relevant suppliers in addition to the following requirements:

17.1. planning – all cable laying activities must be planned and supported by a SHW plan, site-specific risk assessments and method statements;

17.2. buried services – appropriate controls must be in place to detect or minimise the risk of contact with buried services, detection equipment such as (GPR- Ground Penetrating Radars) shall be used along with testing pits based on the survey conducted;

17.3. when digging near buried services, the following must be taken into consideration:

- 17.3.1. use insulated hand tools in preference to machines; and
- 17.3.2. where depth of service can be determined, mechanical digging can be used to remove the top surface. Consider using alternative methods, being mindful of the associated risks:
  - 17.3.2.1. vacuum;
  - 17.3.2.2. water jets;
  - 17.3.2.3. compressed air; and
  - 17.3.2.4. horizontal manual digging.

17.4. trenching – appropriately engineered shoring, bracing & barriers must be used when working in excavations to prevent injury caused by trench collapse, items falling into the trench or persons falling into the trench;

17.5. underground chambers – underground chambers (confined space) must only be entered when sufficient training and control measures are in place;

17.6. ensure that correct separation distances from live cables are maintained;

17.7. proximity detectors are used by all personnel working near power sources;

17.8. appropriate insulated tools are used;

17.9. no throwing of fibre in the vicinity of overhead power lines;

17.10. traffic control – appropriate measures must be in place to safely control traffic;

17.11. training – all operatives must be appropriately trained and competent for the tasks they undertake;

17.12. material handling – appropriate control processes must be in place to control material movement, including safe delivery, Safe storage of materials on site, Safe access to materials, and safe handling;

17.13. personal Protective Equipment (PPE) – all operatives must be provided with the necessary PPE;

17.14. supervision – all high-risk activities associated with cable laying must have the appropriate level of competent supervision on the ground. They must have the authority to stop work, monitor and be held accountable for the delivery;

17.15. where existing fibre installations are to be maintained or repaired the following are to be adhered to:

- 17.15.1. treat any unknown cables as live;
- 17.15.2. ensure correct separation distances are maintained;
- 17.15.3. voltage proximity detectors are to be used; and
- 17.15.4. emergency procedures shall include all potential emergencies, including hitting utility services, gas leaks, and other hazards based on the site-specific scope, nature of the activities, and other environmental factors.

17.16. welfare – Appropriate welfare facilities must be made available to all operatives.

18. Control of Access

Suppliers shall ensure that access to high risk activity work areas are controlled for only authorised persons and in addition:

18.1. ensure that hazards associated with high risk activities have been identified, assessed and controls are in place to eliminate the hazard, and that high risk activities and/or activities taking place in a high risk environment are planned and have been approved by a competent person before the work commences;

18.2. ensure that suppliers have a process in place to demonstrate that high risk activity was completed and verified as planned, including keeping any necessary records of activity; and

18.3. have access and work approval processes for 100% of the high-risk activities and/or activities taking place in a high-risk environment to ensure:

- 18.3.1. activities have been adequately planned;
- 18.3.2. access and work are approved by an authorised person;
- 18.3.3. associated hazards have been identified, assessed, and SHW risks are eliminated/mitigated, and control measures are applied in accordance with the hierarchy of controls; and
- 18.3.4. the effective implementation of SHW requirements and control measures during the activity till the completion shall be supervised onsite by a competent supervisor and monitored by SHW (whether physically onsite by suppliers' personnel or remotely).

Part C – Incident Reporting & Investigation Process

19. Incident Reporting and Investigation

Supplier shall ensure that:

19.1. all necessary systems are in place to report, record and investigate all incidents, including product failures;

19.2. where an incident occurs that has the potential to directly impact Vodafone, this must be reported and classified as per Vodafone definitions in the table (below) and in accordance with the reporting process as set out below;

19.3. it co-operates with and supports Vodafone in the investigation of all incidents; and

19.4. all details related to incidents and investigations are shared with Vodafone.

Classification	Description
Fatality	• Work-related injury or illness that results in a fatality
Major Incident	A work-related incident that results in: • An injury causing incapacity for more than 7 days • Fractures, other than to fingers, thumbs, or toes • Amputation • Dislocation of the shoulder, hip, knee, or spine • Loss of sight (temporary or permanent) • Chemical or hot metal burns to the eye, or penetrating injury to the eye • Any incident resulting in unconsciousness or requiring resuscitation • Significant harm arising from substance inhalation, ingestion or absorption, or exposure to a biological agent • Serious burns requiring professional medical attention • Chronic ill-health • Collapse, overturn or failure of any lifting machinery or accessories • Collapse or partial collapse of any antenna supporting structure • Any unplanned contact with a utility service • Plant or equipment coming into contact with, or creating an arc with overhead power lines • Any electric shock or electrical burn
Minor Incident	A work-related incident resulting in: • No treatment injury • Any treatment of minor scratches, cuts, burns, splinters and so forth, and any follow-up visit for the purpose of observation • Any work-related injury or illness requiring medical care (beyond first aid) • Acute occupational illness, e.g., contact dermatitis.

20. Incident Report

Supplier shall:

20.1. send official notification within 24 hours in case of incident and to include as a minimum “location, injured persons & type of injury, short description of the incident & immediate actions, Vehicle & driver details, photos”;

20.2. ensure that it provides a report to Vodafone with concise, timely information concerning any Incident;

20.3. co-operate and grant Vodafone reasonable access and audit rights to any scene of an Incident, together with other premises, personnel and documents as is necessary to complete a full investigation;

20.4. arrange for any witnesses to the Incident to be identified and to be present to assist in the investigation and completion of an investigation report;

20.5. where reasonable, ensure that the scene of an Incident remains undisturbed except for necessary remediation work. If the scene cannot remain substantially undisturbed, Supplier shall arrange for photographs and measurements, and the necessary drawings and plans, to facilitate the work of the investigation;

20.6. investigate a full investigation into the causes of any Incident and how to avoid reoccurrence, and provide the full report to Vodafone within 10 working days;

20.7. minimum required data for Incident Notification:

20.7.1. nature of incident (Fatality, serious injury & near miss);
20.7.2. country/region, specific location & date/time;
20.7.3. business area;
20.7.4. details of injured person(s);
20.7.5. nature of injury (Contact type, injury type & part of body);
20.7.6. description of incident; and
20.7.7. immediate actions taken.

20.8. minimum required data for Incident Investigation:

20.8.1. immediate causes (Substandard acts/practices);
20.8.2. immediate causes (Substandard conditions);
20.8.3. basic Causes (Personal factors);
20.8.4. basic Causes (Job/system factors);
20.8.5. basic Causes (Supporting documentation);
20.8.6. action plan;
20.8.7. days lost information; and
20.8.8. loss estimation.

21. Near-Miss Incident Reporting

21.1. Vodafone highly values the reporting of near-miss incidents by its Suppliers and their personnel. A near-miss incident is defined as an event that could have resulted in harm or damage but did not, either by chance or through timely intervention. It is crucial to report such incidents as they provide valuable opportunities to improve safety and prevent future harm; and

21.2. **no consequences for near-miss reporting:** Vodafone ensures that the reporting of genuine near-miss incidents will never result in consequence management for the reporter or those involved - it is regarded as a highly positive action, reflecting a proactive approach to maintaining a safe and healthy working environment. Suppliers should ensure those reporting incidents are positively recognised appropriately and are encouraged to foster a culture of openness and continuous improvement by actively promoting the reporting of all near-miss incidents.

22. Final Close Out Reports

22.1. Supplier shall issue a close-out report which contains a summary of the following information:

22.1.1. updated nature of injury and condition/prognosis;
22.1.2. description of incident;
22.1.3. action taken to prevent reoccurrence;
22.1.4. direct feedback to understand the perspective of the persons involved; and
22.1.5. any follow-up actions, support for family members, contractors, counselling of individuals and other reasonable remedial activities.

22.2. supplier shall include the following support documentation and include it with the close-out report:

22.2.1. contracts/works orders;
22.2.2. safety plans/work method statements;
22.2.3. induction and training records; and
22.2.4. site supervisor/inspection/audit records.

23. Final Close Out Meetings

23.1. Supplier shall organise a close-out meeting and ensure that the incident has been appropriately managed, and Supplier has clearly understood the root cause of the incident that occurred and any lessons learned have been communicated; and

23.2. Supplier must address the following key issues:

23.2.1. Welfare of the injured person, or in the case of a fatality, the welfare of the individual's family and co-workers;
23.2.2. How to prevent future incidents;
23.2.3. Root cause of the incident, including human factors; and
23.2.4. Specific lessons learned from all incidents and their communication.

Part D – Consequences of Non-compliance

24. Supplier Obligations

24.1. Supplier shall: (i) comply with this Supplier Policy and the Absolute Rules; (ii) follow an appropriate SHW plan; (iii) have appropriate systems and processes in place to monitor any failures in such compliance; (iv) have an appropriate "consequences" process in place to ensure that Supplier personnel breaching this Policy or Absolute Rules face appropriate disciplinary action, to the extent permitted by Applicable Law and expressly on the basis that Supplier remains responsible for managing its own personnel; and (v) implement this process at the earliest opportunity;

24.2. supplier shall: (i) immediately cease all related work in the event of any fatality; and (ii) only re-commence work upon Vodafone authorising it in writing to do so. In such circumstances, Supplier shall not be entitled to any right to delay performance, increase the price payable or other form of contractual waiver, forbearance or relaxation;

24.3. supplier shall (when requested by Vodafone) exclude any Supplier personnel who repeatedly fail to observe this Supplier Policy or the Absolute Rules from being involved in the ongoing provision of products or services to Vodafone. Supplier shall make such exclusion automatically in the event that such personnel are found with a positive drug test or not wearing appropriate safety harness and fall protection equipment when working at height; and

24.4. suppliers shall compensate any of the human resources, whether it's their own resources or their sub-contractors, that are working for Vodafone Egypt's premises based on the following:

24.4.1. **fatality cases:** The minimum immediate compensation shall be Fifty-Five (55) months from the total pay or minimum amount of One Million Egyptian pounds (1000,000.00 Egyptian Pounds) to be paid, whichever is greater, and shall be paid to the deceased person's family according to relevant Egyptian laws; and

24.4.2. **disability cases:** Based on the same amount mentioned above in in the Fatality cases, compensation shall be a percentage in accordance with partial and permanent disability insurance index mentioned in the Egyptian Social Insurance Law and its valid amendments at the time of incident, and to be paid to the injured person or his official trustee according to relevant Egyptian laws.

25. Vodafone Rights

25.1. Vodafone shall: (i) have absolute discretion on whether to classify an incident as Red Card or Yellow Card; and (ii) notify Supplier of its decisions in this respect;

25.2. Vodafone can conduct audits and ask for compliance evidence at any time and shall be entitled to apply the measures set out in "25.4" (Consequence Table), where there is a failure to comply with the Supplier Policy or the Absolute Rules. Supplier shall assist and provide access to information as is necessary to establish a classification. Incidents shall not be classified as Red Card or Yellow Card if the Supplier can unequivocally demonstrate compliance with this Supplier Policy or the Absolute Rules;

25.3. any classification of individual incidents shall typically have validity of 36 months from the point of notification; however, this validity is at Vodafone's discretion; and

25.4. **Consequence Table:**

Incident Cards	Card Description	Consequence
	Yellow Card	Vodafone will send a warning notification.
	3 x Yellow Cards	3 Yellow Cards are equivalent to a single Red Card.
	Related Yellow Card	Any Yellow Card that has a cause related to a previous Yellow Card will result in the card being equivalent and counted as a Red Card.
	1st Red Card	Vodafone may exclude Supplier from participating in future bids or tender opportunities for a number of events or time period of 12 months.
	2nd Red Card	Vodafone may exclude Supplier from participating in future bids or tender opportunities for a further number of events or time period.
	3rd Red Card	Vodafone may terminate all or part of the agreement or any orders placed with Supplier (on the basis of breach of contract by Supplier).

Annexes

The current Annexes may be modified or updated without modification of the entire policy/document!

Annexe (SHW22-1)

Approved Training Centres:

Training Provider	Trainer	Contacts	Required trainings								
			Risk Assessment	Firefighting	First aid & CPR	Electrical safety	Lifting Operation and Slinging	Working at heights and rescue	PPE & Gear Inspection including manual lifting gears	Scaffolding Erection, Dismantling, and Inspection	Defensive Driving two-year Validity
Partner Success	Mr. Mohamed El-Masry	0122-214-2705 melmasry@partners-success.com	√	√	√	√					
HSSE Solutions	Dr. Yassin Darwish	0100-007-2146 yassin@hsse-ltd.com	√	√	√	√					√
GTSC	Tamer Hossni	0100-004-2708 thosney@gtsc.biz	√	√	√	√	√				√
Safety Point	Mr. Omar Sheta	0100-523-2000 osheta@safety-point.com training@safety-point.com						√	√	√	
Platinum	Mr. Ahmed El-Naggar	010-000-72095 ahmed.elnaggar@platinum-eg.com						√	√	√	
المركز المصري للقيادة الامنة **Egyptian Centre for Safe Driving**	Mr. Khaled Younes	0114-363-4444 reservation@etf-rstc.org.eg									√
Proficiency for safety, health & environmental solutions	Mr. Sary ElFayoumy	0102-324-4262 Info@proshes.com	√	√	√	√	√				√
TUV NORD Egypt	Mr. Amr Tarek	0128-880-0955 atarek@tuv-nord.com					√				

Approved Labs for medical examinations & drug tests:

Provider	Contacts	
The Lab	Ibrahim Abdeen	01004077056
Nile Lab	Besan Elrefai	01026030092

Approved calibration & thorough examination suppliers:

Provider	Contacts		
Petrolift	Usama Saad	Usama@petrolift.com	01223912660
TUV	Amr Tarek	atarek@tuv-nord.com	01288800955

Approved PPE suppliers:

Approved PPE Provider	Supplier contacts		PPE Brand
Safety Point	osheta@safetypoint.com.eg mfathy@safetypoint.com.eg	01005232000 01000266323	Specific **Petzl** Products Specific **Kong** Products
Safe Science	saeed.okiel@gmail.com	01117701220	Specific **Irudek** Products
SKY	mohamed.abdelhamed@sky-grp.com	01066612802	Specific **CAMP** Products
Platinum	ahmed.elnaggar@platinum-eg.com>	01065549199	Specific **Gravity & CAMP** Products
Eye-In Solution	ramy.mohamed1@eyeinsolutions.com	01068992099	Specific **KAYA** Products

Note: Miller and 3M purchased products are valid till the expiry of the product, conditional that it passes the inspection and in accordance with the manufacturer's requirements.

PPE EN Standards

Harness

1. EN 361 EN 358, EN 813 - Full Body Harness shall have a minimum of two EN 361 D-Rings (At the top point of the Harness front and back)

Connectors

1. EN 341 Descender devices for rescue with anti-panic function
2. EN 354 Lanyards
3. EN 355 Energy absorbers
4. EN 358 Belts and lanyards for work positioning or restraint
5. EN 360 Retractable-type fall arresters
6. EN 362 Connectors
7. EN 1496 Rescue lifting devices
8. EN 1891 Low stretch kernmantel ropes - EN 1891 Ropes for "industrial" rope access and climbing
9. EN 12278 Pulleys

Anchors

1. EN 353-1 +A1 Guided type fall arresters including a flexible anchor line
2. EN 353-2 Guided-type fall arresters including a flexible anchor line
3. EN 795 Anchor devices
4. EN 795 Type A Fixed to the structure
5. EN 795 Type B Not fixed to the structure

6. EN 795 Type C Flexible horizontal anchor line
7. EN 795 Type D Rigid horizontal anchor line
8. EN 795 Type E Counterweight anchor
9. EN 566 Rescue Sling

PPE For Electrical Work:

1. EN/IEC 60903 Live working - Gloves of insulating material and Insulated tools
2. EN50321 Footwear for Live working
3. EN61112 Switchgear insulating matting
4. EN IEC 62819 Arc flash face shield

General

1. EN 363 Personal fall protection systems
2. EN 364 General requirements for instructions for use, maintenance, periodic examination, repair, marking and packaging
3. EN 365/ AC:2006 Test methods
4. EN 397 Industrial safety helmets
5. EN 12492 Climbing Mountaineering Helmet
6. EN 20345 S3 Safety Shoes pair
7. EN 388 Mechanical Risk Safety Gloves
8. EN 1868:1997 List of equivalent terms
9. EN 12278 Pulleys
10. EN 1891 Ropes for “industrial” rope access and climbing